

U.S. Virgin Islands DPNR

Major Coastal Zone Management Permit Application— Tier 1

For a Proposed Solar Energy Facility with Battery Storage

Parcel No. 17 Remainder Bovoni Estate Bovoni, St. Thomas, U.S. Virgin Islands

HTA Project No. 23.141001.00

October 2025

Applicant:
STB Solar, LLC
A Vielectron, LLC Company



Table of Contents

- 1. Form L&WD-2 Major Coastal Zone Management Permit Application
- 2. Form L&WD-3 Zoning Requirements
- 3. Form L&WD-4 Major Project Summary Data
- 4. Form L&WD-5 Proof of Legal Interest
- 5. Form L&WD-6 Income Tax Clearance Letter
- 6. Form L&WD-7 Corporations and Associates
- 7. Form L&WD-8 NFIP Flood Zone Designation
- 8. Approved Permit Letter Request for Partial Clearing
- 9. Environmental Assessment Report (EAR) Narrative
- 10. Attachment A Deed / STB Solar, LLC Subsidiary of Vielectron, LLC Documentation
- 11. Attachment B Property Tax Clearance Letter
- 12. Attachment C NOI and Construction SWPPP
- 13. Attachment D Biological Study
- 14. Attachment E Archaeological Study
- 15. Attachment F Driveway Permit Application and Plans
- 16. Attachment G Site and Erosion Control Plans
- 17. Attachment H Required Maps and Plans
 - a. FEMA Firm Map
 - b. NRCS Soil Survey Map
- 18. Attachment I Hydrology Report

L&WD Forms



GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-2 PERMIT APPLICATION

Date	Received:
Date	Declared Complete: Permit No
Appl	ication is hereby made for a Earth Change/Coastal Zone Permit
1.	Name, mailing address and telephone number of applicant. STB SOLAR, LLC PMB 348 00830
2.	Name, title, mailing address and telephone number of owner of property and of developer. Owner Developer ———————————————————————————————————
3.	Location of activity. Plot No
4.	Zoning District
5.	Name, mailing address and telephone number of project designer.
6.	Name, mailing address and telephone number of principal earthwork contractor. Mongoose Solar, LLC 5000 Estate Enighed, PMB 348 St John, VI 00830 (508) 965-8637
7.	Summary of proposed activity. Include all incidental improvements such as utilities, roads, etc. (Use additional sheets if necessary).
7a.	State type of Land Uses as specified in the VI Zoning Law, which are applied for e.g., restaurant, hotel, single dwelling, etc.

FORM L&WD-2/PERMIT APPLICATION CONT'D

8.	Date activity is proposed to sta	rt, be	completed
9.	Classification of minor or major p	permit. Check one:	
	() Minor Permit Application		
	() Major Permit Application		
	State below which criterion appli	es in making above check	
10.	any additional information/data the to show that the proposed project or other environmental protection completed. I also agree to provide protection agencies for the purpose	nat may be necessary to prowill comply with the appli on standards both during le entry to the project site he of making inspections re the information provided h	ties described herein. I agree to provide ovide reasonable assurance or evidence cable territorial water quality standard construction and after the project is for inspectors from the environmental garding this application, and that to the erein, is true, complete and accurate. I proposed activities.
	Signature of Applicant or Agent Signature of Owner (Where App or Agent is not Owner)	licant	Date 10/15/2025
	FOR D	EPARTMENT USE OF	NLY
Date	Inspected:	()Permit Approve	
Inspe	ctor's Remarks:	()Permit Disappr	oved
	Inspector		Date
	Commissioner, Planning & Natur	ral Resources	Date

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-3 ZONING REQUIREMENTS TABLE

The following table shall be completed by the applicant with entries as appropriate for the zoning district in which the activity is taking place. Not all the requirements will necessarily apply to a particular zone. Consult the Zoning Law. For your guidance also consult the zoning Requirement Matrix attached to the application forms, i.e., for a R-2 zone only items 1 through 11 will apply.

STB Solar, LLC

Appli	cants Name:	Signature:	tow'	Date: 10/15/202
Locat	ion of Activity-Plot No	Estate		Island
Zonin	ng District:			
1.	Proposed use (residential etc.)_			
2.	Accessory use if any			
3.	Number of on site parking spaces	s Existing	proposed	
4.	Area of lot, (sq. ft. or acreage)			
5.	Area covered by proposed and exist	ing buildings, (sq. ft.)		
6.	Setback of building from street prop	perty line, (ft.)		
7.	Side yard setback ft)			
8.	Rear yard setback (ft)			
9.	Height of building (ft. or stories d	epending on zone) _		
10.	Proposed:			
11.	Lot width at street line (ft.)			
12.	Area of usable open space (sq. ft	. and (%) of lot		
13.	Persons per acre ratio			
14.	Floor area ratio			
15.	Number of onsite parking and loa			
16.	Building setback (yards 11, W-2	only)		
	FOR DE	PARTMENT USE	ONLY	
Inspe	ctor:	Date:	Permit No.	

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-4 MAJOR PROJECT SUMMARY DATA

Section I. Applicant

1.	Name, address and telephone number of applicant.
S	TB SOLAR, LLC
	348,
2.	Name, address and telephone number of owner of Property and of developer.
Sect	ion II. Summary of Proposed Development
3.	Describe the proposed development
Sect	ion III. Description of Proposed Development
4.	Name of development
5.	Plot No
6.	Zoning District:
7.	PWD Map No.
8.	Proposed use (residential, etc. as listed in Zoning Law):
9.	Accessory use if any

FORM L&WD-4 MAJOR PROJECT SUMMARY DATA Cont'd

	Person	Persons	
Schedule of units:	Efficiencies ———-	x 1.5 Unit — =	
	1 bedroom —	x 2=	
	2 bedroom —	x 3	
	3 bedroom —	x 4	=
	Other —	x	=
	Total Persons —		
Number of on site	parking and loading spaces		
Maximum building	height (stories/ft)		
Adjoining property	land use(s)		
Setback of building	from street property line (f	:)	
Sideyard setback (ft)		
Area of usable ope	n space (sq. ft. % of lot)		

FORM L&WD-4 MAJOR PROJECT SUMMARY DATA Cont'd

Section IV. Comments

26.	Proposed Potable Water Supply (method & quality estimate gal/day)
27.	Proposed Sewage Treatment (method & quality estimate gal/day)
28.	Proposed Solid Waste Disposal (method & quality estimate lbs/day)
29.	Proposed Electrical Supply (method & demand estimate KWH for single & 3 phase)
30.	Air Conditioning (method & demand estimate (KWH)
31.	Other Utilities
32.	Other
Section 33.	Will the development extend onto or adjoin any beach tidelands, submerged lands or public
34. the co	Will the development maintain, enhance or conflict with public access to the shoreline and along
35.	Will the development protect or provide moderate income housing opportunities? Will it displace moderate income housing?
36.	How will the development affect traffic on the coastal access roads?
	Signature of owner or authorized agent Date

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-5 PROOF OF LEGAL INTEREST

AFFIDAVIT				
Ι,	Applicant(s)* (or John Doe of Entity A	A 11 0	being duly sworn dep	oose and say that:
	Applicant(s)* (or John Doe of Entity A	Applicant)		
1	(I or Entity/Applicant)	am/is the (cl	heck one)	
☐ Record t	itle owner (fee simple)	☐ Lessee	☐ Other (specify)	
Of the real prop	perty described as Parcel No((s)		
Estate	Quarter	Is	land	
*Applicant(s) i	is required to provide docu	mentation for le	gal interest stated above (e.g. deed, lease,
	revocable approvals, permiss rty to undertake the work prophereto:			
Signature	Da	te Signa	ture	Date
Print		Print		
The foregoing i	instrument was acknowledge	ed before me this	day of	
20 by	(Name or Name/Title of E	Entity)	at	county
of	<u>.</u>			
Notary Public		My Commi	ission expires	

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

PUBLIC NOTICE (SUPPLEMENT TO FORM L&WD-6)

Pursuant to Act 5270, as approved by the Governor of the Virgin Islands on July 30, 1987, amending Section 910 (a) (2) and 911 (d) (2) of the Coastal Zone Management Act (Title 12, VI Code, Chapter 21), all applicants for Coastal Zone Management permits are required to present "certification from Bureau of Internal Revenue and Department of Finance" indicating "that the applicant has filed and paid all taxes, penalties and interest, and from the Office of the Lieutenant Governor that the applicants has filled its required annual report or has satisfactorily made agreement to pay the taxes or fill the required reports "12 VIC 910 (a) (2) (C), and "(2) A coastal zone permit that includes an occupancy or development lease shall only be granted for a particular parcel of filled land for a lease period of not more than 20 years; provided that nothing in this subsection shall prohibit a lessee or permittee from executing a new lease at the end of the 20 year period. Any lease executed at the end of the lease period shall meet the requirements of this Chapter and shall be approved by the Governor and ratified by the Legislature, or in the event the Legislature is not in session, by the Committee on Planning and Environmental Protection.

For applicants not required by law to submit an annual report or to satisfactorily make an agreement to pay taxes or file the required reports, a letter from the Bureau of Internal Revenue, and/or the Department of Finance, and/or the Lieutenant Governor's office so indicating will be required to continue further processing of the application.

Accordingly, all Coastal Zone Management permit applications (both minor and major), which are not accompanied by the certificates, as required by Act 5290, or written notification from said agencies indicating waiver or exemption of these requirements will not be accepted by the permitting office, It is the responsibility of each applicant to demonstrate compliance with the provisions of this Act.

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES -0-

VIRGIN ISLANDS BUREAU OF INTERNAL REVENUE

(DPNR FORM L&WD-6) APPLICATION FOR TAX FILING AND PAYMENT STATUS REPORT**

Date: 16/15/2025

The applicant identified below hereby requests a letter certifying his or her tax filing and payment status for the purpose of receiving a Coastal Zone Management Permit from the Virgin Islands Department of Planning and Natural Resources pursuant to Act 5270, amending Sections 910 (a)(2) and 911 (d)(2) of the Coastal Zone Management Act (Title 12, Chapter 21, Virgin Islands Code). The applicant authorizes the Bureau of Internal Revenue to disclose any taxpayer information necessary to process this application to the Virgin Islands Department of Planning and Natural Resources, who may make such further disclosures as are necessary to carry out the requirements of the Coastal Zone Management Act, as amended.

Name:	As manager STB SOLAR, LLC		
Business Name:		3	STB SOLAR, LLC
EIN/TIN: 66-1110485			
SSN:			
Please Indicate: *Corporation Partnership Individual Other		Please circle form	ss: Solar Development ss that you use: 1120, 1120s, TI, 722 VI, 720, 720 VI, 720 (list)
Date Business Started:_	10/15/2025		
Person Representing App	olicant: Christian Loranger	Position:	Manager
Signature:			
Mailing Address: 5000	Estate Enighed, PMB 348, St Jo	hn, VI 00830	
Date: 10/15/2025	Telephor	ne Number:	(508) 965-8637

Reply to: #1A Lockharts Garden, St. Thomas VI 00802 or 4008 Estate Diamond, St. Croix VI 00820

^{*} Partnerships and/or Corporations must list partners/ corporate officers, social security numbers and addresses on a seperate sheet and attach it to this application.

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-7 CORPORATION/ASSOCIATION APPLICATION

(To be used when a corporation or association is making a Permit Application in Tier 1)

STB SOLAR, LLC

(Corporation or Association Name)		
By: Monage	Owner / Developer / Operato	
(Signature) President or Vice-President or equivalent	Title/Position (Print)
Christian Loranger Print		
WITNESS:	ATTEST:	
DAVID J. FASS	Secretary (or equivalent)	Signature
	Secretary (or equivalent)	Print
	David J. Fa NOTARY PUE COMMONWEALTH OF MA MY COMMISSION JUNE 18, 20	ASSACHUSETTS EXPIRES
On this 15Th day of October, 2025, before	ore me the undersigned officer, personally appe	ared
CHRISTIAN CORMER who acknowledges him	nself to be the OWNER	
of SOB SOLAR, LLC; that he execut	ted the foregoing instrument in the capacity abo	ove and has the
authority to execute this application on behalf of the compar	ny.	
IN WITNESS WHEREOF, I have hereunto set my ha	nd and official seal the day and year above w	ritten.
	DAVID J. FASS	
Include Supporting Documents:		

- 1. Compliance with Act No. 5270 by providing:
 - (a) Tax clearance letter from the Bureau of Internal Revenue
 - (b) Property tax clearance letter from the Lieutenant Governor's Office.
 - (c) Corporations and Associations: Certificate of Good Standing or equivalent, organizational documents & Amendments (Articles, Bylaws, Operating Agreement, Declarations)
 - (d) Corporate Resolution (or equivalent) authorizing action on behalf of the company.

GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PLANNING AND NATURAL RESOURCES DEVELOPMENT PERMIT APPLICATION

FORM L&WD-5 PROOF OF LEGAL INTEREST

AFFIDAVIT	
I, Christian Loranger of STB SOLAR LLC.	being duly sworn depose and say that:
Applicant(s)* (or John Doe of Entity Applicant)	
1. STB SOLAR, LLC am/is	the (check one)
☐ Record title owner (fee simple) ☐ Les	ssee Other (specify)
Of the real property described as Parcel No(s) 109402	010100
Estate Bovoni Quarter No. 1&2 Frenchman's Ba	Island Saint Thomas
*Applicant(s) is required to provide documentation etc.)	for legal interest stated above (e.g. deed, lease,
2. I have the irrevocable approvals, permission, or power in the property to undertake the work proposed in the (s) attached hereto:	permit application as more fully set forth in the exhibit
Signature Date	Signature Date
Print	Print
The foregoing instrument was acknowledged before m	e this 15TH day of OCTOBER
20 25 by CHRISTIAN LORANGER (Name or Name/Title of Entity)	at PLYMOUTH county
OF MASSACHUSETTS	
	-2032
Notary Public DAVID J. TASS My C	Commission expires

David J. Fass

NOTARY PUBLIC

MY COMMISSION EXPIRES

JUNE 18, 2032

Flood Plain Determination and Permit Application

Tob	se completed by all applicants		
l.	Owner:		
	Mailing Address		
	Home Tel. #:	Business Tel. #:	Cellular #:
2.	Designer:		
			Cellular #:
3.	Plot #:	Estate:	Quarter:
	Flood Zone Designation:		
1.	Type of development: 1 or 2 Family dwelling () 3 Family or more, Apartment Commercial Structure () Addition to Structure ()	Mobile Home () Non-	Non- Residential Structure: () Non-Structural () ent of Existing Structure ()
2.			fL above mean sea level (msl)
3.	Elevation of the First Floor,	Basement or Flood proof leve	el for proposed structure isfl_
4.	Describe the Non-Structural location and development):_	Activity i.e. septic tank, was	te water treatment plants etc. (including the
5.	Attach a certified copy of sit	e plan (8.5" x 11") showing	Base Flood Elevation. See sample attached.
		FOR OFFICE USE ON	TLY
s the	property located in an identifi	ied Flood Hazard Area?	() YES () NO
VFIP :	Zone Designation:	Forward to Flood Plain N	Manager: () YES () NO
Applio	cation: APPROVED()	DENIED () RESUBMIT	r()
lan R	Reviewer Name:		
ignati	ture:		Date:

Se	SCALEI ONE INCH EQUALS SQ.F.; SFEA OF 100-Year, Flood plain BEE BEE BASCH AND WILL BE LEFT UNFINISHED. POF CHINGE BLOCK AND WILL BE LEFT UNFINISHED. FOR STRUCTURES LICKATED ON LOTS AT AND 24. POST STRUCTURES LICKATED ON LOTS AT AND 24. BFE BASE OF 100 Years Flood Elevation (Tied Into Elevation 6.0 NGTD) (Tied Into Elevation 6.0 NGTD) ANSWERT FLOOR INTO A STRUCTURE CONTROLL OF THE STRUCTURE OF THE STRUC	
	Lores Estate Road Estate Road	e participatores, se el presidente el porte de la contrata del contrata de la contrata de la contrata del contrata de la contrata de la contrata de la contrata de la contrata del contrata del contrata del contrata de la contrata del contra

Approved Permit Letter Request for Partial Clearing



Christian Loranger CB Loranger Companies 5000 Estate Enighed, Suite 4a, PMB348 St. John, USVI 00830

Web: www.cbloranger.com

October 10, 2023

via email to jp.oriol@dpnr.vi.gov

The Honorable Jean-Pierre L. Oriol, Commissioner Department of Planning and Natural Resources 4611 Tutu Mall Park Suite 300, Second Floor St. Thomas, VI 00802

RE: Rem. 17 Bovoni Solar Energy Facility Permit Letter Request

Dear Commissioner Oriol:

VIElectron, LLC (VIElectron) has signed a Power Purchase Agreement (PPA) with the Virgin Islands Water and Power Authority (VIWAPA) to construct several Solar Energy Facilities in the U.S. Virgin Islands.

One solar energy facility will be located at the south-eastern end of St. Thomas at Rem. 17 Estate Bovoni. This site is located in the Coastal Zone (Tier I). This system is being designed to generate about 13 MWdc of electrical power and will cover a land area of approximately 30 acres. This facility will be designed to provide power directly to the local grid throughout the day, while also charging an on-site battery energy storage systems (BESS). The battery system will provide power to the grid during nighttime hours or cloudy days with lower solar field output.

For this project, the intention is to work within the existing grades and outside the limits of any flood zones that may exist to minimize the impacts on the existing properties while installing the solar panel modules, and any associated infrastructure.

Over the next couple of months, VIElectron will be preparing and submitting A Major Land CZM Permit Application for the Bovoni Solar Project. In this regard, a CZM Pre-Application Meeting organized by the DPNR CZM Division was held on Thursday, October 5, 2023.

As you know, the Major CZM Application Process can take quite a few months to complete. In the interim, VIElectron would like to proceed with some critical, preliminary work on the Bovoni Site to include installing fencing around the perimeter of the property; conducting a Phase I Archeological Study, as well as Topographic and Boundary Surveys. To this end, VIElectron kindly seeks your approval to allow a partial clearing of the Site using transects as

VIELECTRON Bovoni, St. Thomas Solar Farm Permit Request


per the attached plan shown below. The plan depicts clearing a 15' swath around the perimeter of the projects for fencing and 15' wide transects in an east-west direction through the sites for proper site investigations. 40' of vegetation will be left between the transects.

Thank you for your careful consideration of this request. Your approval and support of this matter will be greatly appreciated and will have a significant impact to the timeline of these projects which are critical to the significant improvement to the power reliability on St. Thomas.

If you have any questions or concerns, please contact me at (508) 985 5637.

Sincerely, VIElectron LLC

Christian B. Loranger Manager





SITE CLEARING PLAN BOVONI 17 REMAINDER ESTATE BOVONI SAINT THOMAS, VI

LOT AREA: 30.50± ACRES

CLEARING AREA: 9.49± ACRES

CLEARING NOTES:

- 1. A REGISTERED LAND SURVEYOR SHALL CLEARLY MARK THE PROPERTY LINES, OUTER LIMITS OF CLEARING AND CENTERLINE OF EACH TRANSECT PRIOR TO THE START OF ANY WORK.
- 2. TRANSECTS MAY BE FIELD ADJUSTED AROUND OBSTACLES SUCH AS LARGE ROCKS.
- 3. ALL CLEARING SHALL BE COMPLETED WITH A LOW GROUND PRESSURE SKID STEER OR TRACK EXCAVATOR WITH A MULCHING ATTACHMENT TO REMOVE AND GRIND THE TREES AND VEGETATION WITHIN 2 INCHES OF THE EXISTING GROUND SURFACE. ALL ROOTS AND STUMPS SHALL REMAIN IN PLACE WITH NO SOIL DISTURBANCES. EXCESS MULCH SHALL BE PLACED IN A BERM AT THE BOTTOM OF THE DOWNHILL SLOPES AS SHOWN FOR EROSION CONTROL.

SCALE: 1" = 250'

SEPTEMBER 20, 2023

PREPARED FOR:

VIelectron, LLC

PREPARED BY:



Environmental Assessment Report (EAR) Narrative SECTION 1.00 – APPLICANT INFORMATION

Applicant

STB Solar, LLC

c/o Christian Loranger

5000 Est Enighed, STE 4A, PMB 146

Saint John, VI 00830

(508) 965-8637

SECTION 2.00 - LOCATION OF PROJECT

The proposed solar energy facility ("the project") is located in Tier I (coastal zone), near the eastern section of United States Virgin Island St. Thomas, near the existing landfill, on a parcel identified as No. 17 Remainder Bovoni (Parcel No. 109402010100). The project is expected to be completed in one phase.

SECTION 3.00 - ABSTRACT

The existing site has been extensively disturbed, previously used for agricultural purposes, and is vacant and primarily consists of overgrown woods, grass and mixed growth vegetation where stormwater flows downhill in the southern direction of the site towards the coast. The 100-year flood zone "VE" is present and runs along the coastline; however, the proposed project is entirely within zone "X" and does not anticipate affecting any flooding on-site due to the hydrological outfall is the ocean. Please refer to the Existing Conditions Plan as part of **Attachment G** and FEMA Firm Map as part of **Attachment H**.

Based on a recently performed Biological Study (included as **Attachment D**), although tree boas were not found on the site, conditions of the site fall well within their habitat preference, and the area is within their distribution range. In particular, care should be taken to protect the endangered species of the tree boas and should be closely watched by equipment operators, surveyors and all workers on-site. DPNR should be notified if one is seen so the species can be removed and relocated accordingly.

Based on a recently performed Archeological Study (included as **Attachment E**), there are no known cultural resources that would be impacted by the proposed project.

Due to the location of the site in relation to nearby airports, a Glint & Glare Study was not required for the site; therefore, the solar system runs along the east-west axis.

SECTION 4.00 – STATEMENT OF OBJECTIVES

The proposed project intends to work within the existing grades and outside the limits of the flood zone to minimize the impacts on the surrounding land while installing the solar panel modules, and any associated infrastructure, to connect to the Water and Power Authority (WAPA).

The system itself is designed to provide power directly to the local grid throughout the day, while also charging one (1) on-site battery energy storage system (BESS).

SECTION 5.00 - DESCRIPTION OF PROJECT

5.01 – Summary of Proposed Activities

The proposed activities for the installation of the project includes; an initial survey and staking the limits of all work, constructing the stabilized construction entrance, installing silt fences and other various perimeter erosion control measures prior to any site clearing and grubbing. On December 1, 2023, a Permit Letter Request was approved allowing for partial clearing of the site for 15' wide perimeter around the project area for fence installation and 15' wide transects in the east-west direction for proper site investigation at 40' intervals between each transect. Currently the site has been cleared according to the approved letter (included as part of this application) and appropriate erosion control measures are already in place.

Once additional permits are obtained, the remaining activities for installation will include; the installation of the security fence, construction of the 20' wide gravel access roads, construction of any stormwater rock berms and other best management practices, installation of the solar racking screws, construction of the solar racking system and installation of the solar panels, then the installation of all conduit runs and electrical equipment. The project area should be seeded in any disturbed areas that appear bare after construction.

5.02 - Purpose of Project

The proposed project intends to generate clean energy for WAPA and ultimately to the residences of the Virgin Islands. The battery system will provide power to the grid during nighttime hours or cloudy days with lower solar field output for a more consistent power supply.

5.03 – Presence and Location of Any Critical Area(s)

The site may contain steep slopes and several drop-offs.

There are no ghuts present on-site.

There are no wetlands present on-site.

5.04 – Proposed Method of Construction

The clearing and grubbing for the site has been, and will continue to be, completed with a low ground pressure skid steer or track excavator with a mulching attachment to remove and grind the trees and vegetation within 2-inches of the existing ground surface to preserve all topsoil and allow existing roots to remain. The majority of the mulch is left in place, while any excess mulch is placed in a perimeter berm along the downhill slopes toward the coast.

The proposed racking system is supported on 2.375-inch diameter ground screws that are installed into the ground setting the lower end of the panels approximately 24-inches above ground. The proposed technology utilizes First Solar Series-6 465W solar panel modules set at either a 10- or 20-

degree tilt, depending on the orientation of existing slopes – the site experiences reverse slopes along the north side of the property. Each panel is placed within a galvanized ground mounted racking system, custom made specifically for the USVI to withstand 180 mph wind speeds, installed in rows running in the east-west direction, where each row is spaced to provide a minimum two (2) feet of clearance between adjacent solar panels; depending on the existing slopes of the site some five (5) and eight (8) foot clearances are necessary especially to the north where the site experiences reverse slopes. At the end of each row, all power lines used to operate the solar panels will be distributed above ground to connect to the equipment pads where the low-voltage wires will run through a Class 2 Circuit (CAV) system and the high-voltage wires will run through conduits on concrete pads.

For installation of the solar panels and associated racking system within the steep slopes of the site, cut ins and steps may need to be constructed for access.

No proposed water, sewer, lighting or stormwater infrastructure (i.e. inlets, manholes, etc.) as part of this project.

5.05 - Provisions to Limit Site Disturbance

The on-going clearing and mulching of the site, cutting all trees and vegetation within 2-inches of the existing ground, allows all roots and stumps to remain in place creating no soil disturbance and preserving all topsoil and maintaining ground stabilization.

No potable water, sewer or stormwater infrastructure (i.e. inlets, manholes, infiltration basins) are proposed therefore no excavation is required.

All electrical runs, both low- and high-voltage, will be distributed above ground on concrete pads eliminating the need for excavation therefore minimizing any earth disturbance.

Cut ins and steps along the steep slopes will be constructed only on an as needed basis to install the solar system to reduce the overall ground disturbance of the site.

5.06 – Erosion and Sedimentation Controls

The project proposes erosion and sedimentation controls to ensure the site's disturbance material is contained on-site that includes, but are not limited to, site fencing, mulch-in-place and perimeter berms, temporary and permanent rock berms, and natural spray tack adhesives for necessary stepping access paths, as needed, for installation requirements on steep slopes.

5.07 – Construction Activities and Erosion Control Implementation Methods

The current construction activities of partially clearing the site have implemented erosion control methods including mulch-in-place, mulch berms, and silt fencing. These methods have proven to be very effective construction means and methods on site and will continue to be used throughout the duration of construction for the project.

Construction and installation of the ground screws and racking system within the steep slopes on-site will have additional erosion control methods implemented where cut ins and steps may be required. Silt fencing and natural spray tack adhesives should be used, as needed, for sections of the cuts and/or steps that appear to fail on-site during construction activities. Temporary rock berms may be

necessary in areas that form stormwater flow paths due to construction activities, especially during heavy rains. Permanent rock berms will be installed within the project area at locations that demonstrate forming flow paths to prevent future stormwater erosion. Please refer to the Hydrology Report as part of **Attachment I**.

5.08 - Maintenance of Erosion and Sediment Control Measures

The contractor will be responsible for implementing all erosion and sediment control devices needed to stabilize the project area during construction with both temporary and permanent measures to prevent excess runoff, due to construction, to the on-site ghuts and/or off-site to the coast. All temporary stabilization measures will be removed after the site has been stabilized and/or construction is complete. Erosion control measures are to be inspected weekly and after every heavy rainfalls within 24 hours.

5.09 - Method of Sewage Disposal

The proposed project does not include any residential or office spaces producing sewage waste and therefore methods of disposal is not applicable.



Attachment A – Lease Agreement / STB Solar, LLC – Subsidiary of VIelectron, LLC Documentation



Attachment B – Property Tax Clearance Letter



GOVERNMENT OF THE U.S. VIRGIN ISLANDS BUREAU OF INTERNAL REVENUE

6115 EST. SMITH BAY-

11/22/2022

4008 ESTATE DIAMOND - PLOT 7-B

ST. THOMAS, VI 00802

CHRISTIANSTED, VI 00820

Tel: (340) 714-9320 Fax: (340) 714-9341 Tel: (340) 773-1040 Fax: (340) 773-1006

GENTLE WINDS CONDOMINIUM ASSOCIATION

9003 GENTLE WINDS

FREDERIKSTED, VI 00841-0000

Business EIN: 660637966

RE:

Please Submit This Letter To Your CZM Authority

Dear Taxpayer:

This is in response to your application of 11/22/2022 in which you requested a letter of clearance for a Costal Zone Management Permit pursuant to Title 12, V. I. Code, Section 910 (a) (c).

Based on the information in our files, we find that you are current in the filing and payment of your tax obligation. This Certification is for Costal Zone Permit purposes only and does not absolve you of any subsequent revelation of tax obligation past or future.

Sincerely,

Delinquent Accounts & Returns

Attachment C – NOI and Construction SWPPP



Stormwater Pollution Prevention Plan (SWPPP)

For Construction Activities At:

Proposed Solar Energy Facility with Battery Storage Parcel No. Bovoni 17 Remainder of Estate Bovoni, Western Por. No. 1&2 Frenchman's Bay Quarter, St. Thomas, VI 00802

SWPPP Prepared For:

Quantum Solar, LLC
Subsidiary of VIELECTRON, LLC
c/o Christian Loranger
5000 Est. Enighed, Ste 4a PMB 146, St. John, U.S.V.I. 00830
Phone: 508-965-8637
nbdsolar@gmail.com

SWPPP Prepared By:

Hoyle, Tanner & Associates, Inc. 95 E. Mitchell Hammock Road, Suite 200 Oviedo, FL 32765 603-431-2520

SWPPP Preparation Date:

10/14/2025

Estimated Project Dates: 11/01/2025 – 07/01/2026

Contents

SECTION	N 1: CONTACT INFORMATION/RESPONSIBLE PARTIES	1
1.1	Operator(s) / Subcontractor(s)	1
1.2	Stormwater Team	2
SECTION	N 2: SITE EVALUATION, ASSESSMENT, AND PLANNING	4
2.1	Project/Site Information	4
2.2	Discharge Information	4
2.3	Nature of the Construction Activities	5
2.4	Sequence and Estimated Dates of Construction Activities	6
2.5	Authorized Non-Stormwater Discharges	
2.6	Site Maps	7
SECTION	N 3: DOCUMENTATION OF COMPLIANCE WITH OTHER FEDERAL REQUIREMENTS	7
3.1	Endangered Species Protection	7
3.2	Historic Property Screening Process	
3.3	Safe Drinking Water Act Underground Injection Control Requirements	.11
SECTION	N 4: EROSION AND SEDIMENT CONTROLS	
4.1	Natural Buffers or Equivalent Sediment Controls	.12
4.2	Perimeter Controls	
4.3	Sediment Track-Out	.12
4.4	Stockpiled Sediment or Soil	.12
4.5	Minimize Dust	
4.6	Minimize Steep Slope Disturbances	
4.7	Topsoil	
4.8	Soil Compaction	
4.9	Storm Drain Inlets	
4.10	Constructed Site Drainage Feature	
4.11	Sediment Basins	
4.12	Chemical Treatment	
4.13	Dewatering Practices	
4.14	Other Stormwater Controls	
4.15	Site Stabilization	
	N 5: POLLUTION PREVENTION STANDARDS	
5.1	Potential Sources of Pollution	
5.2	Spill Prevention and Response	
5.3	Fueling and Maintenance of Equipment or Vehicles	
5.4	Washing of Equipment and Vehicles	.17
5.5	Storage, Handling, and Disposal of Building Products, Materials, and Wastes	.17
5.6	Washing of Applicators and Containers used for Paint, Concrete or Other	
Materia		
5.7	Fertilizers	
5.8	Other Pollution Prevention Practices	
	N 6: INSPECTION, MAINTENANCE, AND CORRECTIVE ACTION	
6.1	Inspection Personnel and Procedures	
6.2	Corrective Action	
6.3	Delegation of Authority	
SECTION	N 7: TURBIDITY BENCHMARK MONITORING FROM DEWATERING DISCHARGES	22

Stormwater Pollution Prevention Plan (SWPPP) Proposed Solar Energy Facility with Battery Storage – Bovoni

SECTION 8: CERTIFICATION AND NOTIFICATION	22
SWPPP APPENDICES	23

SECTION 1: CONTACT INFORMATION/RESPONSIBLE PARTIES

1.1 Operator(s) / Subcontractor(s)

Operator(s):

Quantum Solar, LLC Subsidiary of VIELECTRON, LLC Christian Loranger 5000 Est. Enighed, Ste 4a PMB 146 St. John, U.S.V.I 00830 Phone 508-965-8637 nbdsolar@gmail.com Area of Control: Entire Site

Emergency 24-Hour Contact:

VIELECTRON Christian Loranger Phone 508-965-8637

1.2 Stormwater Team

Stormwater Team

Name and/or Position, and Contact	Responsibilities	I Have Completed Training Required by VI CGP Part 6	I Have Read the CGP and Understand the Applicable Requirements	
Christian Loranger QUANTUM SOLAR, LLC Owner 508-965-8637 nbdsolar@gmail.com	Developer	□ Yes □ No	☐ Yes Date:	
Christian Loranger VIELECTRON, LLC Operator 508-965-8637 nbdsolar@gmail.com	Operator; Inspections of stormwater controls	□ Yes □ No	☐ Yes Date:	
Hoyle Tanner & Associates Engineer 603-431-2520	SWPPP Development	□ Yes □ No	□ Yes Date:	

Stormwater Team Members Who Conduct Inspections Pursuant to CGP Part 4

Name and/or Position and Contact	Training(s) Received	Date Training(s) Completed	If Training is a Non-EPA Training, confirm that it Satisfies the Minimum Elements of VI CGP Part 6
Christian Loranger Quantum Solar, LLC Subsidiary of VIELECTRON Operator 508-965-8637 nbdsolar@gmail.com	Insert Title of Training Received	Date: Click here to enter a date.	 Principles and practices of erosion and sediment control and pollution prevention practices at construction sites Proper installation and maintenance of erosion and sediment controls and pollution prevention practices used at construction sites Performance of inspections, including the proper completion of required reports and documentation, consistent with the requirements of Part 4

See Appendix I for required Training Documentation.

SECTION 2: SITE EVALUATION, ASSESSMENT, AND PLANNING

2.1 Project/Site Information Project Name and Address Proposed Solar Energy Facility with Battery Storage - Bovoni Parcel No. Bovoni 17 Remainder of Estate Bovoni, Western Por. No. 1&2 Frenchman's Bay Quarter, St. Thomas, VI 00802 Project Latitude/Longitude Longitude: - 64.8828 ° W Latitude: 18.3089° N (decimal degrees) (decimal degrees) Latitude/longitude data source: Map GPS Other (please specify): Google Earth Horizontal Reference Datum: NAD 27 NAD 83 **X** WGS 84 Additional Site Information Is your site located on Indian country lands, or on a property of religious or cultural significance to an Indian Tribe? ☐ Yes X No 2.2 Discharge Information ☐ Yes X No Does your project/site discharge stormwater into a Municipal Separate Storm Sewer System (MS4)? X No ☐ Yes Are there any waters of the U.S. within 50 feet of your project's earth disturbances?

Stormwater Pollution Prevention Plan (SWPPP) Proposed Solar Energy Facility with Battery Storage – Bovoni

For each point of discharge, provide a point of discharge ID (a unique 3-digit ID, e.g., 001, 002), the name of the first receiving water that receives stormwater directly from the point of discharge and/or from the MS4 that the point of discharge discharges to, and the following

receiving water information, if applicable:	receiving water	information,	if applicable:
---	-----------------	--------------	----------------

Point of Discharge ID	Name of receiving water that receives stormwater discharge:	Is the receiving water impaired (on the CWA 303(d) list)?	If yes, list the pollutants that are causing the impairment:	Has a TMDL been completed for this receiving waterbody?	If yes, list TMDL Name and ID:	Pollutant(s) for which there is a TMDL:	Is this receiving water designated as a Tier 2, Tier 2.5, or Tier 3 water?	If yes, specify which Tier (2, 2.5, or 3)?
001	Unidentified Water – 800042165	☐ Yes ☒ No		☐ Yes ☒ No			☐ Yes ☒ No	
002	Unidentified Water – 800042287	☐ Yes ☒ No		☐ Yes ☒ No			☐ Yes ☒ No	

2.3 Nature of the Construction Activities

General Description of Project

Installation of a solar farm at Bovoni 17 Remainder, Western Por. No. 1&2 Frenchman's Bay Quarter, St. Thomas, U.S. Virgin Islands. The parcel is roughly 30.9 acres and undeveloped. Approximately 27.9 acres will be used for the installation of a solar farm designed to generate about 10 MW of power. The site is currently being cleared where mulched vegetation is being mulched-in-place. The project consists of the installation of ground screws for the solar racking units where panels will be held. Installation of electrical equipment and conduits will be installed in concrete pads above ground, and access to the site will be through a gravel access drive. No grading is proposed on-site.

Business days and hours for the project: 6am-7pm Daily

Size of Construction Site

Size of Property	30.93 +/- Acres
Total Area Expected to be Disturbed by Construction Activities	27.94 +/- Acres
Maximum Area Expected to be Disturbed at Any One Time, Including On-site and Off-site Construction Support Areas	27.94 +/- Acres

Type of Construction Site (c	check all that apply):
------------------------------	------------------------

☐ Single-Family Residential	\square Multi-Family Residential \square	☐ Commercial	☐ Industrial
☐ Institutional ☐ Highway	or Road \square Utility \boxtimes Othe	er <u>Solar Energy I</u>	Facility
Will you be discharging dewate	· ·	☐ Yes	3
If yes, will you be discharging dewatering water from a current or former Federal or State remediation site? $\hfill\Box$			⊠ No

Pollutant-Generating Activities

List and describe all pollutant-generating activities and indicate for each activity the associated pollutants or pollutant constituents that could be discharged in stormwater from your construction site. Take into account where potential spills and leaks could occur that contribute pollutants to stormwater discharges, and any known hazardous or toxic substances, such as PCBs and asbestos, that will be disturbed during construction.

Pollutant-Generating Activity	Pollutants or Pollutant Constituents
(e.g., paving operations; concrete, paint, and stucco washout and waste disposal; solid waste storage and disposal; and dewatering operations)	(e.g., sediment, fertilizers, pesticides, paints, caulks, sealants, fluorescent light ballasts, contaminated substrates, solvents, fuels)
Demolition/Clearing	Sediment, debris

Pollutant-Generating Activity	Pollutants or Pollutant Constituents
(e.g., paving operations; concrete, paint, and stucco washout and waste disposal; solid waste storage and disposal; and dewatering operations)	(e.g., sediment, fertilizers, pesticides, paints, caulks, sealants, fluorescent light ballasts, contaminated substrates, solvents, fuels)
Use of heavy equipment	Oil and grease
Landscaping activities	Fertilizers, Nutrients
Natural spray tack adhesive (Erosion Control)	Sealants, Solvents

2.4 Sequence and Estimated Dates of Construction Activities

Phase I

Phase 1	
Estimated Start Date of Construction Activities for this	11/1/2025
Phase	
Estimated End Date of Construction Activities for this	7/1/2026
Phase	
Estimated Date(s) of Application of Stabilization	12/1/2025
Measures for Areas of the Site Required to be	
Stabilized	
Estimated Date(s) when Stormwater Controls will be	7/1/2026
Removed	

2.5 Authorized Non-Stormwater Discharges

List of Authorized Non-Stormwater Discharges Present at the Site

Authorized Non-Stormwater Discharge	Will or May Occur at Your Site?
Discharges from emergency fire-fighting activities	☐ Yes ☒ No
Fire hydrant flushings	☐ Yes ☒ No
Landscape irrigation	☐ Yes ☒ No
Water used to wash vehicles and equipment	☐ Yes ☒ No
Water used to control dust	
Potable water including uncontaminated water line flushings	☐ Yes ☒ No
External building washdown (soaps/solvents are not used and external surfaces do not contain hazardous substances)	☐ Yes ☒ No
Pavement wash waters	☐ Yes ☒ No
Uncontaminated air conditioning or compressor condensate	☐ Yes ☒ No
Uncontaminated, non-turbid discharges of ground water or spring water	☐ Yes ☒ No
Foundation or footing drains	☐ Yes ☒ No
Uncontaminated construction dewatering water	☐ Yes ☒ No

2.6 Site Maps

See Appendix A of this SWPPP for Site Map

SECTION 3: DOCUMENTATION OF COMPLIANCE WITH OTHER FEDERAL REQUIREMENTS

3.

1 Endangered Species Protection
Eligibility Criterion Following the process outlined in Appendix C of the VI CGP, under which criterion are you eligible for coverage under this permit?
Criterion A: No ESA-listed species and/or designated critical habitat present in action area. Using the process outlined in Appendix C of the VI CGP, you certify that ESA-listed species and designated critical habitat(s) under the jurisdiction of the USFWS or NMFS are not likely to occur in your site's "action area" as defined in Appendix A of the VI CGP. Please Note: NMFS' jurisdiction includes ESA-listed marine and estuarine species that spawn in inland rivers.
☐ Check to confirm you have provided documentation in your SWPPP as required by VI CGP Appendix C (Note: reliance on State resources is not acceptable; see VI CGP Appendix C).
Documentation: Insert Text Here
Criterion B: Eligibility requirements met by another operator under the 2012 VI CGP. The construction site's discharges and discharge-related activities were already addressed in another operator's valid certification of eligibility for your "action area" under eligibility Criterion A, C, D, E, or F of the 2012 VI CGP and you have confirmed that no additional ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS not considered in the that certification may be present or located in the "action area." To certify your eligibility under this criterion, there must be no lapse of TPDES permit coverage in the other VI CGP operator's certification. By certifying eligibility under this criterion, you agree to comply with any conditions upon which the other VI CGP operator's certification was based. You must include in your NOI the TPDES ID from the other 2012 VI CGP operator's notification of authorization under this permit and list any measures that you must comply with. If your certification is based on another 2012 VI CGP operator's certification under criterion C, you must provide EPA with the relevant supporting information required of existing dischargers in Criterion C.
☐ Check to confirm you have provided documentation in your SWPPP as required by VICGP Appendix C.

Documentation: Insert Text Here

Elig	ibilit	y Cri	terion

Following the process outlined in Appendix C of the VI CGP, under which criterion are you eligible for coverage under this permit?

Criterion C: Discharges not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat. ESA-listed species and/or designated critical habitat(s) under the jurisdiction of the USFWS and/or NMFS are likely to occur in or near your site's "action area," and you certify to EPA that your site's discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed threatened or endangered species and/or designated critical habitat. This certification may include consideration of any stormwater controls and/or management practices you will adopt to ensure that your discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat. To certify your eligibility under this criterion, indicate 1) the ESA-listed species and/or designated habitat located in your "action area" using the process outlined in Appendix C of this permit; 2) the distance between the site and the listed species and/or designated critical habitat in the action area (in miles); and 3) a rationale describing specifically how short- or long-term
adverse effects to ESA-listed species will be avoided from the discharges and discharge-related activities. (Note: You must include a copy of your site map from your SWPPP showing the upland and in-water extent of your "action area" with your NOI.)
☐ Check to confirm you have provided documentation in your SWPPP as required by VI CGP Appendix C.
Documentation: The Biological Study prepared by Kadison Islands Consulting, LLC concluded that no threatened or endangered species were observed within the development area; however, the site conditions found it falls well within the habitat preference of the federally protected tree boas, but none were observed on-site during the study investigations. Tree boas are largely nocturnal, therefore there is a reasonable chance that hey inhabit the property and particular care should be taken to protect the endangered species including the tree boa if present. A copy of the study is included in this Coastal Zone Management Permit Application.
Criterion D: Coordination with USFWS and/or NMFS has successfully concluded. Coordination between you and the USFWS and/or NMFS has concluded. The coordination must have addressed the effects of your site's discharges and discharge-related activities on ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS, and resulted in a written confirmation from USFWS and/or NMFS that the effects of your site's discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects. By certifying eligibility under this criterion, you agree to comply with any conditions you must meet for your site's discharges and discharge-related activities to not likely result in any short- or long-term adverse effects. You must include copies of the correspondence with the participating agencies in your SWPPP and this NOI.
☐ Check to confirm you have provided documentation in your SWPPP as required by VI CGP Appendix C.
Documentation: Insert Text Here

Eligibi	lity	Criterion

Following the process outlined in Appendix C of the VI CGP, under which criterion are you eligible for coverage under this permit?

- ☐ Criterion E: ESA Section 7 consultation has successfully concluded. Consultation between a Federal agency and the USFWS and/or NMFS under section 7 of the ESA has concluded. Consultations can be either formal or informal, and would have occurred only as a result of a separate Federal action (e.g., during application for an individual wastewater discharge permit or the issuance of a wetlands dredge and fill permit), and the consultation must have addressed the effects of your construction activity's discharges and discharge-related activities on all ESA-listed threatened or endangered species and all designated critical habitat under the jurisdiction of each Service, as appropriate, in your action area. The result of this consultation must be either:
 - i. A biological opinion currently in effect that determined that the action in question (taking into account the effects of your facility's discharges and discharge-related activities) is likely to adversely affect, but is not likely to jeopardize the continued existence of listed species or result in the destruction or adverse modification of critical habitat. The biological opinion must have included the effects of your facility's discharges and discharge-related activities on all the listed species and designated critical habitat in your action area under the jurisdiction of each Service, as appropriate. To be eligible under (i), any reasonable and prudent measures specified in the incidental take statement must be implemented;
 - ii. Written concurrence (e.g., letter of concurrence) from the applicable Service(s) with a determination that your facility's discharges and discharge-related activities are not likely to adversely affect ESA-listed species and/or designated critical habitat. The concurrence letter must have included the effects of your facility's discharges and discharge-related activities on all the ESA-listed species and/or designated critical habitat on your species list(s) acquired from USFWS and/or NMFS as part of this worksheet.

The consultation does not warrant reinitiation under 50 CFR §402.16; or, if reinitiation of consultation is required (e.g., due to a new species listing, critical habitat designation, or new information), the Federal action agency has reinitiated the consultation and the result of the consultation is consistent with the statements above. (Note: you must include any reinitiation documentation from the Services or consulting Federal agency with your NOI.) -

Check to confirm you have provided documentation in your SWPPP as required by	V
CGP Appendix C.	

Documentation: Insert Text Here

Follov	ility Criterion wing the process outlined in Appendix C of the VI CGP, under which criterion are you ble for coverage under this permit?
	Criterion F: <u>Issuance of section 10 permit.</u> Potential take is authorized through the issuance of a permit under section 10 of the ESA by the USFWS and/or NMFS, and this authorization addresses the effects of the site's discharges and discharge-related activities on ESA-listed species and designated critical habitat. You must include copies of the correspondence between yourself and the participating agencies in your SWPPP and your NOI.
	☐ Check to confirm you have provided documentation in your SWPPP as required by VI CGP Appendix C.
	Documentation: Insert Text Here
3.2	Historic Property Screening Process
Do you	ndix D, Step 1 u plan on installing any stormwater controls that require subsurface earth disturbance, ing, but not limited to, any of the following stormwater controls at your site?
all stor	osurface earth disturbance of any stormwater controls is proposed for this project. Due to mwater runoff discharging into the coast and downstream flooding not being a concern, vater retention/detention via an infiltration basin is not proposed.
area t For the in a sir experi	orary mulch berms have been installed on-site at the bottom of all downhill slopes for the hat has been partially cleared per an approved Permit Letter Request received in 2023. It remaining brush and vegetation to be cleared, temporary mulch berms will be installed milar way. Permanent rock berms are proposed in locations within the project area that ence concentrated flow to account for any additional runoff rates and erosion. A copy of posion Control Plan and Grading Plan are included in this Coastal Zone Management Permit ration.
If you a	answered yes in Step 1, have prior professional cultural resource surveys or other ations determined that historic properties do not exist, or have prior disturbances at the site precluded the existence of historic properties? If yes, no further documentation is required for Section 3.2 of the Template, and you may provide the prior documentation in your SWPPP. If no, proceed to Appendix D, Step 3.
If you	ndix D, Step 3 answered no in Step 2, have you determined that your installation of subsurface earth- sing stormwater controls will have no effect on historic properties? YES NO

- If yes, provide documentation of the basis for your determination.
- If no, proceed to Appendix D, Step 4.

f you	answered	eps 4 and 5 Ino in Step 3, did the State Historic Preservation Officer (SHPO), Tribal Historic fice (THPO), or other Tribal representative (whichever applies) respond to you
ooten	tially pres	dar days to indicate their views as to the likelihood that historic properties are ent on your site and may be impacted by the installation of stormwater controls obsurface earth disturbance? YES NO
•	_	escribe the nature of their response: Written indication that no historic properties will be affected by the installation of stormwater controls.
		Written indication that adverse effects to historic properties from the installation of stormwater controls can be mitigated by agreed upon actions.
		No agreement has been reached regarding measures to mitigate effects to historic properties from the installation of stormwater controls.
		Other:
•	If no, no	further documentation is required for Section 3.2 of the Template.
3.3	Safe Drii	nking Water Act Underground Injection Control Requirements
Оо уо	u plan to	install any of the following controls? Check all that apply below.
Vo.		
		on trenches (if stormwater is directed to any bored, drilled, driven shaft or dug at is deeper than its widest surface dimension, or has a subsurface fluid distribution
		ercially manufactured pre-cast or pre-built proprietary subsurface detention chambers, or other devices designed to capture and infiltrate stormwater flow
	drilled, c	s, seepage pits, or improved sinkholes (if stormwater is directed to any bored, driven shaft or dug hole that is deeper than its widest surface dimension, or has a uce fluid distribution system)

SECTION 4: EROSION AND SEDIMENT CONTROLS AND DEWATERING PRACTICES

4.1 Natural Buffers or Equivalent Sediment Controls

Buffer Compliance Alternatives

Are there any receiving waters within 50 feet of your project's earth disturbances?

NO

4.2 Perimeter Controls

General

The site is currently being cleared based on an approved Permit Letter Request. Excess cleared vegetation can be moved to the bottom of the downhill slopes of the project area and formed into a berm to prevent the runoff from carrying any sediment off-site. Other erosion control methods currently implemented on-site are mulch-in-place and silt fencing where both have proven to be very effective construction means and methods and will continue to be used throughout the duration of construction for the project.

Specific Perimeter Controls

Mulch Berm			
Description: Ve	Description: Vegetation is being cleared with a low ground pressure skid steer or track		
excavator with	excavator with a mulching attachment to remove and grind the trees and vegetation within 2		
inches of the existing ground surface. All roots and stumps are being left in place with no			
soil/earth disturl	soil/earth disturbances. Excess mulch can be formed into a berm at the bottom of the		
downhill slopes	downhill slopes of the proposed work area for erosion control measures.		
Installation	10/14/2025		
Maintenance	Berm should be inspected immediately after each rainfall event and at least		
Requirements	daily during prolonged rainfall. Needed repairs to the berm must be made		
immediately. Remove any debris that comes into contact with berm.			

4.3 Sediment Track-Out

General

 Temporary construction access/exit was installed in the western part of the site to prevent track-out of sediment from the site while the approved clearing is being performed and shall remain in place until construction is completed.

Specific Track-Out Controls

Stabilized Construction Exit			
Description: 50' long and 20' wide, 6" minimum depth gravel construction entrance. 2"-3"			
diameter crushed stone minimum placed over a geotextile fabric.			
Installation	10/14/2025		
Maintenance	Add gravel when necessary to maintain effective construction entrance		
Requirements	ements throughout project construction.		
Design	Details provided		
Specifications			

4.4 Stockpiles or Land Clearing Debris Piles Comprised of Sediment or Soil

The construction may include small amounts of excavation of areas needing cut ins/steps within the steep slopes on-site for installation of the racking system, but no stockpiles of sediment are anticipated during construction of the project.

4.5 Minimize Dust

General

The Contractor is responsible for sweeping their own travel ways and the area located within 100 feet of the entrances and exits of the construction work zone. Sweeping will be conducted as needed to prevent the tracking of sediment/dust on the public roadway.

Specific Dust Controls

Water Truck	Water Truck			
Description:	Description:			
	 During construction, the smallest practical portion of the project area will be disturbed at one time to minimize the potential for dust generation. 			
A water	truck will be used to wet exposed areas within the work limits as needed for			
dust sup	pression.			
	the tact-out controls discussed above, sediments on the paved areas outside			
of the w	ork limits will be removed by sweeping to suppress dust generated by vehicle			
traffic.				
Installation 10/14/2025				
Maintenance	Wet exposed areas within the work limits as needed for dust suppression.			
Requirements				
Design	Refer to project specifications.			
Specifications				

4.6 Minimize Steep Slope Disturbances

General

Certain embankments and shoulders where work will be performed may feature steep slopes where cut ins and/or steps may need to be constructed for the installation of the proposed project on an as needed basis. Areas that require cut ins and/or steps shall be regularly inspected and protected from erosion with BMPs and Erosion Control Methods such as natural spray tack adhesive and additional silt fencing, as needed, before it results in sediment discharges/releases. Permanent stabilization will be provided by loaming and seeding slopes with grass in areas that appear bare after construction.

Specific Steep Slope Controls

Slope Stabilization			
Description: Ste	Description: Steep slopes work will be performed as work encounters them.		
Installation	11/1/2025		
Maintenance Requirements	Contractor shall maintain erosion controls in a functional condition at all times, including inspections once every seven (7) calendar days and within 24 hours of the occurrence of a storm event that produces 0.25 inches or more of rain within a 24-hour period. All damaged areas shall be replaced immediately.		
Design Specifications	Refer to project specifications.		

4.7 Topsoil

General

- Native topsoil shall be preserved unless infeasible. Preserving native topsoil is not required
 where the intended function of a specific area of the site calls for topsoil to be disturbed
 or removed. If suitable topsoil is found in disturbed areas, it will be removed and
 stockpiled and temporarily seeded until ready to use.
- Vegetation will be cleared and mulched to be spread over topsoil. This mulch will prevent erosion of the topsoil during construction activities.

4.8 Soil Compaction

General

 Vehicle and equipment use shall be avoided in areas where seeding and vegetative stabilization will occur to avoid compaction of soil. Prior to seeding in areas of disturbed soils, the contractor shall condition the soil as necessary to support vegetative growth.

4.9 Storm Drain Inlets

Not required for this project.

4.10 Constructed Site Drainage Feature

Not required for this project.

4.11 Sediment Basins or Similar Impoundments

Not required for this project.

4.12 Chemical Treatment

No chemical treatment is anticipated.

4.13 Dewatering Practices

No dewatering is anticipated for this project.

4.14 Other Stormwater Controls

Ν	$ \cap $	ne	115	ed	

4.1	5 Site Stabilization
Tota	al Amount of Land Disturbance Occurring at Any One Time
	Five Acres or less
\boxtimes	More than Five Acres

Seeding				
	e 🗌 Non-Vegetative			
☐ Temporary	□ Permanent			
Description:				
 Contract 	ctor shall implement and maintain stabilization measures that minimize erosion			
from an	y areas of exposed soil on the site. Disturbed soils will be seeded with a seed			
mix that	matches existing grasses.			
Installation	Refer to project schedule			
Completion	Refer to project schedule			
Maintenance	Any grassed areas disturbed by the work shall be restored with loam			
Requirements	and seed.			
	Contractor shall reseed and if necessary maintain until grass has			
	grown.			
	Landscaped areas disturbed by work shall be restored to existing			
	conditions.			
Design	Refer to project specifications for seeding requirements.			
Specifications				

Mulching			
☐ Vegetative	☐ Vegetative ☒ Non-Vegetative		
□ Temporary □ Permanent			
Description:			
 Contract 	 Contractor shall mulch cleared vegetation and spread over disturbed areas to 		
provide	provide protection from erosion		
Installation	Refer to project schedule		
Completion	Refer to project schedule		
Maintenance	Mulch shall be reapplied in areas where mulch has been removed or		
Requirements	no longer provides adequate protection during construction.		

SECTION 5: POLLUTION PREVENTION CONTROLS

5.1 Potential Sources of Pollution

Construction Site Pollutants

Potential sources of sediment come from: Clearing and grubbing activities, any site grading or excavation, vehicle tracking, topsoil stripping and stockpiling, and landscaping activities.

Potential pollutants and sources come from sanitary facilities, heavy equipment and vehicles, and materials storage areas.

Pollutant-Generating Activity	Pollutants or Pollutant Constituents (That could be discharged if exposed to stormwater)	Location on Site (Or reference SWPPP site map where this is shown)
Organic Fertilizer	Nitrogen and phosphates	Open seeded areas for final stabilization
Concrete	Limestone, sand, pH, chromium	Equipment pads, fence posts
Hydraulic Oil/Fluids	Mineral oil, petroleum distallates	Leaks or broken equipment
Gasoline	Benzene, ethyl benzene, toluene, xylene, MTBE	Staging areas
Diesel Fuel	Petroleum distillate, oil and grease, naphthalene, xylenes	Staging areas
Antifreeze/coolant	Ethylene glycol, propylene glycol, heavy metals (copper, lead, zinc)	Leaks or broken equipment hoses
Temporary Sanitary Facilities	Bacteria, parasites, viruses, funguses	Staging areas

5.2 Spill Prevention and Response

In the event of a spill an on-site spill kit shall be available to contain and remove the spill. In the event the spill cannot be contained and removed with the on-site spill kit, immediately notify emergency personnel.

5.3 Fueling and Maintenance of Equipment or Vehicles

General

 A variety of vehicles and equipment will be used on-site. Care shall be taken to eliminate discharge of any spilled or leaked chemicals, including fuel, from the project area. All fueling will be performed off-site. When fueling must occur on-site, the area shall be protected by secondary containment.

Specific Pollution Prevention Practices

Daily Inspection			
Description: All vehicles shall be inspected prior to use daily for leaks, damage, and other			
	problems and brought up to the site superintendent. Leaks shall be repaired immediately, or		
the equipment shall be removed from the site.			
Implementation	nplementation Inspections are daily starting during mobilization until the end of the		
project.			
Maintenance	Daily inspections will occur prior to work.		
Requirements			

5.4 Washing of Equipment and Vehicles

General

- Equipment will generally be washed off location. When done on site, it shall be done in a contained area without detergents.
- 5.5 Storage, Handling, and Disposal of Building Products, Materials, and Wastes
- 5.5.1 Building Materials and Building Products

General

- Building materials will be stockpiled in a designated staging area when kept on site.
- 5.5.2 Pesticides, Herbicides, Insecticides, Fertilizers, and Landscape Materials

No pesticides, herbicides, or insecticides are anticipated to be used. Landscape materials will be stored at a combined staging area and materials storage area.

Storage in Containers in Materials Storage Area		
Description: Secure containers to contain materials in the staging area.		
Implementation	11/1/2025	
Maintenance	Inspections must be performed once every seven (7) calendar days and	
Requirements	within 24 hours of the occurrence of a storm event that produces 0.25	
·	inches or more of rain within a 24-hour period.	

5.5.3 Diesel Fuel, Oil, Hydraulic Fluids, Other Petroleum Products, and Other Chemicals

No diesel fuel, oil, hydraulic fluids, or other petroleum products or other chemicals are anticipated to be stored on site.

5.5.4 Hazardous or Toxic Waste

General

Diesel fuel, oil, hydraulic fluids, other petroleum products, and other chemicals will be limited in scope of use and preferably stored off-Site; if they must be stored on site, they will be stored at a combined staging area and materials storage area within a secure and covered area. In the event of any spills, the spill must be reported to the appropriate authorities and the engineer.

5.5.5 Construction and Domestic Waste

General

Waste will be stored in appropriate waste containers in the staging area until disposed of. All waste shall be disposed of properly by the contractor in accordance with all local, state, and federal regulations. No waste shall be buried or dumped on the project site.

5.5.6 Sanitary Waste

General

- Portable toilets may be provided at the site throughout the construction phase. Toilets will be secure to not be tipped or knocked over. Waste will be collected from the portable facilities as needed to keep sanitary conditions. Toilets will be inspected regularly for evidence of leaking holding tanks. Toilets with leaking holding tanks will be removed and replaced with new toilets.
- 5.6 Washing of Applicators and Containers used for Stucco, Paint, Concrete, Form Release Oils, Cutting Compounds, or Other Materials

Not to be performed on site during construction.

5.7 Application of Fertilizers

General

Commercial fertilizer shall be a product complying with the local and United States fertilizer laws. Fertilizer for planting shall be formulated for top-dressing, soil surface application to plants. Fertilizer shall be designed and certified by the manufacturer to provide controlled release of fertilizer continuously for not less than 9 months. One hundred percent of the nitrogen content shall be derived from organic materials. Nitrogen source shall be coated to ensure slow release. Fertilizer will not be kept on-site and only small volumes will be brought for use.

5.8 Other Pollution Prevention Practices

No other pollution prevention practices are anticipated.

SECTION 6: INSPECTION, MAINTENANCE, AND CORRECTIVE ACTION

6.1 Inspection Personnel and Procedures

ite Inspection Schedule
Standard Frequency:
■ Every 7 calendar days
☐ Every 14 calendar days and within 24 hours of either:
 A storm event that produces 0.25 inches or more of rain within a 24-hour period (including when there are multiple, smaller storms that alone produce less than 0.25 inches but together produce 0.25 inches or more in 24 hours), or A storm event that produces 0.25 inches or more of rain within a 24-hour period on the first day of a storm and continues to produce 0.25 inches or more of rain on subsequent days (you conduct an inspection within 24 hours of the first day of the storm and within 24 hours after the last day of the storm that produces 0.25 inches or more of rain (i.e., only two inspections would be required for such a storm event)), or A discharge caused by snowmelt from a storm event that produces 3.25 inches or more of snow within a 24-hour period.
Increased Frequency (if applicable):
For areas of sites discharging to sediment or nutrient-impaired waters or to waters designated as Tier 2, Tier 2.5, or Tier 3
☐ Every 7 days and within 24 hours of either:
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A discharge caused by snowmelt from a storm event that produces 3.25 inches or more of snow within a 24-hour period.
Reduced Frequency (if applicable)
For stabilized areas
☐ Twice during first month, no more than 14 calendar days apart; then once per month after first month until permit coverage is terminated consistent with Part 8 in any area of your site where the stabilization steps in 2.2.1.2a and 2.2.1.2b have been completed.
For stabilized areas on "linear construction sites" (as defined in Appendix A)
☐ Twice during first month, no more than 14 calendar days apart; then once more within 24 hours of a storm event that produces 0.25 inches or more of rain within a 24-hour period, or within 24 hours of a snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period

For arid, semi-arid, or drought-stricken areas during seasonally dry periods or during drought Once per month and within 24 hours of either:
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period.
Insert beginning and ending month identified as the seasonally dry period for your area or the valid period of drought: • Beginning month of the seasonally dry period: 1/1/2025 • Ending month of the seasonally dry period: 4/30/2025
For frozen conditions where construction activities are being conducted Once per month
Insert beginning and ending dates of frozen conditions on your site: Beginning date of frozen conditions: Insert approximate date Ending date of frozen conditions: Insert approximate date
For frozen conditions where construction activities are suspended Inspections are temporarily suspended
Insert beginning and ending dates of frozen conditions on your site: Beginning date of frozen conditions: Insert approximate date Ending date of frozen conditions: Insert approximate date
Devictoring Increation Cohedule

Dewatering Inspection Schedule

Dewatering Inspection	
☐ Once per day on which the discharge of dewatering water occurs.	

Rain Gauge Location (if applicable) https://forecast.weather.gov/MapClick.php?lat=17.7123&lon=-64.8436

Inspection Report Forms
See Appendix D of this SWPPP for Site Inspection Report Form

6.2 Corrective Action

Personnel Responsible for Corrective Actions Christian Loranger 508-965-8637 nbdsolar@gmail.com

Corrective Action Logs See Appendix E of this SWPPP for Corrective Action Logs

6.3 Delegation of Authority

Duly Authorized Representative(s) or Position(s):

Quantum Solar, LLC

Subsidiary of Vielectron, LLC

Christian Loranger

Owner

5000 Est. Enighed, Ste 4a PMB 146 St. John, U.S.V.I 00830

Phone: 508-965-8637 nbdsolar@gmail.com

VIELECTRON, LLC

Christian Loranger

Operator

5000 Est. Enighed, Ste 4a PMB 146 St. John, U.S.V.I 00830

Phone: 508-965-8637 nbdsolar@gmail.com

SECTION 7: TURBIDITY BENCHMARK MONITORING FOR DEWATERING DISCHARGES

Not anticipated for this project

SECTION 8: CERTIFICATION AND NOTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name: Christian Loranger	Title: Owner / Developer / Operator
Signature:	Date:
signature.	Date.

SWPPP APPENDICES

Attach the following documentation to the SWPPP:

Appendix A - Site Maps

Appendix B - Copy of 2012 VI CGP

Appendix C - NOI and EPA Authorization Email

Appendix D - Site Inspection Form and Dewatering Inspection Form (if applicable)

Appendix E - Corrective Action Log

Appendix F - SWPPP Amendment Log

Appendix G - Subcontractor Certifications/Agreements

Appendix H - Grading and Stabilization Activities Log

Appendix I - Training Documentation

Appendix J - Delegation of Authority


Appendix K - Endangered Species Documentation

Appendix L - Historic Preservation Documentation

Appendix M - Rainfall Gauge Recording

Appendix N – Turbidity Meter Manual and Manufacturer's Instructions

Appendix A - Site Maps



WWW.EPA.GOV/NPDES/STORMWATER FOR ADDITIONAL INFORMATION.

9. CONSTRUCT SOLAR RACKING AND INSTALL SOLAR PANELS ON RACKING.

10. INSTALL UNDERGROUND CONDUIT, PV INVERTERS, EQUIPMENT PADS,

11. APPLY EROSION CONTROL LOW HEIGHT GRASS MIX TO ANY DISTURBED

BATTERIES AND POWER POLES.

VEGETATION AREAS THROUGHOUT THE SITE.

CONTROL PLAN

PROJECT NO. 23.141001.00

SHEET 3 OF 9

SCALE IN FEET

AND PREVENT EROSION.


PROJECT.

CORRECTED IN A TIMELY MANNER.

9. THE SITE SHALL BE INSPECTED AFTER ALL MAJOR STORM EVENTS. ANY

DEFICIENCIES IN THE EROSION CONTROL AND VEGETATION SHALL BE

10. THERE IS NO PROPOSED WATER, SEWER OR LIGHTING AS PART OF THIS



- 2. LAYOUT ALL WORK, ESTABLISH GRADES, LOCATE EXISTING UNDERGROUND BARRICADES AND PROTECTION FACILITIES PRIOR TO THE BEGINNING OF ANY GRADING, EXCAVATION OR TRENCHING OPERATIONS.
- IN AREAS OF GRADING, THE SUBGRADE SHALL BE LOOSENED BY SCARIFYING TO A DEPTH OF AT LEAST 2" TO ENSURE BONDING OF THE TOPSOIL AND SUBSOIL.
- 4. AREAS OF EXCAVATION ACTIVITIES SHALL BE RESTORED TO A MINIMUM OF 4" OF SEEDED TOPSOIL, FERTILIZER, AND MULCH.
- 5. CONTRACTOR'S WORK INCLUDES, BUT IS NOT LIMITED TO, PROVIDING ALL LABOR, MATERIALS, EQUIPMENT, SUPERVISION, QUALITY CONTROL, AND INCIDENTALS NECESSARY TO EXCAVATE, DEWATER AND CONTROL SURFACE WATER, BACKFILL, CONDUCT COMPACTION AND TESTING OF MATERIALS, ROUGH GRADE, AND REMOVE SEDIMENT AND SOIL AND OTHER SUBSURFACE MATERIALS IN ACCORDANCE WITH THE DESIGN DOCUMENTS, APPLICABLE LAW, APPLICABLE PERMITS, AND PROJECT AGREEMENTS.
- 6. ALL STAKING AND LAYOUT WORK REQUIRED FOR WORK INCLUDED UNDER THIS SECTION SHALL BE THE RESPONSIBILITY OF CONTRACTOR. CONTRACTOR SHALL ESTABLISH ALL REFERENCE POINTS, LAY OUT THE WORK, AND BE RESPONSIBLE FOR ALL LINES, ELEVATIONS, MEASUREMENTS AND OTHER GRADING OPERATIONS.
- UNIFORMLY GRADE AREAS WITHIN SPECIFIED LIMITS, INCLUDING ADJACENT TRANSITIONS. SMOOTH FINISHED SURFACES WITHIN SPECIFIED TOLERANCES, COMPACT WITH UNIFORM LEVELS OR SLOPES BETWEEN POINTS INDICATED, IN DESIGN DOCUMENTS.

- B. LANDSCAPE AREAS: COMPACT TOP 6 INCHES OF SUBGRADE AND EACH LAYER OF FILL MATERIAL AT 85 PERCENT MAXIMUM DENSITY, OR AS REQUIRED.
- C. EQUIPMENT PADS: THE UPPER 12 INCHES OF SUBGRADE SHALL BE COMPACTED TO 95 PERCENT RELATIVE COMPACTION, OR AS REQUIRED.
- MATERIAL DISPOSAL AND STORAGE SITES
 - A. SUITABLE EXCAVATED MATERIALS MAY BE STOCKPILED AND RE-USED IN SYSTEM CONSTRUCTION.
 - B. DISPOSE OF UNSUITABLE OR EXCESS EXCAVATED AND WASTE MATERIALS IN ACCORDANCE WITH APPLICABLE LAW AND APPLICABLE PERMITS.
 - C. CONTRACTOR STOCKPILE AND LAYDOWN AREAS SHALL BE DEVELOPED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONSTRUCTION DESIGN DOCUMENTS.
- 10. EMBANKMENTS AND BACKFILL SURROUNDING STRUCTURES SHALL BE COMPACTED TO A MINIMUM OF 95 PERCENT.
- 11. EARTH SLOPES SHALL NOT EXCEED 3 HORIZONTAL TO 1 VERTICAL UNLESS SHOWN OTHERWISE.

- SEDIMENT CONTROL DEVISES NEEDED TO PREVENT RUNOFF TO THE COAST AND OFFSITE.
- 3. THE CONTRACTOR SHALL STABILIZE ANY AND ALL DITCHES AND SWALES PRIOR TO DIRECTING STORMWATER RUN-OFF TO THEM.
- 4. ACCESS DRIVEWAYS MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
- 5. EROSION CONTROL MEASURES ARE TO BE INSPECTED WEEKLY AND AFTER EVERY 0.25" OF RAINFALL WITHIN A 24 HOUR PERIOD.
- 6. UNSTABILIZED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 72 HOURS OF FINAL GRADING, OR PRIOR TO A 0.25" STORM OCCURING AFTER THE DISTURBANCE, WHICHEVER OCCURS SOONER.
- 7. TEMPORARY STABILIZATION MEASURES MUST REMAIN IN PLACE THROUGH ALL CONSTRUCTION PHASES, UNTIL THE SITE IS PERMANENTLY
- 8. THE SITE SHALL BE STABILIZED BY ESTABLISHING AT LEAST 95% VEGETATIVE COVER UNIFORMLY DISTRIBUTED, INCLUDING UNDER THE
- 9. PROVIDE EROSION CONTROL MATTING ON ALL 3:1 OR GREATER SLOPES.
- 10. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AFTER THE SITE HAS BEEN STABILIZED.



SCALE IN FEET

QUANTUM SOLAR LLC

4 VIELECTRON LLC COMPANY

D EST. ENIGHED, STA 4A, PMB 1

SHA AN HO' USEI OR INC

FOR PERMITTING

PURPOSES ONLY

GRADING & DRAINAGE PLAN

PROJECT NO. 23.141001.00

SHEET 5 OF 9

Appendix B - Copy of 2012 VI CGP

Appendix C - Copy of NOI and EPA Authorization Email

Appendix D - Copy of Site and Dewatering Inspection Forms

Project Name: Proposed	d Solar Energy	Facility with	Battery S	torage -	Bovoni
ΓPDES ID Number:					

Section A – General Information (If necessary, complete additional inspection reports for each separate inspection location.)				
Inspector	Information			
Inspector Name:	Title:			
Company Name:	Email:			
Address:	Phone Number:			
Inspection	on Details			
Inspection Date:	Inspection Location:			
Inspection Start Time: Inspection End Time:				
Current Phase of Construction: Weather Conditions During Inspection:				
Did you determine that any portion of your site was unsafe for inspection per	CGP Part 4.5? Yes No			
If "Yes," provide the following information:				
Location of unsafe conditions:				
The conditions that prevented you inspecting this location:				
Indicate the required inspection frequency: (Check all that apply. You may be subject to different inspection frequencies in different areas of the site.)				
Standard Frequency (CGP Part 4.2): At least once every 7 calendar days; OR Once every 14 calendar days and within 24 hours of the occurrence of either:				
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period 				
Increased Frequency (CGP Part 4.3.1) (If site discharges to sediment or nutrient-impaired waters or to waters designated as Tier 2, Tier 2.5, or Tier 3): Once every 7 calendar days and within 24 hours of the occurrence of either:				
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period 				

2022 Construction General Permit Site Inspection Report

TPDES ID Number:
Reduced Frequency (CGP Part 4.4): For stabilized areas: Twice during first month, no more than 14 calendar days apart; then once per month after first month until permit coverage is terminated
□ For stabilized areas on "linear construction sites": Twice during first month, no more than 14 calendar days apart; then once more within 24 hours of the occurrence of either:
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period
☐ For arid, semi-arid, or drought-stricken areas during seasonally dry periods or during drought: Once per month and within 24 hours of the occurrence of either:
 A storm event that produces 0.25 inches or more of rain within a 24-hour period, or A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period
☐ For frozen conditions where construction activities are being conducted: Once per month
Was this inspection triggered by a storm event producing 0.25 inches or more of rain within a 24-hour period? ☐ Yes ☐ No
If "Yes," how did you determine whether the storm produced 0.25 inches or more of rain? On-site rain gauge Weather station representative of site. Weather station location:
Total rainfall amount that triggered the inspection (inches):
Was this inspection triggered by a snowmelt discharge from a storm event producing 3.25 inches or more of snow within a 24-hour period? Yes No
If "Yes," how did you determine whether the storm produced 3.25 inches or more of snow? On-site rain gauge Weather station representative of site. Weather station location:
Total snowfall amount that triggered the inspection (inches):

Project Name: Proposed Solar Energy Facility with Battery Storage - Bovoni

2022 Construction General Permit Site Inspection Report

Project Name: Proposed Solar Energy Facility with Batte	ery Storage - Bovoni
TPDES ID Number:	

Section B - Condition and Effectiveness of Erosion and Sediment (E&S) Controls (CGP Part 2.2) (Insert additional rows if needed)						
Type and Location of E&S Control	Conditions Requiring Routine Maintenance? ¹	If "Yes," How Many Times (Including This Occurrence) Has This Condition Been Identified?	Conditions Requiring Corrective Action? ^{2, 3}	Date on Which Condition First Observed (If Applicable)?	Description of Conditions Observed	
1.	☐ Yes ☐ No		□ Yes □ No			
2.	☐ Yes ☐ No		☐ Yes ☐ No			
3.	☐ Yes ☐ No		☐ Yes ☐ No			
4.	☐ Yes ☐ No		□ Yes □ No			
5.	☐ Yes ☐ No		☐ Yes ☐ No			
If the same routine maintenance was found to be necessary three or more times for the same control at the same location (including this occurrence), follow the corrective action requirements and record the required information in your corrective action log, or describe here why you believe the specific condition should still be addressed as routine maintenance:						

- 1. A stormwater control needs a significant repair or a new or replacement control is needed, or, in accordance with Part 2.1.4.c, you find it necessary to repeatedly (i.e., three (3) or more times) conduct the same routine maintenance fix to the same control at the same location (unless you document in your inspection report under Part 4.7.1.c that the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix under 2.1.4); or
- 2. A stormwater control necessary to comply with the requirements of this permit was never installed, or was installed incorrectly; or
- 3. Your discharges are not meeting applicable water quality standards; or
- 4. A prohibited discharge has occurred (see CGP Part 1.3); or
- 5. During the discharge from site dewatering activities:
 - a. The weekly average of your turbidity monitoring results exceeds the 50 NTU benchmark (or alternate benchmark if approved by EPA pursuant to Part 3.3.2.b); or
- b. You observe or you are informed by EPA, State, or local authorities of the presence of the conditions specified in Part 4.6.3.e.

¹ Routine maintenance includes minor repairs or other upkeep performed to ensure that the site's stormwater controls remain in effective operating condition, not including significant repairs or the need to install a new or replacement control. Routine maintenance is also required for specific conditions: (1) for perimeter controls, whenever sediment has accumulated to half or more the above-ground height of the control (CGP Part 2.2.3.c.i); (2) where sediment has been tracked-out from the site onto paved roads, sidewalks, or other paved areas (CGP Part 2.2.4.d); (3) for inlet protection measures, when sediment accumulates, the filter becomes clogged, and/or performance is compromised (CGP Part 2.2.10.b); and (4) for sediment basins, as necessary to maintain at least half of the design capacity of the basin (CGP Part 2.2.12.f)

² Corrective actions are triggered only for specific conditions (CGP Part 5.1):

³ If a condition on your site requires a corrective action, you must also fill out a corrective action log found at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. See CGP Part 5.4 for more information.

Construction General Permit Site Inspection Report

Project Name: F	Proposed Solar E	nergy Facility v	with Battery Sto	rage - Bovoni
TPDES ID Numb	er:			

Section C - Condition and Effectiveness of Pollution Prevention (P2) Practices and Controls (CGP Part 2.3) (Insert additional rows if needed)					
Type and Location of P2 Practices and Controls	Conditions Requiring Routine Maintenance? ¹	If "Yes," How Many Times (Including This Occurrence) Has This Condition Been Identified?	Conditions Requiring Corrective Action? ^{2, 3}	Date on Which Condition First Observed (If Applicable)?	Description of Conditions Observed
1.	□ Yes □ No		☐ Yes ☐ No		
2.	□ Yes □ No		☐ Yes ☐ No		
3.	☐ Yes ☐ No		☐ Yes ☐ No		
4.	☐ Yes ☐ No		☐ Yes ☐ No		
5.	□ Yes □ No		☐ Yes ☐ No		
If the same routine maintenance was found to be necessary three or more times for the same control at the same location (including this occurrence), follow the corrective action requirements and record the required information in your corrective action log, or describe here why you believe the specific condition should still be addressed as routine maintenance:					

Project Name: Proposed	Solar Energy	Facility with	Battery Sto	rage - Bovoni
ΓPDES ID Number:				

Section D - Stabilization of Exposed Soil (CGP Part 2.2.14) (Insert additional rows if needed)					
Specific Location That Has Been or Will Be Stabilized	Stabilization Method and Applicable Deadline	Stabilization Initiated?	Final Stabilization Criteria Met?	Final Stabilization Photos Taken?	Notes
1.		☐ Yes ☐ No	☐ Yes ☐ No	☐ Yes ☐ No	
		If "Yes," date initiated:	If "Yes," date criteria met:		
2.		☐ Yes ☐ No	☐ Yes ☐ No	☐ Yes ☐ No	
		If "Yes," date initiated:	If "Yes," date criteria met:		
3.		☐ Yes ☐ No	☐ Yes ☐ No	☐ Yes ☐ No	
		If "Yes," date initiated:	If "Yes," date criteria met:		
4.		☐ Yes ☐ No	☐ Yes ☐ No	☐ Yes ☐ No	
		If "Yes," date initiated:	If "Yes," date criteria met:		
5.		☐ Yes ☐ No	☐ Yes ☐ No	☐ Yes ☐ No	
		If "Yes," date initiated:	If "Yes," date criteria met:		

Project Name: Proposed Solar Energy Facility with Battery Storage - Bovon	ıi
TPDES ID Number:	

Section E - Description of Discharges (CGP Part 4.6.2) (Insert additional rows if needed)				
Was a discharge (not includ	ling dewatering) occurring from any part of your site at the time of the inspection? ⁴ ☐ Yes ☐ No			
 If "Yes," for each point of discharge, document the following: The visual quality of the discharge. The characteristics of the discharge, including color; odor; floating, settled, or suspended solids; foam; oil sheen; and other indicators of stormwater pollutants. Signs of the above pollutant characteristics that are visible from your site and attributable to your discharge in receiving waters or in other constructed or natural site drainage features. 				
Discharge Location	Observations			
1.				
2.				
3.				
4.				
5.				

⁴ If a dewatering discharge was occurring, you must conduct a dewatering inspection pursuant to CGP Part 4.3.2 and complete a separate dewatering inspection report.

Project Name: Proposed Solar Energy Facility with Battery Storage	- Bovoni
TPDES ID Number:	

Section F - Signature and Certification (CGP Part 4.7.2)

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information contained therein. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information contained is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

MANDATORY: Signature of Operator or "Duly Authorized Representative:"			
Signature:	Date:		
Printed Name:	Affiliation:		
OPTIONAL: Signature of Contractor or Subcontractor			
Signature:	Date:		
Printed Name:	Affiliation:		

Appendix E - Copy of Corrective Action Log

2022 CGP Corrective Action Log

Project Name: Proposed Solar Energy Facility with Battery Storage - Bovoni

Section A – Individual Completing this Log			
Name:	Title:		
Company Name:	Email:		
Address:	Phone Number:		
	Problem (CGP Part 5.4.1.a) ing the condition that triggered corrective action.		
Date problem was first identified:	Time problem was first identified:		
What site conditions triggered this corrective action? (Check the box that applies. See instructions for a description of each triggering condition (1 thru 6).) 1 1 2 3 4 5 5 5 6			
Specific location where problem identified:			
Provide a description of the specific condition that triggered the need for corrective action and the cause (if identifiable):			
Section C - Corrective Action Completion (CGP Part 5.4.1.b) Complete this section <u>within 24 hours</u> after completing the corrective action.			
For site condition # 1, 2, 3, 4, or 6 (those not related to a dewatering discharge) confirm that you met the following deadlines (CGP Part 5.2.1):			
 Immediately took all reasonable steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events. AND 			
Completed corrective action by the close of the next business day, un	lless a new or replacement control, or significant repair, was required. OR		
 Completed corrective action within seven (7) calendar days from the time of discovery because a new or replacement control, or significant repair, was necessary to complete the installation of the new or modified control or complete the repair. OR 			
It was infeasible to complete the installation or repair within 7 calenda information:	r days from the time of discovery. Provide the following additional		
Explain why 7 calendar days was infeasible to complete the installatio	n or repair:		

Provide your schedule for installing the stormwater control and making it operational as soon as feasible after the 7 calendar days:					
For site condition # 5a, 5b, or 6 (those related to a dewatering discharge), confirm that you met the following deadlines: Immediately took all reasonable steps to minimize or prevent the discharge of pollutants until a solution could be implemented, including shutting off the dewatering discharge as soon as possible depending on the severity of the condition taking safety considerations into account. Determined whether the dewatering controls were operating effectively and whether they were causing the conditions. Made any necessary adjustments, repairs, or replacements to the dewatering controls to lower the turbidity levels below the benchmark or remove the visible plume or sheen.					
Describe any modification(s) made as part of corrective action: (Insert additional rows below if applicable)	Date of completion:	SWPPP update necessary?	If yes, date SWPPP was updated:		
1.		Yes No	updated.		
2.		Yes No			
Section D - Signature	and Certification (CGP	Part 5.4.2)			
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information contained therein. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information contained is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."					
MANDATORY: Signature of Operator or "Duly Authorized Representative:"					
Signature:	Date:	Date:			
Printed Name:	Affiliation:	Affiliation:			
OPTIONAL: Signature of Contractor or Subcontractor					
Signature:	Date:	Date:			
Printed Name:	Affiliation:	Affiliation:			

Appendix F - SWPPP Amendment Log

No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

Appendix G - Subcontractor Certifications/Agreements

SUBCONTRACTOR CERTIFICATION STORMWATER POLLUTION PREVENTION PLAN

As a subcontractor, you are required to comply with the Stormwater Pollution Prevention Plan (SWPPP) for any work that you perform on-site. Any person or group who violates any condition of the SWPPP may be subject to substantial penalties or loss of contract. You are encouraged to advise each of your employees working on this project of the requirements of the SWPPP. A copy of the SWPPP is available for your review at the office trailer.

Each subcontractor engaged in activities at the construction site that could impact stormwater must be identified and sign the following certification statement:

I certify under the penalty of law that I have read and understand the terms and conditions of the SWPPP for the above designated project and agree to follow the practices described in the SWPPP.

Appendix H - Grading and Stabilization Activities Log

Date Grading Activity Initiated	Description of Grading Activity	Description of Stabilization Measure and Location	Date Grading Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures Initiated
			Date:	
			☐ Temporary☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	
			Date:	
			☐ Temporary ☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	
			Date:	
			☐ Temporary	
			☐ Permanent	

Appendix I –Training Documentation

Appendix J - Delegation of Authority Form

Delegation of Authority

below to be a environmenta	(name), hereby designate the person or specifically described position aduly authorized representative for the purpose of overseeing compliance with all requirements, including the EPA's Construction General Permit (CGP), at the construction site. The designee is authorized to sign any water pollution prevention plans and all other documents required by the permit.
	(name of person or position) (company) (address) (city, State, zip) (phone)
as set forth in A	authorization, I confirm that I meet the requirements to make such a designation Appendix G of EPA's CGP, and that the designee above meets the definition of a ed representative" as set forth in Appendix G.
direction or su properly gather or persons whe information, the accurate, and than true, acc	penalty of law that this document and all attachments were prepared under my apervision in accordance with a system designed to assure that qualified personnel ered and evaluated the information submitted. Based on my inquiry of the person o manage the system, or those persons directly responsible for gathering the ne information submitted is, to the best of my knowledge and belief, true, discomplete. I have no personal knowledge that the information submitted is other curate, and complete. I am aware that there are significant penalties for se information, including the possibility of fine and imprisonment for knowing
Name:	
Company:	
Title:	
Signature:	
Date:	

Appendix K - Endangered Species Documentation

A copy of the Biological Study is included in this Coastal Zone Management Permit Application.

Appendix L – Historic Properties Documentation

No cultural resources were identified on-site. A copy of the Phase 1 (A&B) Archaeological Survey is included in this Coastal Zone Management Permit Application.

Appendix M - Rainfall Gauge Recording

Use the table below to record the rainfall gauge readings at the beginning and end of each work day. An example table follows.

Month/Year		Month/Year		Month/Year				
Day	Start time	End time	Day	Start time	End time	Day	Start time	End time
1			1			1		
2			2			2		
3			3			3		
4			4			4		
5			5			5		
6			6			6		
7			7			7		
8			8			8		
9			9			9		
10			10			10		
11			11			11		
12			12			12		
13			13			13		
14			14			14		
15			15			15		
16			16			16		
17			17			17		
18			18			18		
19			19			19		
20			20			20		
21			21			21		
22			22			22		
23			23			23		
24			24			24		
25			25			25		
26			26			26		
27			27			27		
28			28			28		
29			29			29		
30			30			30		
31			31			31		

Appendix N – Turbidity Monitoring Sampling Documentation

Not anticipated for this project

Attachment D – Biological Study



A BIOLOGICAL SURVEY BOVONI 17 REMAINDER ESTATE BOVONI, ST. THOMAS USVI

Prepared For Garitech





By Kadison Islands Consulting, LLC P.O. Box 305124 St. Thomas, U.S. Virgin Islands 00803

20 February 2024

A BIOLOGICAL SURVEY

BOVONI 17 REMAINDER ESTATE BOVONI, ST. THOMAS USVI

TABLE OF CONTENTS

		Page
INTRODU	JCTION AND METHODS	4
RESULTS	AND DISCUSSION	
		7
SIGNIFIC	ANCE OF RESULTS and RECOMMENDATIONS3	35
TABLES		
Table 1.	A list of plant species observed during floral surveys from January 23 to February 11, 2024 at the proposed solar field development at Bovoni 17 Remainder, St. Thomas USVI.	18
Table 2.	A list of animal species observed during surveys from January 23 to February 11, 2024 at the proposed solar field development at Bovoni 17 Remainder, St. Thomas USVI.	20
Table 3.	Marine algae observed during a three hour survey in Stalley Bay on February 4, 2024	ł. 29
Table 4.	Stony corals observed during a three hour survey in Stalley Bay on February 4, 2024	. 30
Table 5.	Marine macro-invertebrates observed during a three hour survey in Stalley Bay on February 4, 2024.	30
Table 6.	Fish observed during a three hour survey in Stalley Bay on February 4, 2024.	31
FIGURES		
Figure 1.	Location map with project location shown.	5
Figure 2.	Map showing the location of the project site (yellow border) in relation to the Bovoni Landfill and Mangrove Lagoon Wastewater Treatment Plant.	5
Figure 3.	The ecological survey area at 17 Remainder, Estate Bovoni. A survey was conducted across the site and seaward of the property approximately 100 m.	6
Figure 4.	Survey routes and listening/viewing stations established during the study.	6
Figure 5.	Animals encountered on the Boyoni 17 Remaining property	20

Figure 6.	Insects encounted durinthe survey on the Bovoni 17 Remaining property.	21
Figure 7.	The rocky coastline along the proposed development site is covered in terrigenous rocks of various sizes, worn pebbles, and sparse areas of sand.	29
Figure 8.	The underwater benthos is covered in terrigenous rocks and boulders, with occasional patches of course, light sand.	2 4
Figure 9.	Emergent and barely submerged rocks and boulders define the outer edges of the small bays surveyed.	2 4
Figure 10.	A variety of macro-algae cover the rocks and boulders. The brown algae <i>Sargassum spp.</i> , <i>Turbinaria turbinata</i> and <i>Dictyota spp.</i> grow in thick mats over much of the site.	
Figures 11	• Herbaceous fishes like blue tang (<i>Acanthurus coeruleus</i>) and ocean surgeonfish (<i>A. bahianus</i>) grazed the algae covered rocks and boulders.	25 25
Figure 12.	Rock boring sea urchins (<i>Echinometra lucunter</i>), West Indian top shell (<i>Cittarium pica</i>) and West Indian sea eggs (<i>Tripneustes ventricosus</i>) grazed on the turf and calcareous algae growing on the rocks and boulders.	25
Figure 13.	Fire coral (<i>Milipora spp.</i>) and small oportunistic stony corals like finger coral (<i>Porites porites</i>) and mustard hill coral (<i>P. asteroides</i>) colonized the site.	26
Figute 14.	A small grass bed offshore of the survey area supported small fish and larger predatory jacks (<i>Caranx ruber</i>).	26
Figure 15.	Elkhorn (<i>Acropora palmata</i>) and fused staghorn (<i>A. prolifera</i>) corals were found on the rocky outcroppings at both the east and west side of the survey area.	27
Figure 16.	Areas of elkhorn coral (<i>A. palmata</i>) colonization. Stars represent where 5 or more cononies were found.	27
Figure 17.	A variety of macro-invertebrates were found in Stalley Bay. Commercially important species included the Caribbean spiney lobster (<i>Panularus argus</i>) and West Indian top shell (<i>Cittarium pica</i>).	32
Figure 18.	A wide variety of fishes were found in Stalley bay off the proposed development site	39

A BIOLOGICAL SURVEY

BOVONI 17 REMAINDER ESTATE BOVONI, ST. THOMAS USVI

INTRODUCTION AND METHODS:

The proposed development of a solar field, on property at Bovoni 17 Remainder, initiated a biological study of the site that included a flora and fauna survey as well as a marine benthic survey in Stalley Bay, adjacent to the proposed property. The property for the proposed development is located on the eastern end of the island of St. Thomas in the United States Virgin Islands (USVI) along the southern shoreline. It lies south-southeast of the Bovoni landfill and southwest of the Mangrove Lagoon Wastewater Treatment Plant (Figures 1 and 2). The site is approximately 2.3 miles west of the city of Red Hook, 4 miles east of Charlotte Amalie, 6.4 miles east of Cyril E. King Airport and 4.8 miles south of Magens Bay. It is part of the Frenchman's watershed and gets most of its water from upland sheet runoff. The area is hilly and dry, with thin clay and bedrock that is exposed along the shore and ridgeline.

Between January 23 and February 10, 2024, a flora and fauna survey was conducted on the proposed site within the property boundaries. The survey was conducted on foot by two biologists, traversing the property on trails created by earth moving equipment from west to east along the approximate axis of the property. In addition, biologists bushwhacked and hiked along the southern coastline where trails had not been created, to capture primarily the coastal plant community. The surveyed routes were recording using an iPhone GPS in a hiking web application (https://www.gaiagps.com), and with a Garmin GPSMAP 79s (Figure 4). Three stations were chosen at which biologists sat quietly for 15-20 minutes to observe wildlife and listen for bird calls (Figure 4). Merlin, a Cornell University Ornithology Lab web application created to identify bird songs (https://merlin.allaboutbirds.org) was used throughout the terrestrial survey. Approximately eighteen hours were spent surveying the site, which covered approximately 30 acres.

On February 3, 2024, a marine benthic survey was conducted in and around Stalley Bay, south-southwest of the Bovoni proposed solar farm site. Biologists on snorkel gear swam the property shoreline out to approximately 100 m from land (Figure 3). This included an area of about 11,000 m². The benthic substrate was recorded and photographed, as were ecological marine communities. Endangered species or those of special concern were noted, mapped, and photographed.

The general terrestrial habitats were characterized and photographed and lists of plant species and vertebrate animals observed or detected were compiled. The marine habitat directly seaward of the

proposed development site was also characterized and photographed, with lists of plants, corals, macro-invertebrates and fish species compiled. A summary of survey findings and recommendations for sound ecologically conservative development is provided.




Figure 1. Location map with project location shown.




Figure 2. Map showing the location of the project site (yellow border) in relation to the Bovoni Landfill and Mangrove Lagoon Wastewater Treatment Plant.



Figure 3. The ecological survey area at 17 Remainder, Estate Bovoni. A survey was conducted across the site and seaward of the property approximately 100 m.




Figure 4. Survey routes and listening/viewing stations established during the study.

RESULTS AND DISCUSSION:

FLORA AND FAUNA SURVEY

The terrestrial habitats surveyed on the Bovoni 17 Remainder property included highly disturbed roadside vegetation, secondary dry scrubland, lowland dry forest and coastal thornbush. These habitat types occur on rapidly drained soils and on sites formally used for agriculture and/or grazing. Floristic diversity tends to be low in all of these habitat types, with generally low stature, a high density small trees, and a poorly developed herb layer. This is due to frequent drought conditions due to rapid runoff, low water storage in shallow soils, and high sunlight. Although there were general differences between habitat types, there was also considerable mixing of flora, and a very vague habitat delineation across the property. Below are the four vegetation groups with a general location on property for each and characteristic species shown.

Roadside Vegetation

The road running along the northwest side of the property divides it from the Bovoni landfill. The area is filled with a considerable amount of garbage and refuse, and the fenced shoulder is lined with opportunistic, sun and draught tolerant plants, primarily non-native species. Very fast growing exotic and invasive grasses, vines and small scrubs cover this zone. Catch and keep (*Acacia retusa*), Indian rubber vine (*Crypotostegia grandiflora*) and tan tan (*Leucaena leacocephala*) are dominant. Below are images of the vegetation found along the periphery of the Bovoni property.





Belly-ache bush Jatopha gossypiifolia



snake weed Stachytarpheta jamaicensis



catch and keep Acacia retusa



goatbush Castela erecta



Indian rubber vine Crypotostegia grandiflora



Egyptian sesban Sesbania sesban



cats claw Pithecellobium unquis-cati



American cotton Gossypium barbadense



tan tan Leucaena leacocephala




Secondary Dry Scrubland

Secondary dry scrubland covered the hill tops and crests on the Bovoni property. Secondary dry scrubland appears as a result of disturbance on dry forests and is characterized with very little leaf litter or soil remaining. Trees and scrubs generally do not exceed 8 m and are thorny. The herb layer is very poor or lacking. Many non-native or invasive specicies are present. Floristic diversity is extremely low. Plants very tolerant to low rainfall, drought and salt spray including legumes, cactus and bromiliads are common. The species indicative of this habitat found on the Bovoni property included tree cactus (Pilosocereus lanuginosus), jumbie pineapple (Tillandsia utriculate), tan tan (Leucaena leacocephala) and bromiliads (Neoregelia spp.). Below are common plants found in this habitat during the survey.









tan tan Leucaena leacocephala



sea torchwood Amyris elemenfera

Turk's cap

Melacactus intortus



jumbie pineapple Tillandsia utriculata



white frangipani
Plumeria alba





Bromiliads Neoregelia spp.

fiddlewood Citharexylum spinosum



Pigeon plum Coccoloba diversifolia



century plant
Agave americana

Lowland dry forest

Lowland dry forests are characterized by low stature, high density small and medium sized trees with a high density of stems for draught tolerance, a single layer canopy and a poorly developed herb layer. Floristic diversity is low and species include both non-native and native species. In fragmented areas like the Bovoni property, which occurs away from large tracts of dry forest, diversity has undoubtably been further lost with lack of seed dispersal. This habitat was found on the seaward facing slope of the property, where moisture and leaf litter was higher than on the hill crest, and less disturbance has been experienced. Dry deciduous trees dominated the zone. These included the tan tan (*Leucaena leucocephala*), gumbo limb (*Bursera simaruba*), water mampoo (*Pisonia subcordata*), tamerind (*Tamarindus indica*), and rattlebush (*Albizia lebbeck*). Below are common species found in this habitat.





Gumbo limbo

Bursera simaruba



water mampoo Pisonia subcordata



Tamerind

Tamarindus indica



Rattlebush Albizia lebbeck



wild frangipani Plumeria alba



cherry
Bourreria succulenta



pinguin Bromilia pinguin



arjuna Terminalia arjuna



tropical almond
Terminalia catappa



neem Azadirachta indica



Christmas bush Comocladia dodonaea



coco-plum Chrysobalanus icaco



Coastal plants

Along the coastline under the steep cliffs dropping to the sea, few plant species were found. All are salt water tolerent and resilient to high winds. These included some grasses, herbs and scrubs. The zone is dominated by buttonwood (Conocapus erectus), sea grape (Coccoloba uvifere) and tropical crabgrass (Digitaria ciliaris).



Table 1. lists all plants identified during the survey. Over 80 species in 35 families were identified, and several others were found but unidentifiable without seeds or flowers present. Many species were indicative of dry forests, scrubland, or disturbed areas of the US Virgin Islands, however some species occur in both moist and dry forest conditions. There was a mix of native, naturalized, exotic, and invasive species on the property.

Table 2. lists the vertebrate animals encountered during the survey. Several bird species were detected on Merlin but were not visually identified. One deer white tail deer (*Odocoileus virginianus*) was observed on the property (Figure 6), and several deer trails and footprints were found. Native anoles and lizards were seen on tree branches, trunks and leaves (Figire 6), and both mongoose and green iguanas were observed scampering across the boundary roads. Assorted spiders, moths, butterflies, bees and beetles were found. The high number of flowering trees, annuals and perennials

appeared to support many insects and hummingbirds. Termite nests were found in the larger trees and spiders webs hug webs across shrubs and grasses..

Table 1. A list of plant species observed during floral surveys from January 23 to February 11, 2024 at the proposed solar field development at Bovoni 17 Remainder, St. Thomas USVI.

Order	Family	Species	Common Name	Comments
Asparagales	Asparagaceae Orchidaceae	Agave americana Encyclia spp Oeceoclades maculata	century plant orchids monk orchid	naturalized native naturalized
Poales	Poaceae	Megathyrsus maximus Sporobolus virginicus Brachypodium sylvaticum Digitaria ciliaris Cynodon dactylon	Guinea grass marsh grass false broom grass Tropical crab grass Burmuda grass	invasive native non-native imvasive non-native
	Bromilliceae	Tillandsia utriculata Bromilia pinguin Neoregelia spp.	jumbie pineapple pinguin bromeliad species	native native
Malvales	Malvaceae	Thespecia populnea Gossypium barbadense Corchorus hirsutus Guazuma ulmifloria Wissadula hernandioides Abutilon indicum	beach maho American cotton jack switch West Indian elm yellow velvetleaf Indian abutilon	naturalized non-native native native native
Geraniales	Rutaceae	Amyris elemenfera Triphasia trifolia Guettarda krugii Amyris elemifera	sea torchwood sweet lime frogwood sea amyris	native native native
	Meliaceae	Azadirachta indica	neem	native
Rhoeadales	Caparaceae	Capparis cynophallophora Capparis flexuosa	Jamaican caper dog caper	native native
Caryophyllales	Caryophylladeae Petiveriaceae	Pisonia subcordata Rivina humilis Trichostima ochtandrum	water mampoo pigeonberry hoop vine	native non-native native
	Amaryllidacea Polygonaceae	Hymenocallis caribbaea Coccoloba uvifere Coccoloba diversifolia	white lily sea grape pigeon plum	native native native
Malpighiales	Euphorbiaceae	Hippomane mancinella Tragia volubilus Jatopha gossypiifolia Gymanthes lucida	manchineel stinging vine bellyache bush shiney oysterwood	native native native
	Salacaceae Malpighiaceae Crotoneae	Casearia guianensis Byrsonima lucida Croton flavens	wild coffee locustberry yellow balsum	native native native
		Croton astroites	wild marang	native

Table 1 cont. A list of plant species observed during floral surveys from January 23 to February 11, 2024 at the proposed solar field development at Bovoni 17 Remainder, St. Thomas USVI.

Order	Family	Species	Common Name	Comments
	Chrysobalanaceae	Chrysobalanus icaco	Coco-plum	native
Gentianles	Apocynaceae	Plumeria alba	white frangipani	native
V		Crypotostegia grandiflora	Indian rubber vine	naturalized
	Rubiaceae	Exostema caribaeum	princewood	native
	rasiaceae	Randia aculeata	inkberry	native
Solanales	Camoneae	Camonea umbellata	hogvine	non-native
	Cuscuteae	Cuscuta americana	dodler	invasive
Rosales	Fabaceae	Sesbania sesban	Egyptian susban	non-native
		Albizia lebbeck	rattle bush	naturalized
		Leucaena leacocephala	tan tan	invasive
		Acacia retusa	catch and keep	non-native
		Acacia fernisiana	sweet acacia	invasive
		Acacia tortuosa	casha	native
		Piscidia piscipula	Jamaican dogwood	native
		Haematoxylum campechannum	longwood casha	naturalized
		Pithecellobium unquis-cati	cats claw	native
		Tamarindus indica	tamerind	naturalized
Myrtales	Combretaceae	Conocapus erectus	buttonwood	native
		Bucida bucerus	gree gree	naturalized
		Terminalia catappa	tropical almond	native
		Terminalia arjuna	arjun	native
	Myrtaceae	Eugenia axillaris	white stopper	
Cactales	Cactaceae	Melacactus intortus	Turk's cap	native
		Pilosocereus lanuginosus	tree cactus	native
Celastrales	<u>Aquifoliaceae</u>	Ilex vomitoria	yaupon holly	non-native
Sapindales	Burseraceae	Bursera simaruba	gumbo limbo	native
	Anacardiaceae	Comocladia dodonaea	Christmas bush	native
	Simaroubaceae	Castela erecta	goat bush	non-native
	Sapindecae	Meliococcus bijugatus	genip	naturalized
Lamiales	Boraginaceae	Cordia sulcata	white manjack	native
		Cordia dichotoma	fragrant manjack	native
		Bourreria succulenta	cherry	native
	Bignoniaceae	Tecoma stans	Ginger Thomas	naturalized
	T7 1	Dolichandra unquis-cati	cats eye creeper	native
	Verbenaceae	Stachytarpheta jamaicensis	snake weed	native
		Citharexylum spinosum	fiddlewood	native
		Lantana involucrate	wild sage	native
Commelinales	Commelinaceae	Commelina erecta	widow's tears	native
Boragenales	Boraginaceae	Bourreria succulenta	Bahama strongbark	native

Table 2. A list of animal species observed during surveys from January 23 to February 11, 2024 at the proposed solar field development at Bovoni 17 Remainder, St. Thomas USVI.

Class	Family	Species	Common Name	Comments
Mammalia	Cervidae Herpestidae.	Odocoileus virginianus Urva auropunctata	whitetail deer small Indian mongoose	introduced, 1950's introduced 1970's
Aves	Trochilidae	Orthorhyncus cristatus	crested hummingbird	year round common
	Falconidae	Falco sparverius	American kestrel	year round, rare
	Emberizidae	Coereba flaveola	bananaquit	year round, common
	Tyrannidae	Tyrannus dominicensis	grey kingbird	year round,
	Columbidae	Columbina passerina	ground dove	common
		Passer domesticus	house sparrow	naturalized
		Setophaga petechia	yellow warbler	
		Gallus gallus	domesticated chicken	
Reptilia	Iguanidae	Iguana iguana	green iguana	naturalized
	Dactyloidae	Anolis cristatellus	crested anole	native, occaional
		Anolis stratulus	banded anole	native, occaional
		Anolis pulchellus	Puerta Rico anole	Native, occasional



banded anole Anolis stratulus

crested anole

Anolis cristatellus



St. Croix ground lizard *Pholidoscelis polops*

white tail deer
Odocoileus virginianus

Figure 5. Animals encountered on the Bovoni 17 Remaining property. Native anoles and lizards as well as the naturalized whitetail deer (*Odocoileus virginianus*). Many deer tracks were found on the property.




Figure 6. Nests and insects encounted during the survey on the Bovoni 17 Remaining property.

MARINE BENTHIC SURVEY Stalley Bay, St. Thomas USVI

The shoreline bordering the southwest edge of the Bovoni property is rugged and steep, with narrow beaches between rocky points. Beaches are made up of worn pebbles, various sized rocks and boulders, and small patches of course, brown sand (Figure 7). The shoreline immerges into a similar underwater benthic habitat of terrigenous rocks, pebbles and boulders, with occasional small patches and channels of course unconsolidated light sand (Figure 8). This benthic habitat type extends across the survey area along the coast, and out beyond the 100 m boundary, dropping in depth from 0 to 15 feet. Offshore of the the rocky points defining the small bays along the coastline, large boulders are either emergent or lay slightly below the surface of the water (Figures 9). These boulders and rocks grow a variety of turf, macro and calcareous algae (Table 3, Figures 10), which provides food and habitat for macro-invertebrates and fishes. Schools of herbaceous fishes, as well as various sea urchins and other macro-invertebrates were found grazing on the site (Figures 11 and 12). Wrasses and small damselfish darted around the shallow rocks and crevices.

The benthos surveyed in and around Stalley Bay constituted only one habitat type. This was the rocky, macro-algae dominated ecosystem described. Consolidated limestone reef was absent. A few small opportunistic coral species colonized the terrigenous hardbottom (Table 5, Figure 13) but density was low of these species. Sponges and gorgonian corals were also observed at low densities. In the center of the bay, slightly beyond the survey area, small patches of native manatee grass (*Syringodium filiforme*) mixed with turtle grass (*Thalassa testudium*) and marine algae were observed (Figure 14). These supported milk conch (*Macrostrombus costatus*) and bar jacks (*Caranx ruber*) searching for food in the seagrass habitat.

On the rocky points defining the edges of the bay, numerous colonies of staghorn coral (*Acropora palmata*) were found colonizing the rocks and boulders (Figure 15). Over 56 colonies were counted within the survey area, both fragments and large, established colonies. There was evidence of some disease and recent mortality on the Acroporids off the point in the western end of the survey area. Three colonies of fused elkhorn coral (*A. prolifera*) were also found on the eastern point. The areas of high density fused staghorn and elkhorn are shown in Figure 16.



Figure 7. The rocky coastline along the proposed development site is covered in terrigenous rocks of various sizes, worn pebbles, and sparse areas of sand.



Figure 8. The underwater benthos is covered in terrigenous rocks and boulders, with occasional patches of course, light sand.



Figure 9. Emergent and barely submerged rocks and boulders define the outer edges of the small bays surveyed.



Figures 10. A variety of macro-algae cover the rocks and boulders. The brown algae *Sargassum spp.*, *Turbinaria turbinata* and *Dictyota spp.* grow in thick mats over much of the site.



Figures 11. Herbaceous fishes like blue tang (*Acanthurus coeruleus*) and ocean surgeonfish (*A. bahianus*) grazed the algae covered rocks and boulders.



Figure 12. Rock boring sea urchins (*Echinometra lucunter*), West Indian top shell (*Cittarium pica*) and West Indian sea eggs (*Tripneustes ventricosus*) grazed on the turf and calcareous algae growing on the rocks and boulders.



Figure 13. Fire coral (*Milipora spp.*) and small oportunistic stony corals like finger coral (*Porites porites*) and mustard hill coral (*P. asteroides*) colonized the site. A small number of brain coral colonies (*Pseudodiploria strigosa* and *P. clivosa*) were observed colonizing the terrigeous boulders. Most corals were at very low densities.



Figute 14. A small grass bed offshore of the survey area supported small fish and larger predatory jacks (*Caranx ruber*)



Figures 15. Elkhorn (*Acropora palmata*) and fused staghorn (*A. prolifera*) corals were found on the rocky outcroppings at both the east and west side of the survey area. Colonies were found at many sizes and both healthy and diseased/recently dead were observed.



Figure 16. Areas of elkhorn coral (A. palmata) colonization. Stars represent where 5 or more cononies were found.

Table 3-6 list the plants and animals recorded during the survey off the Bovoni proposed project site. Although with the exception of staghorn, coral was nearly absent on the site, over 30 macro-invertebrates and 55 fish species were recorded, including one nurse shark (*Ginglymostoma cirratum*) and one red lionfish (*Pterios volitans*). Most of the fish encountered were small species like wrasses and damselfish, or larger fish in juvenile stage. This is as would be expected in the shallow nearshore water. Species of commercial value found included juvenile Caribbean spiny lobsters (*Panulirus argus*), West Indian top shell (whelks, *Cittarium pica*), juvenile yellowtail snapper (*Ocyurus chrysurus*), and several grunt, jack and parrotfish species. One green turtle was observed moving rapidly through the survey area.

Table 3. Marine algae observed during a three hour survey in Stalley Bay on February 4, 2024.

Phylum	Family	Species	Common Name
Chlorophyta	Caulerpaceae	Caulerpa mexicana	green grape alga sp.
green algae		Caulerpa racemosa	green grape alga sp.
		Caulerpa sertulariodes	green feather alga
		Caulerpa taxifolia	
	Dasycladaceae	Neomeris annulata	fuzzy tip alga
	Halimedaceae	Halimeda tuna	
		Halimeda discoidea	watercress alga
		Halimeda opuntia	
	Udoteaceae	Penicillus pyriformis	
		Udotea occidentalis	mermaids fan sp.
		Udotea flabellum	mermaids fan sp.
	Valoniaceae	Ventricaria ventricosa	sea pearl
Phaeophyta	Dictyotaceae	Dictyota caribaea	y branched alga sp.
brown algae	·	Dictyota divaricata	y branched alga sp.
J		Dictyopteris delicatula	,
		Padina spp.	leafy rolled-blade alga
		Turbinaria turbinata	·
		Sargassum hystrix	sargassum seaweed
Rhodophyta	Galaxauraceae	Galaxaura oblongata	tubular thicket alga
red algae		Galaxaura rugosa	tubular thicket alga
	Rhodomelaceae	Wrightiella blodgettii	_
	Corallinaceae	Jania adherens	pink segmented alga
Cyanophyta	Oscillatoriaceae	Schizothrix calcicola	red filamentous alga
Tracheophyta	<u>Cymodoceaceae</u>	Syringodium filiforme	manatee sea grass
sea grass		Thalassia testudinum	turtle grass

Table 4. Stony corals observed during a three hour survey in Stalley Bay on February 4, 2024.

Family	Species	Common Name	Endangered
Acroporidae	Acropora prolifera	fused staghorn coral	*
_	Acropora palmata	elkhorn coral	*
Agariciidae	Agaricea agaricites	lettuce coral	
Faviidae	Favia fragum	golfball coral	
	Orbicella faveolata	boulder star coral	*
	Pseudodiplora strigosa	symmetrical brain coral	
	Pseudodiplora clivosa	knobby brain coral	
Poritidae	Porites asteroides	mustard hill coral	
	Porites porites	finger coral	
Milleporidae	Millepora alcicornis	branching fire coral	
•	Millepora complanata	blade fire coral	
Siderastreidae	Siderastrea siderea	starlet coral	
	Siderastrea radians	lesser starlet coral	

Table 5. Marine macro-invertebrates observed during a three hour survey in Stalley Bay on February 4, 2024.

Phylum	Species	rree nour survey in Stalley Bay on February 4, 2024. Common Name
A 1' 1		
Annelida	Spirobranchus giganteus	Christmas tree worm
	Anamobaea orstedii	split crown feather duster worm
	Bispira brunnea	social feather duster worm
Arthropoda	Periclimenes pedersoni	pederson shrimp
	Panulirus argus	Caribbean spiny lobster
	Stenocionops furcatus	furcate spider crab
Cnidaria	Bartholomea annulata	corkscrew anemone
	Condylactis gigantea	giant anemone
Echinodermata	Ophiocoma echinata	blunt-spined brittle star
	Tripneustes ventricosus	West Indian sea egg
	Diadema antillarum	long-spined urchin
	Eucidaris tribuloides	pencil urchin
	Echinometra lucunter	rock boring urchin
Porifera	Amphimedon compressa	erect rope sponge
	Ircinia strobilina	black-ball sponge
	Holopsamma helwigi	lumpy overgrowing sponge
	Pseudosquilla ciliate	ciliated false squilla
Mollusca	Macrostrombus costatus	milk conch
	Lithopoma tectum	West Indian starsnail
	Cerithium litteratum	stocky cerith
	Chicoreus brevifrons	West Indian murex
	Cittarium pica	West Indian top shell

Table 6. Fish observed during a three hour survey in Stalley Bay on February 4, 2024.

Family	Species	Common Name	Relative abundance
Acanthuridae	Acanthurus coeruleus	blue tang	common
	Acanthurus bahianus	ocean surgeonfish	common
	Acanthurus chirugus	doctorfish	common
Belonidae	Ablennes hians	flat needlefish	rare
Blennidae	Ophioblennius macclurei	redlip blenny	rare
	Malacoctenus triangulatus	saddled blenny	common
	Malacoctenus macropus	rosy blenny	rare
Carangidae	Caranx ruber	bar jack	common
J	Caranx bartholomew	yellow jack	common
Gerreidae	Gerres cinereus	yellowfin mojarra	common
Grammatidae	Gramma loreto	fairy basslet	common very
Gobiidae	Coryphopterus hyalinus	glass goby	common
Haemulon	Haemulon flavolineatum	French grunt	common
	Haemulon aurolineatum	tomtate	occasional
	Haemulon sciurus	stripped grunt	rare
Holocentridae	Holocentrus adscensionis	squirrelfish	occasional
	Holocentrus rufus	longspine squirrelfish	occasional
	Myripristis jacobus	blackbar soldierfish	occasional
Labridae	Halichoeres radiatus	puddingwife	occasional
	Halichoeres bivittatus	slippery dick	common
	Halichoeres garnoti	yellowhead wrasse	common
	Halichoeres maculapinnae	clown wrasse	common
	Thalasoma bifasciatum	bluehead wrasse	common
Lutjanidae	Lutjanus apodus	schoolmaster snapper	rare
	Lutjanus synagris	lane snapper	rare
	Ocyurus chrysurus	yellowtail snapper	occasional
Mullidae	Mulloidichthys martinicus	yellow goatfish	occasional
	Pseudopeneus maculatus	spotted goatfish	occasional
Pomocentridae	Stegastes partitus	bicolor damselfish	common
	Stegastes leucostictus	beaugregory	common
	Stegastes adustus	dusky damselfish	common
	Stegastes variabilis	cocoa damselfish	common
	Stegastes planifrons	3-spot damselfish	common
	Abudefduf saxatillis	sergeant major	common

Table 6 cont. Fish observed during a three hour survey in Stalley Bay on February 4, 2024

Family	Species	Common Name	Number
Scaridae	Sparisoma viride	stoplight parrotfish	occasional
	Sparisoma aurofrenatum	redband parrotfish	occasional
	Sparisoma chrysopterum	redtail parrotfish	occasional
	Sparisoma rubripannae	yellowtail parrotfish	occasional
	Sparisoma radians	bucktooth parrotfish	common
	Scarus iserti	striped parrotfish	common
	Scarus vetula	queen parrotfish	occasional
	Scarus taeniopterus	princess parrotfish	
Scorpaenidae	Pterios volitans	red lionfish	one
Serranidae	Hypoplectrus nigricans	black hamlet	rare
	Hypoplectrus unicolor	butter hamlet	rare
	Hypoplectus puella	barred hamlet	rare
	Serranus tigrinus	harlequin bass	rare
	Serranus tabacarius	tobaccofish	rare
	Cephalopholis cruentatus	graysby	rare
Sphyreanidae	Sphyrna barracuda	great barracuda	one
Tetraodontidae	Canthigaster rostrata	sharpnose puffer	occasional
	Diodon hystix	porcupinefish	rare
	Sphoeroides testudineus	checkered puffer	one
Chondrichthyes			
<u>Ginglymostomatidae</u>	Ginglymostoma cirratum	nurse shark	one




Figure 17. A variety of macro-invertebrates were found in Stalley Bay. Commercially important species included the Caribbean spiney lobster (*Panularus argus*) and West Indian top shell (*Cittarium pica*).



Figure 18. A wide variety of fishes were found in Stalley bay off the proposed development site. Most were small wrasses and damselfish species but snapper, grunts, parrotfish and jacks were also fairly abundant in deeper water under and around rocks and ledges.

PROTECTED SPECIES

Federally protected tree boas (*Chilabothrus granti*) were not found on the Bovoni property site however the conditions found there fall well within their habitat preference (i.e. rocky shallow soil with dense dry vegetation), and the area is within their distribution range. Since they are largely nocturnal, there is a reasonable chance that they inhabit the property but were not detected during daytime surveys. Federally protected elkhorn and staghorn (*Acropora spp.*), coral colonies were present within the study area, colonizing the rocky bottom and boulders seaward of the coastal points of land. One star coral (*Orbicella faveolata*), also federally protected, was found within the survey area. All other coral species found within Stalley Bay were opportunistic corals or brain corals growing on the submerged rocky substrate. Manatee and turtle grass was present outside of the survey area but was very sparse inside the bay. One green sea turtle (*Chelonia mydas*) as observed. Hawksbill turtles were not seen.





SIGNIFICANCE OF RESULTS and RECOMMENDATIONS

Although the property at Bovoni 17 Remainer is a garbage strewn, ecologically fragmented, highly disturbed property with harsh environmental conditions, little remaining topsoil, seasonal draught, and exposure to regular heavy winds and salt spray, it retains plant and animal species that are native to dry forests of the US Virgin Islands and exist in an apparently resilient cycle of life. Destruction of the natural communities and attributes of the property for the solar farm development should not be taken lightly, but instead with respect and with the aim of conserving the natural resources that can be conserved. In particular, care should be taken to protect the endangered species including the tree boa if present, and the *Acropora* corals in Stalley Bay.

- Best conservation practices should be employed when clearing and developing the site. Tree
 boas should be closely watched for by equipment operators, surveyors and all workers, and
 DPNR should be notified if one is seen so that it can be removed and relocated.
- Sediment control with the use of silt curtains along the steep hillside is recommended.
 Immediate grass planting or the use of soil covering material is highly recommended to prevent runoff and sedimentation of Stalley Bay.



Attachment E – Archeological Study



PHASE I (A&B) ARCHAEOLOGICAL SURVEY 30.5 ACRES, PARCEL 17 REM. ESTATE BOVONI, ST. THOMAS US VIRGIN ISLANDS

Prepared for:

Mr. Christian Loranger Quantum Solar LLC PO Box 6347 St Thomas, US Virgin Islands 00804

CocoSol International Inc. Project 230927

Prepared by:

CocoSol International Inc. 777 Brickell Ave #500-97996 Miami, Florida 33131

May 13, 2024

TABLE OF CONTENTS

 1.1 Proposed Project	
9	3
1.3 Environmental Setting	
2.0 2.7. Oldinoron Souring	3
2.0 SURVEY METHODS	7
2.1 Literature and Records Review	
2.2 Field Survey	
3.0 FINDINGS	
3.1 Literature and Records Search	
3.1.1 Precolonial Cultural Setting	
3.1.2 Colonial Cultural Setting	
3.2 Field Survey	
4.0 CONCLUSIONS AND RECOMMENDATIONS	
5.0 REFERENCES	
TABLE OF FIGURES	
Figure 1: Google Earth image depicting the location of the survey area	1
Figure 2: Topographic map of !7 Rem., Estate Bovoni	
Figure 3: Map depicting the proposed solar panel array.	
Figure 4: Photograph depicting the vegetation and immediate environment of the subject property to the southeast.	
Figure 5: Photograph of the characteristic northwestern slopes of the subject property	
Figure 6: NRCS soil map depicting the extent and location of the Southgate-Rock complex. Source	:
complexhttps://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx	
rigure 7. I notograph of the summit of the easiern most knott	
	0
Figure 8: Photograph of characteristic ground surface contexts with exposed gravelly loam	8
Figure 8: Photograph of characteristic ground surface contexts with exposed gravelly loam	8

1.0 INTRODUCTION

CocoSol International Inc. (CocoSol) performed a Phase I (A&B) Cultural Resources Survey (Survey) for approximately 30.5 acres of land located on 17 Rem., Estate Bovoni, St. Thomas, U.S Virgin Islands (Figures 1 and 2). The Survey was performed on behalf of Quantum Solar LLC of St. John, USVI.



Figure 1: Google Earth image depicting the location of the survey area.




Figure 2: Topographic map of !7 Rem., Estate Bovoni

1.1 Proposed Project

Quantum proposes to construct a solar photovoltaic panel array on the subject property as shown in Figure 3. The installation of the panels will include the clearing of the land by mulching, access road construction, and other limited earth change activities. The panels frames will be anchored with screws to depths of approximately 2.5 meters below the existing ground surface.




Figure 3: Map depicting the proposed solar panel array.

1.2 Regulatory Framework

Because of the earth change activities required to develop the subject property, the project is required to comply with Title 29, Chapter 17, Section 959, of the Virgin Islands Code, also known as the Virgin Islands Antiquities and Cultural Properties Act. Because of federal permitting for the project, it is also required to comply with Section 106 of the National Historic Preservation Act of 1966, as amended.

1.3 Environmental Setting

The subject property is in the southeastern part of St. Thomas on a peninsula overlooking the Caribbean Sea. The topography of the subject property consists of a narrow ridge top with steeply sloping side slopes ranging from 40 to 90 percent slope gradient. Three knolls (Figure 2) are the highest elevations of the ridge, these are narrow and less sloping, the center knoll is the less sloping area of the subject property, the highest elevation is on the eastern knoll. The vegetation consists of secondary growth of pioneer species such as tan-tan, caccia, various bromeliads and cacti. Figures 4 and 5 depict the site conditions described above.

An abandoned, and until recently overgrown road, was identified in the northeast part of the ridge. The road was cut on the ridge shoulder (Figure 2). Barbed wire was observed throughout the property, indicating that the subject property was used to graze cattle.

The soil on the subject property is defined by the United States Department of Agriculture: National Resource Conservation Service as belonging to the Southgate-Rock complex (SRE, SRF, and SRG). These soils are characterized as containing thin (< 15 centimeters) gravelly to very gravelly loam topsoil that are underlain by weathered rock. The existing conditions found throughout the subject property indicate that extensive erosion has deflated the soil column leaving exposed on surface very gravelly loam or the weathered rock, Figures 6 to 8 provide the soil map for the subject property and the ground surface and soil characteristics.



Figure 4: Photograph depicting the vegetation and immediate environment of the subject property, view to the southeast.



Figure 5: Photograph of the characteristic northwestern slopes of the subject property



Figure 6: NRCS soil map depicting the extent and location of the Southgate-Rock complex. Source: complexhttps://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx



Figure 7: Photograph of the summit of the eastern most knoll




Figure 8: Photograph of characteristic ground surface contexts with exposed gravelly loam.

2.0 SURVEY METHODS

The methods employed during the Survey are presented below.

2.1 Literature and Records Review

The literature and records review include the following:

- Review of the archaeological site files through consultation with the VISHPO
- Review of historic and modern cartographic sources
- Review of readily available published and unpublished literature

The findings obtained during the literature and records search are presented in Section 3.0 of this report.

2.2 Field Survey

The less steep and narrow lands of the ridge summit were shovel tested along a single transect established along the spine of the ridge with shovel tests performed at 30-meter intervals, where soil was present. The shovel tests measured approximately 30 centimeters in diameter and were excavated to depths no longer considered to have the potential of containing non-random artifact bearing matrices.

Generally, the shovel tests were extended to between 4 and 10 centimeters below ground surface, the depths at which the artifactually sterile, weathered rock substrata were encountered. The soil from each shovel test was screened through ¼ inch hardware cloth to recover artifacts, if any.

As the survey team walked from test location to the next, careful observation of the ground surface was made to identify cultural materials in surface contexts, if any. Figures 9 and 10 depict the field survey activities and an example shovel test.



Figure 9: Photograph of typical survey transect



Figure 10: Photograph of example shovel test depicting the thin gravely loam that is underlain by weathered rock

3.0 FINDINGS

The findings for the literature and records search, and field survey are presented below.

3.1 Literature and Records Search

The literature and records review performed did not identify potentially significant cultural resources within the survey areas. The VISHPO informed us that no cultural resources of record were listed in the archaeological site files or the VI Registry for the subject property. The VISHPO did provide information for archaeological studies and sites of record for the Bovoni Peninsula. The information provided by the VISHPO includes multiple sites to the northwest of the subject property that include the Bovoni plantation settlement, a lime kiln, a cemetery, and an indigo works.

Several colonial sites have been identified in the vicinity but are outside of the subject property. David Knight performed a reconnaissance survey of 66 acres on Plots 18-I, 18-J, 18-K and 18-M (2006) and identified several constructed colonial features and scatters of historic artifacts. Knight did not encounter pre-colonial materials, though it should be noted that he did not perform subsurface testing.

Ms. Kourtney Donohue performed a Phase I Archaeological Survey for Plots 16 and 17E (2015) during which she identified the remains of the Bovoni Plantation site that was dedicated to cotton and sugar canebased agriculture, with production from the late 18th to the approximate mid 19th century. Donohue recommended a Phase II Archaeological Testing and Evaluation Study to assess whether the site met criteria of eligibility to the National Register of Historic Places (NRHP). Subsequently, the University of Alabama performed the Phase II study and determined that the archaeological contexts did not meet criteria of eligibility to the NRHP because of extensive disturbances to the site and as such, the site lacked contextual integrity, although preservation of the remains of constructed features was recommended.

3.1.1 Precolonial Cultural Setting

The U.S. Virgin Islands (USVI) contains a rich milieu of cultural resources that offer testimony to over three thousand years of human experience. These cultural resources range from habitation sites established during the Archaic Period at Krum Bay and the Magens Bay Arboretum Complex on St. Thomas approximately three thousand years ago, to the multiple village and farmstead sites on all the islands, to chiefly ceremonial centers such as the Salt River Site on St. Croix, which is the site of the first encounter between the Taino and Europeans.

After the Archaic Period, the indigenous people of the Virgin Islands participated in a geographically vast network of social and economic relationships as evidenced by shared stylistic attributes of ceramics from the Saladoid, Ostionan and Chican culture periods across a significant part of the Antilles. Shared cosmological ideas are also evidenced by the presence of cemis and other religious paraphernalia in the Virgin Islands and across large areas of the Caribbean Archipelago.

Recent archaeological research indicates that the insular landscapes were dotted with small and large villages along the coastal section fringes of the islands as well as the uplands. Additionally, small settlements herein characterized as farmsteads are now being discovered in the uplands. These small upland farmsteads have mostly been unrecognized in the archaeological record; however, recent archaeological surveys for large development projects have resulted in the identification of such sites.

Long distance trade is evidenced by the presence of jadeite artifacts manufactured from raw lithic sources found in Central America and chert from Puerto Rico and down island. A whole host of cultigens with origins in the continent became part of the quotidian diet; more exotic items such as guinea pig, an Andean

domesticate, have been found in Puerto Rico and are likely be documented by future archaeological studies as also present in Virgin Island archaeological contexts.

3.1.2 Colonial Cultural Setting

Following the brief European incursion on St. Croix in 1493, the islands became the possession of several European nations including Spain, England, Malta, the Netherlands, and France. The colonies that these nations attempted to establish largely failed. Not until Denmark's Danish West Indies Company settled in St. Thomas in 1672 and on St. John in 1694, did these colonies become viable enterprises. The Danes purchased St. Croix from the French in 1733 and the island, with its larger size, gentler topography, fertile soils, and surface streams, became a dynamic sugarcane-based enterprise that lasted for a century.

The Danes divided the islands into estates that were largely dedicated to agriculture. Although largely owned by Danes, British managers often administered the estates. The early plantations, particularly on St. Thomas and St. John were primarily dedicated to the production of cotton and indigo, but because of competition from the continent, particularly the southern United States, these two agricultural pursuits were largely abandoned in favor of sugar cane. The economies of St. Croix and St. John were primarily based on sugar cane agriculture and the production of muscovado sugar and rum. In contrast, the economy of St. Thomas was primarily based on trade, although agricultural pursuits also formed an integral part of its economy.

3.1.3 Estate Bovoni

Throughout its Danish colonial history, Estate Bovoni was generally known as plantation 1 and 2 in the Frenchman Bay Quarter (Franskmand Bay Quarter) and/or as Dværgsteen and Emanuel. Over the course of the Danish colonial period the lands changed hands more than twenty-five times (University of Alabama: 2016:12). As with most St. Thomas plantations, the Bovoni enterprise engaged in cotton and sugar cane agriculture well into the 19th-century. Following the virtual demise of cotton and then sugar cane agriculture, these lands reverted to bush and grazing fields in the late 19th and 20th centuries.

The early historic cartographic sources do not provide sufficient detail to discern the presence of settlements within the subject property. Significantly more accurate, the 1839 Hornbeck map of St. Thomas (Figure 11) depicts the Bovoni peninsula as devoid of structures or settlements. Modern cartographic sources such as the 1922 US Coastal Geodetic Map for St. Thomas, the 1952 and 1982 USGS maps for Eastern St. Thomas do not depict structures or settlements located within the subject property.




Figure 11: Segment of the 1839 Hornebeck map depicting the location of the subject property (red arrow). Source map: www5.kb.dk/maps/kortsa/2012/jul/kortatlas/object65501/da/

3.2 Field Survey

No cultural resources were identified during the field survey performed for the subject property. The subject property was found to be extensively disturbed, as evidenced by exposed subsoil and parent rock material in ground surface contexts (Figures 8 and 10).

4.0 CONCLUSIONS AND RECOMMENDATIONS

Our concluding remarks and recommendations are presented below.

4.1 Conclusions

No cultural resources were identified during the Phase I (A&B) Cultural Resources Survey performed for 17 Rem., Estate Bovoni, St. Thomas USVI. The subject property has been extensively disturbed by nearly two centuries of agriculture, and later as grazing fields for cattle as indicated by the barbed wire fencing over a significant part of subject property. As noted in Section 3.0, we found the soils to have been deflated leaving only a few centimeters of the very gravelly subsoil exposed or completely absent leaving the weathered rock parent material exposed on the surface. Other disturbance noted include a cut road on the northeast part of the ridge and push-piles from past (20th century) clearing activities using heavy equipment.

No precolonial or colonial artifacts or shell fragments were found in surface contexts, which are often found scattered at disturbed archaeological sites. The topographic variables such as the very narrow ridge top and steep side slopes and nearly vertical cliffs to the ocean have likely rendered the subject property an unattractive settlement location. We note that the sites of record in the peninsula are contained in more level lands with better access to the sea.

4.2 Recommendations

CocoSol recommends that the Virgin Islands State Historic Preservation Office issue a finding of no objection to the construction of the proposed photovoltaic panel array. If cultural resources are encountered during clearing and/or construction activities, we recommend suspension of the work in the area of concern and that the Virgin Islands State Historic Preservation Office is immediately notified.

5.0 REFERENCES

Donohue, Kourtney 2015 Phase I, Cultural Resource Survey: Estate Bovoni, Parcels 16 & 17 E, Frenchman's Bay Quarter, St. Thomas, USVI. Report submitted to Dry Marina, St. Thomas by Kourtney Donohue, St. John, U.S. Virgin Islands.

Knight, David

2006 A Preliminary Assessment of Cultural Resources Within Parcels 18-1, 18-J, 18-K, and 18-M, Estate Bovoni, #1 & #2 Frenchman's Bay Quarter, St. Thomas, USVI. Report submitted to Boyd Holding USVI by David Knight and the Virgin Islands Historical and Genealogical Resource Center (VIHGRC) of St. Thomas, U.S. Virgin Islands.

Persons, Brooke

2015 Phase II Archaeological Testing and Evaluation At The Bovoni Estate Site at Plots 17-E And 16, Estate Bovoni, Frenchman's Quarter, St. Thomas, U.S. Virgin Islands. The University of Alabama, Tuscaloosa.

13


Attachment F - Driveway Permit Application and Plans





DRIVEWAY PERMIT APPLICATION

DATE	
OWNER INFORMATION Name	Telephone
Email Address	
Parcel(s)No./Address	
DRIVEW	AY PERMIT FEES
COMMERCIAL \$35 + IMPACT FEE IMPACT FEE UP TO 3000 SQ. FT. \$450 OVER 3000 SQ. FT. \$650 ACCEPTED N	*The IMPACT FEE is a one-time cost assessed to commercial permits, to offset the latent effects on the island's infrastructure.
Bank/Cashier's Check,	Money Order, Cash, Credit Card
DESIGNER INFORMATION Name	Email Address
Telephone Reg	istration No
Driveway Width20 ft.	Swale Width N/A ft.
Driveway Length225 ft.	Swale Depth N/A ft
Grade of proposed Road/Driveway at intersection of Public Road and/or highw	norcont/Indicate plus or minus slope †/-
Along intersection of Culvert	Invert Depthft., WFt. & L
Please submit four (4) copies of map showing	g: site plan, location map and detailed driveway drawings.
	TMENTAL USE ONLY
☐ Permit Approved ☐ Permit Disapprov	red Permit #
Date Issued	_ Expiration
Total Amount Due	Permit Fees Collected
Attachments: □ Drawings Sample	es Construction Specifications
Commissioner	_



ACCESS DRIVEWAY SITE PLAN

BOVONI 17 REMAINDER ESTATE BOVONI, SAINT THOMAS, VI 00804

STB SOLAR, LLC
A VIELECTRON, LLC COMPANY




95 E. Mitchell Hammock Road Suite 200 Oviedo, FL 32765 (407) 380-1919 www.hoyletanner.com DATE: 10/21/2025

SCALE:

FIGURE:


1"=60'

D1



DRIVEWAY NOTES:

- 1. THE CONTRACTOR SHALL SUBMIT A SAMPLE OF THE PROPOSED CRUSHED GRAVEL FOR REVIEW AND APPROVAL BY THE DESIGN ENGINEER PRIOR TO THE START OF ROADWAY CONSTRUCTION.
- 2. THE PROFILE OF THE ROAD SHALL FOLLOW THE EXISTING TERRAIN TO THE GREATEST EXTENT POSSIBLE.
- 3. THE DRY DENSITY AFTER COMPACTION SHALL NOT BE LESS THAN 95% OF THE STANDARD PROCTOR TEST AND DONE IN ACCORDANCE WITH THE REQUIREMENTS OF ASTM D698.



 $\binom{1}{D2}$

TYPICAL ACCESS DRIVEWAY SECTION

SCALE: NONE

ACCESS DRIVEWAY DETAILS

BOVONI 17 REMAINDER ESTATE BOVONI, SAINT THOMAS, VI 00804

STB SOLAR, LLC
A VIELECTRON, LLC COMPANY



95 E. Mitchell Hammock Road Suite 200 Oviedo, FL 32765 (407) 380-1919 www.hoyletanner.com DATE: 10/21/2025

SCALE: FIGURE:

N.T.S.

D2

Attachment G – Site and Erosion Control Plans



SITE DEVELOPMENT PLANS

FOR A

PROPOSED SOLAR ENERGY FACILITY WITH BATTERY STORAGE 10.725 MWdc (10.000 MWac)

BOVONI 17 REMAINDER ESTATE BOVONI SAINT THOMAS, VI 00804

OCTOBER 30, 2025

PROPERTY OWNER

STB SOLAR LLC (A VIELECTRON LLC COMPANY) 5000 EST. ENIGHED, STE 4A, PMB 14 SAINT JOHN, VI 00830

PROPERTY INFORMATION

PROPERTY ID: 109402010100 OLG MAP NUMBER: A9-553-T000 AREA: 30.95± ACRES DPNR ZONE: C COMMERCIAL ZONE


APPROVALS

PERMIT	NUMBER	DATE
DPNR PARTIAL LAND CLEARING (TRANSECTS)	N/A	12/1/23
DPNR FULL LAND CLEARING	TBD	//25
DPNR MAJOR CZM PERMIT	TBD	//25
DPNR DRIVEWAY PERMIT	TBD	//25
DPNR FLOOD PERMIT	TBD	//25
DPNR BUILDING PERMIT	TBD	//25
DPNR ELECTRICAL PERMIT	TBD	//25

LIST OF DRAWINGS

DWG # SHEET# DWG NAME

C1	1	COVER SHEET
C2	2	EXISTING CONDITIONS PLAN
C3	3	SITE PREP / EROSION CONTROL PLAN
C4	4	SITE LAYOUT PLAN
C5	5	GRADING & DRAINAGE PLAN
C6	6	SITE SECTIONS
C7	7	EROSION CONTROL NOTES & DETAILS
C8	8	CONSTRUCTION DETAILS 1
C9	9	CONSTRUCTION DETAILS 2



APPLICANT

STB SOLAR LLC

A VIELECTRON LLC COMPANY 5000 EST. ENIGHED, STE 4A, PMB 146 SAINT JOHN, VI 00830

ISSUED FOR PERMITTING

SYSTEM DESCRIPTION

MODULE: FIRST SOLAR SERIES 6 465W TOTAL MODULES: 23,064

RACKING: 10° TILT & 20° TILT, 2MIP ROW SPACING: 2'-0" (TYP) CLEARANCE

5'-0" AND 8'-0" WHERE NECESSARY

PROJECT TEAM

CIVIL ENGINEER / PERMITTING CONSULTANT

HOYLE, TANNER & ASSOCIATES, INC. 95 E. MITCHELL HAMMOCK RD, STE 200 OVIEDO, FL 32765 ATTN: BILL DAVIDSON, PE (603) 501-8541

ELECTRICAL ENGINEER

PURE POWER ENGINEERING, INC. 111 RIVER STREET, SUITE 1110 HOBOKEN, NJ 07030 ATTN: ELIZA HARTFORD (551) 220-2790

SURVEYOR

MARVIN BERNING & ASSOCIATES 6501 RED HOOK PLAZA, SUITE 201 SAINT THOMAS, VI 00802 ATTN: HARRY GAURILOFF, RLS (340) 775-6557

RACKING PROVIDER

POLAR RACKING, INC. 6889 REXWOOD ROAD, UNIT #5 MISSISSAUGA, ONTARIO L4V 1R2, CA ATTN: ADRIAN MAROLLY (514) 250-7788

GLINT AND GLARE STUDY

DARE STRATEGIES, LLC 2248 ROSE HALL DRIVE VIRGINIA BEACH, VA 23454 ATTN: DAVE BELOTE (703) 822-1965

CULTURAL RESOURCE SURVEY

COCOSOL INTERNATIONAL, INC. 777 BRICKELL AVENUE, #500-97996 MIAMI, FL 33131 ATTN: CARLOS SOLIS (305) 518-7236

BIOLOGICAL SURVEY

KADISON ISLANDS CONSULTING, LLC P.O. BOX 305124 SAINT THOMAS, VI 00803 ATTN: ELIZABETH KADISON

PHASE 1 ESA

CARITECH GROUP, INC. 125 COTTON VALLEY; P.O. BOX 5018 KINGSHILL, SAINT CROIX, VI 00851 ATTN: ERIC DOUGLAS, MSC, PE (340) 690-9533

PROJECT DEVELOPER

STB SOLAR LLC 5000 EST ENIGHED, STE 4A, PMB 146 SAINT JOHN, VI 00830 ATTN: CHRISTIAN LORANGER (508) 965-8637 WILLIAM DAVIDSON

O=19494-1B

IVARGIN ISLANDS

SHALL REMAIN THE PROPERTY OF HOYLE, TANNER. IT MAY NOT BE USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS PROJECT, WITHOUT THE WRITTEN PERMISSION OF HOYLE, TANNER.

Suite 200 Oviedo, FL 32765 (407) 380-1919 www.hoyletanner.com

HOYLE

EST. ENIGHED, STA 4A, PMB 146
SAINT JOHN, VI 00830

SED SOLAR ENERGY FACILITY
BOVONI 17 REMAINDER
FSTATE BOVONI

SAINT SAINT

<u></u> <u></u>

COVER SHEET

ECT NO. 23.141001.

PROJECT NO. 23.141001.00

SHEET 1 OF 9



SAINT THOMAS, VI 00804

FRONT YARD = N/A

SIDE SETBACK = N/AREAR SETBACK = N/A

BUILDING HEIGHT = 35 FEET

1,348,229± SF / 30.951± ACRES

MINIMUM LOT SIZE = 5,000 SQ. FT.

109402010100

3. PROPERTY ID:

PARCEL AREA:

4. OLG MAP NUMBER: A9-553-T000

5. ZONING DISTRICT: C COMMERCIAL ZONE:

STRUCTURE SETBACK

MINOR CONTOUR

MAJOR CONTOUR

OVERHEAD WIRES

PAVED ROADWAY

DIRT ROADWAY

CLIFF LINE

OVERGROWN ROAD CENTERLINE

SHORELINE PER ARMY CORP.

---- FLOOD ZONE LINE

WILLIAMA DAVIDSON

* WILLIAMA DAVIDSON

0-19494-1-1

|v| 1 105

USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS PROJECT, WITHOUT THE WRITTEN PERMISSION OF HOYLE, TANNER. 2 ISSUED FOR DPNR STT CZM COMMITTEE REVIEW AND APPROVAL 10/3C	10/15	ISSUED FOR DPNR & DPW PERMITTING - NOT FOR CONSTRUCTION	- L	CHECKED BY	DESIGNED BY DRAWN BY CHECKED BY	DESIGNED BY
USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS PROJECT, WITTEN PROJECT, WITTEN	-	ISSUED FOR DPNR STT CZM COMMITTEE REVIEW AND APPROVAL	2	TLE, IANNER.	PERMISSION OF THE	
USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS				THE WRITTEN	PROJECT, WITHOUT	
USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR				SE THAN THIS	NY OTHER PURPO	www.hoyletanner.com
USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER,				ONICALLY, FOR	NCLUDING ELECTRO	_
USED, REPRODUCED, DISSEMINATED				I ANY MANNER,	R TRANSFERRED IN	ō
				DISSEMINATED	SED REPRODUCED	=

HOYLE Suit Oviedo, (407) 3

TANNER (407) 3

IGHED, STA 4A, PMB 146
T JOHN, VI 00830


CLAR ENERGY FACILITY
17 PEMAINIDED

5000 EST. ENIGHED, STA 44
SAINT JOHN, VI 008
ECT
PROPOSED SOLAR ENERGY
BOVONI 17 REMAIND
ESTATE BOVONI

EXISTING CONDITIONS PLAN

PROJECT NO. 23.141001.00

SHEET 2 OF 9



CONTRACTOR COMPLY WITH THE REQUIREMENTS OF THE TERRITORIAL

SWPPP) STORM WATER REGULATIONS, INCLUDING BUT NOT LIMITED TO,

EQUIPMENT MAINTENANCE GUIDELINES, ETC. PLEASE CONTACT USEPA

OFFICE OF WASTEWATER MANAGEMENT AT 202-564-9545 OR AT

WWW.EPA.GOV/NPDES/STORMWATER FOR ADDITIONAL INFORMATION.

VIRGIN ISLANDS STORM WATER POLLUTION PREVENTION PLANS (VI

STORM WATER POLLUTION PREVENTION PLANS (SWPPP'S),

IMPLEMENTATION OR EROSION AND SEDIMENTATION CONTROLS

EROSION CONTROL MEASURES. CONFINE PERIOD OF DISTURBED AND

AND SWALES ARE REQUIRED TO BE STABILIZED PRIOR TO DIRECT

3. REFER TO DWG C7 FOR ADDITIONAL EROSION CONTROL NOTES AND

RECEIPT OF ANY FLOW.

DETAILS.

UNSTABILIZED SOILS TO A MAXIMUM OF FORTY-FIVE DAYS. ALL DITCHES

NO INFILTRATION BASIN IS PROPOSED FOR RETENTION PURPOSES.

AND PREVENT EROSION.

PROJECT.

CORRECTED IN A TIMELY MANNER.

PERMANENT ROCK BERM SERIES ARE PROPOSED IN AREAS ON-SITE

9. THE SITE SHALL BE INSPECTED AFTER ALL MAJOR STORM EVENTS. ANY

10. THERE IS NO PROPOSED WATER, SEWER OR LIGHTING AS PART OF THIS

11. ALL ITEMS TO BE DEMOLISHED SHALL BE REMOVED AND DISPOSED OF

BY THE CONTRACTOR IN ACCORDANCE WITH ALL GOVERNING AGENCIES.

DEFICIENCIES IN THE EROSION CONTROL AND VEGETATION SHALL BE

WITH CONCENTRATED FLOW PATHS TO REDUCE PEAK RUNOFF RATES

6. OBTAIN DPW DRIVEWAY PERMITS AND CONSTRUCT 20' WIDE GRAVEL

9. CONSTRUCT SOLAR RACKING AND INSTALL SOLAR PANELS ON RACKING.

11. APPLY EROSION CONTROL LOW HEIGHT GRASS MIX TO ANY DISTURBED

10. INSTALL UNDERGROUND CONDUIT, PV INVERTERS, EQUIPMENT PADS.

ACCESS DRIVEWAYS AND TURNAROUND.

8. INSTALL SOLAR RACKING SCREWS

BATTERIES AND POWER POLES.

7. CONSTRUCT STORMWATER BPM AS SHOWN ON PLANS.

VEGETATION AREAS THROUGHOUT THE SITE.


LEGEND

SH AN SH AN

SOLAR LLC
RON LLC COMP
GHED, STA 4A, F

SITE PREP / EROSION **CONTROL PLAN**

PROJECT NO. 23.141001.00 SHEET 3 OF 9



28. NO HERBICIDES, PESTICIDES OR CLEANERS SHALL BE USED ONSITE.

19. FILL OR TOPSOIL SHALL NEITHER BE PLACED NOR COMPACTED WHILE IN A MUDDY CONDITION.


	THIS DOCUMENT IS PREPARED AS	FREFARED AS			
	AN INSTRUMENT OF SERVICE AND	SERVICE AND			
	HOYLE, TANNER. IT MAY NOT BE	MAY NOT BE			
	USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER,	, DISSEMINATED A ANY MANNER,			
	INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS	ONICALLY, FOR			
	PROJECT, WITHOUT THE WRITTEN	THE WRITTEN			
	PERMISSION OF HOYLE, LANNER.	YLE, IANNER.	2	ISSUED FOR DPNR STT CZM COMMITTEE REVIEW AND APPROVAL	10/30
	ED BY DRAWN BY CHECKED BY	СНЕСКЕВ ВУ	-	ISSUED FOR DPNR & DPW PERMITTING - NOT FOR CONSTRUCTION	10/15
S	SES	WRD	REV.	REVISION DESCRIPTION	DA

SOLAR LLC
RON LLC COMP
GHED, STA 4A, I

SITE LAYOUT PLAN

PROJECT NO. 23.141001.00

SHEET 4 OF 9




GRADING NOTES

- 2. LAYOUT ALL WORK, ESTABLISH GRADES, LOCATE EXISTING UNDERGROUND
- 3. IN AREAS OF GRADING, THE SUBGRADE SHALL BE LOOSENED BY SCARIFYING TO A DEPTH OF AT LEAST 2" TO ENSURE BONDING OF THE TOPSOIL AND SUBSOIL.
- 4. AREAS OF EXCAVATION ACTIVITIES SHALL BE RESTORED TO A MINIMUM OF 4" OF SEEDED TOPSOIL, FERTILIZER, AND MULCH.
- CONTRACTOR'S WORK INCLUDES, BUT IS NOT LIMITED TO, PROVIDING ALL LABOR, MATERIALS, EQUIPMENT, SUPERVISION, QUALITY CONTROL, AND INCIDENTALS NECESSARY TO EXCAVATE, DEWATER AND CONTROL SURFACE WATER, BACKFILL, CONDUCT COMPACTION AND TESTING OF MATERIALS, ROUGH GRADE, AND REMOVE SEDIMENT AND SOIL AND OTHER SUBSURFACE MATERIALS IN ACCORDANCE WITH THE DESIGN DOCUMENTS, APPLICABLE LAW, APPLICABLE PERMITS, AND PROJECT AGREEMENTS.
- 6. ALL STAKING AND LAYOUT WORK REQUIRED FOR WORK INCLUDED UNDER THIS SECTION SHALL BE THE RESPONSIBILITY OF CONTRACTOR. CONTRACTOR SHALL ESTABLISH ALL REFERENCE POINTS, LAY OUT THE WORK, AND BE RESPONSIBLE FOR ALL LINES, ELEVATIONS, MEASUREMENTS AND OTHER GRADING OPERATIONS.
- UNIFORMLY GRADE AREAS WITHIN SPECIFIED LIMITS, INCLUDING ADJACENT TRANSITIONS. SMOOTH FINISHED SURFACES WITHIN SPECIFIED TOLERANCES, COMPACT WITH UNIFORM LEVELS OR SLOPES BETWEEN POINTS INDICATED, IN DESIGN DOCUMENTS.

- C. EQUIPMENT PADS: THE UPPER 12 INCHES OF SUBGRADE SHALL BE COMPACTED TO 95 PERCENT RELATIVE COMPACTION, OR AS REQUIRED.
- MATERIAL DISPOSAL AND STORAGE SITES
- A. SUITABLE EXCAVATED MATERIALS MAY BE STOCKPILED AND RE-USED IN SYSTEM CONSTRUCTION.
- B. DISPOSE OF UNSUITABLE OR EXCESS EXCAVATED AND WASTE MATERIALS IN ACCORDANCE WITH APPLICABLE LAW AND APPLICABLE PERMITS.
- C. CONTRACTOR STOCKPILE AND LAYDOWN AREAS SHALL BE DEVELOPED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONSTRUCTION DESIGN DOCUMENTS.
- 10. EMBANKMENTS AND BACKFILL SURROUNDING STRUCTURES SHALL BE COMPACTED TO A MINIMUM OF 95 PERCENT.
- 11. EARTH SLOPES SHALL NOT EXCEED 3 HORIZONTAL TO 1 VERTICAL UNLESS SHOWN OTHERWISE.
- 12. CUT INS AND STEPS ALONG ANY STEEP SLOPES MAY BE REQUIRED AND WILL BE CONSTRUCTED ONLY ON AN AS NEEDED BASIS TO INSTALL THE SOLAR SYSTEM TO REDUCE THE OVERALL GROUND DISTURBANCE.

- 3. THE CONTRACTOR SHALL STABILIZE ANY AND ALL DITCHES AND SWALES PRIOR TO DIRECTING STORMWATER RUN-OFF TO THEM.
- 4. ACCESS DRIVEWAYS MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
- 5. EROSION CONTROL MEASURES ARE TO BE INSPECTED WEEKLY AND AFTER EVERY 0.25" OF RAINFALL WITHIN A 24 HOUR PERIOD.
- UNSTABILIZED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 72 HOURS OF FINAL GRADING, OR PRIOR TO A 0.25" STORM OCCURING AFTER THE DISTURBANCE, WHICHEVER OCCURS SOONER.
- TEMPORARY STABILIZATION MEASURES MUST REMAIN IN PLACE THROUGH ALL CONSTRUCTION PHASES, UNTIL THE SITE IS PERMANENTLY
- THE SITE SHALL BE STABILIZED BY ESTABLISHING AT LEAST 95% VEGETATIVE COVER UNIFORMLY DISTRIBUTED, INCLUDING UNDER THE
- 9. PROVIDE EROSION CONTROL MATTING ON ALL 3:1 OR GREATER SLOPES.
- 10. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AFTER THE SITE HAS BEEN STABILIZED.



					1	6	
					ISSUED FOR DPNR STT CZM COMMITTEE REVIEW AND APPROVAL	ISSUED FOR DPNR & DPW PERMITTING - NOT FOR CONSTRUCTION	REVISION DESCRIPTION
					2	-	REV.
PROPERTY OF MAY NOT BE DISSEMINATED A ANY MANNER, ONICALLY, FOR SE THAN THIS THE WRITTEN OYLE, TANNER.							WRD
SHALL REMAIN THE PROPERTY OF HOYLE, TANNER. IT MAY NOT BE USED, REPRODUCED, DISSEMINATED OR TRANSFERRED IN ANY MANNER, INCLUDING ELECTRONICALLY, FOR ANY OTHER PURPOSE THAN THIS PROJECT, WITHOUT THE WRITTEN PERMISSION OF HOYLE, TANNER.						DESIGNED BY DRAWN BY CHECKED BY	SES
						DESIGNED BY	SES
95 E. Mitchell Hamm Suite 200 Oviedo, FL 327 (407) 380-19: www.hoyletanne DATE: EMBER 19, 2024							SEPTEMBER 19, 2024
	NA NA						
						بنا	NW0


STB SOLAR LLC

"LECTRON LLC COMP

". ENIGHED, STA 4A, F

GRADING & DRAINAGE PLAN

PROJECT NO. 23.141001.00 SHEET 5 OF 9



EROSION CONTROL NOTES:

- POLLUTION PREVENTION. MINIMIZE DISTURBED AREAS AND PROTECT NATURAL DOWNGRADIENT BUFFER AREAS TO THE EXTENT PRACTICABLE CONTROL STORMWATER VOLUME AND VELOCITY WITHIN THE SITE TO MINIMIZE SOIL EROSION. MINIMIZE THE DISTURBANCE OF STEEP SLOPES CONTROL STORMWATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND VOLUME, TO MINIMIZE EROSION AT OUTLETS. THE DISCHARGE MAY NOT RESULT IN EROSION OF ANY OPEN DRAINAGE CHANNELS, SWALES, STREAM CHANNELS OR STREAM BANKS, UPLAND, OR COASTAL OR FRESHWATER WETLANDS OFF THE PROJECT SITE. WHENEVER PRACTICABLE. NO DISTURBANCE ACTIVITIES SHOULD TAKE PLACE WITHIN 25 FEET OF ANY PROTECTED NATURAL RESOURCE. IF DISTURBANCE ACTIVITIES TAKE PLACE LESS THAN 25 FEET FROM ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE. PERIMETER EROSION CONTROLS MUST BE DOUBLED AND DISTURBED AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED WITHIN 7 DAYS.
- 2. SEDIMENT BARRIERS. PRIOR TO CONSTRUCTION, PROPERLY INSTALL SEDIMENT BARRIERS AT THE DOWNGRADIENT EDGE OF ANY AREA TO BE DISTURBED AND ADJACENT TO ANY DRAINAGE CHANNELS WITHIN THE DISTURBED AREA. SEDIMENT BARRIERS SHOULD BE INSTALLED DOWNGRADIENT OF SOIL OR SEDIMENT STOCKPILES AND STORMWATER PREVENTED FROM RUNNING ONTO THE STOCKPILE. MAINTAIN THE SEDIMENT BARRIERS BY REMOVING ACCUMULATED SEDIMENT, OR REMOVING AND REPLACING THE BARRIER, UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. WHERE A DISCHARGE TO A STORM DRAIN INLET OCCURS, IF THE STORM DRAIN CARRIES WATER DIRECTLY TO A SURFACE WATER AND YOU HAVE AUTHORITY TO ACCESS THE STORM DRAIN INLET, YOU MUST INSTALL AND MAINTAIN PROTECTION MEASURES THAT REMOVE SEDIMENT FROM THE DISCHARGE.
- 3. STABILIZED CONSTRUCTION ENTRANCE. PRIOR TO CONSTRUCTION, PROPERLY INSTALL A STABILIZED CONSTRUCTION ENTRANCE (SCE) AT ALL POINTS OF EGRESS FROM THE SITE. THE SCE IS A STABILIZED PAD OF AGGREGATE, UNDERLAIN BY A GEOTEXTILE FILTER FABRIC, USED TO PREVENT TRAFFIC FROM TRACKING MATERIAL AWAY FROM THE SITE ONTO PUBLIC ROWS. MAINTAIN THE SCE UNTIL ALL DISTURBED AREAS ARE STABILIZED.
- 4. TEMPORARY STABILIZATION. WITHIN 7 DAYS OF THE CESSATION OF CONSTRUCTION ACTIVITIES IN AN AREA THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS, STABILIZE ANY EXPOSED SOIL WITH MULCH, OR OTHER NON-ERODIBLE COVER. STABILIZE AREAS WITHIN 75 FEET OF A NATURAL RESOURCE WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OF THE SOIL OR PRIOR TO ANY STORM EVENT, WHICHEVER COMES FIRST.
- 5. <u>REMOVAL OF TEMPORARY MEASURES.</u> REMOVE ANY TEMPORARY CONTROL MEASURES, SUCH AS MULCH BERMS OR SILT SOCKS, WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED. REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE.
- 6. PERMANENT STABILIZATION. IF THE AREA WILL NOT BE WORKED FOR MORE THAN ONE YEAR OR HAS BEEN BROUGHT TO FINAL GRADE, THEN PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, OR THROUGH THE USE OF PERMANENT MULCH, OR RIP-RAP. OR ROAD SUB-BASE. IF USING VEGETATION FOR STABILIZATION, SELECT THE PROPER VEGETATION FOR THE LIGHT, MOISTURE, AND SOIL CONDITIONS; AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL OR COMPOST; PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE PLANTING, AND SEEDING SO TO AVOID DIE—OFF FROM DROUGHT. NEWLY SEEDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL-ESTABLISHED WITH 90% COVER BY HEALTHY VEGETATION. IF NECESSARY, AREAS MUST BE REWORKED AND RESTABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPLY TO A PARTICULAR SITE.
- 7. SEEDED AREAS, FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 95% COVER OF THE DISTURBED AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.
 - A. PERMANENT MULCH. FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. MULCH FROM TREE GRINDINGS MAY BE USED AS EROSION CONTROL FOR PERMANENT STABILIZATION. THE MULCH MIX AND COVERAGE SHALL BE REVIEWED AND APPROVED BY THE DESIGN ENGINEER PRIOR TO BEING DETERMINED AS STABILIZED.
 - B. RIP-RAP. FOR AREAS STABILIZED WITH RIP-RAP, PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIP-RAP HAVE AN APPROPRIATE BACKING OF A WELL-GRADED GRAVEL

- OR APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIP-RAP. STONE MUST BE SIZED APPROPRIATELY. ANGULAR STONE SHALL BE USED.
- C. AGRICULTURAL USE. FOR CONSTRUCTION PROJECTS ON LAND USED FOR AGRICULTURAL PURPOSES (E.G., PIPELINES ACROSS CROP LAND), PERMANENT STABILIZATION MAY BE ACCOMPLISHED BY RETURNING THE DISTURBED LAND TO AGRICULTURAL USE.
- D. PAVED AREAS. FOR PAVED AREAS, PERMANENT STABILIZATION MEANS THE PLACEMENT OF THE COMPACTED GRAVEL SUB-BASE IS COMPLETED, PROVIDED IT IS FREE OF FINE MATERIALS THAT MAY RUNOFF WITH A RAIN EVENT
- E. DITCHES, CHANNELS, AND SWALES. FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH A 90% COVER OF HEALTHY VEGETATION, WITH A WELL-GRADED RIP-RAP LINING, TURF REINFORCEMENT MAT, OR WITH ANOTHER NON-EROSIVE LINING SUCH AS CONCRETE OR ASPHALT PAVEMENT. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE CHANNEL LINING, UNDERCUTTING OF THE CHANNEL BANKS, OR DOWN-CUTTING OF THE CHANNEL.
- 9. <u>STORMWATER CHANNELS.</u> DITCHES, SWALES, AND OTHER OPEN STORMWATER CHANNELS MUST BE DESIGNED, CONSTRUCTED, AND STABILIZED USING MEASURES THAT ACHIEVE LONG-TERM EROSION CONTROL. DITCHES, SWALES AND OTHER OPEN STORMWATER CHANNELS MUST BE SIZED TO HANDLE, AT A MINIMUM, THE EXPECTED VOLUME RUN-OFF. EACH CHANNEL SHOULD BE CONSTRUCTED IN SECTIONS SO THAT THE SECTION'S GRADING, SHAPING, AND INSTALLATION OF THE PERMANENT LINING CAN BE COMPLETED THE SAME DAY. IF A CHANNEL'S FINAL GRADING OR LINING INSTALLATION MUST BE DELAYED, THEN DIVERSION BERMS MUST BE USED TO DIVERT STORMWATER AWAY FROM THE CHANNEL, PROPERLY-SPACED CHECK DAMS MUST BE INSTALLED IN THE CHANNEL TO SLOW THE WATER VELOCITY, AND A TEMPORARY LINING INSTALLED ALONG THE CHANNEL TO PREVENT SCOURING.
 - A. THE CHANNEL SHOULD RECEIVE ADEQUATE ROUTINE MAINTENANCE TO MAINTAIN CAPACITY AND PREVENT OR CORRECT ANY EROSION OF THE CHANNEL'S BOTTOM OR SIDE
 - B. WHEN THE WATERSHED DRAINING TO A DITCH OR SWALE IS LESS THAN 1 ACRE OF TOTAL DRAINAGE AND LESS THAN 1/4 ACRE OF IMPERVIOUS AREA, DIVERSION OF RUNOFF TO ADJACENT WOODED OR OTHERWISE VEGETATED BUFFER AREAS IS ENCOURAGED WHERE THE OPPORTUNITY EXISTS.
- 10. SEDIMENT BASINS. SEDIMENT BASINS MUST BE DESIGNED TO PROVIDE STORAGE FOR EITHER THE CALCULATED RUNOFF FROM A 2-YEAR, 24-HOUR STORM OR PROVIDE FOR 3,600 CUBIC FEET OF CAPACITY PER ACRE DRAINING TO THE BASIN. OUTLET STRUCTURES MUST DISCHARGE WATER FROM THE SURFACE OF THE BASIN WHENEVER POSSIBLE EROSION CONTROLS AND VELOCITY DISSIPATION DEVICES MUST BE USED IF THE DISCHARGING WATERS ARE LIKELY TO CREATE EROSION. ACCUMULATED SEDIMENT MUST BE REMOVED AS NEEDED FROM THE BASIN TO MAINTAIN AT LEAST 1/2 OF THE DESIGN CAPACITY OF THE BASIN.
- 11. ROADS. GRAVEL AND PAVED ROADS MUST BE DESIGNED AND CONSTRUCTED WITH CROWNS OR OTHER MEASURES, SUCH AS WATER BARS, TO ENSURE THAT STORMWATER IS DELIVERED IMMEDIATELY TO ADJACENT STABLE DITCHES, VEGETATED BUFFER AREAS, CATCH BASIN INLETS. OR STREET GUTTERS.
- 12. CULVERTS. CULVERTS MUST BE SIZED TO AVOID UNINTENDED FLOODING OF UPSTREAM AREAS OR FREQUENT OVERTOPPING OF ROADWAYS. CULVERT INLETS MUST BE PROTECTED WITH APPROPRIATE MATERIALS FOR THE EXPECTED ENTRANCE VELOCITY, AND PROTECTION MUST EXTEND AT LEAST AS HIGH AS THE EXPECTED MAXIMUM ELEVATION OF STORAGE BEHIND THE CULVERT. CULVERT OUTLET DESIGN MUST INCORPORATE MEASURES, SUCH AS APRONS, TO PREVENT SCOUR OF THE STREAM CHANNEL. OUTLET PROTECTION MEASURES MUST BE DESIGNED TO STAY WITHIN THE CHANNEL LIMITS. THE DESIGN MUST TAKE ACCOUNT OF TAILWATER DEPTH.
- 13. PARKING AREAS. PARKING AREAS MUST BE CONSTRUCTED TO ENSURE RUNOFF IS DELIVERED TO ADJACENT SWALES, CATCH BASINS, CURB GUTTERS, OR BUFFER AREAS WITHOUT ERODING AREAS DOWNSLOPE. THE PARKING AREA'S SUB-BASE COMPACTION AND GRADING MUST BE DONE TO ENSURE RUNOFF IS EVENLY DISTRIBUTED TO ADJACENT BUFFERS OR SIDE SLOPES. CATCH BASINS MUST BE LOCATED AND SET TO PROVIDE ENOUGH STORAGE DEPTH AT THE INLET TO ALLOW INFLOW OF PEAK RUNOFF RATES WITHOUT BY-PASS OF RUNOFF TO OTHER AREAS.


EROSION CONTROL BERM NOTES:

- 1. EROSION CONTROL BERM MAY BE USED BY THE CONTRACTOR AS AN APPROVED EQUAL TO THE PROPOSED SILT FENCE FOR PERIMETER EROSION CONTROL
- 2. THE BERM SHALL BE CONSTRUCTED FROM STUMP AND VEGETATION GRINDINGS. THE SOIL WITHIN THE ROOT BALL SHALL REMAIN WHEN GROUND TO ADD STRUCTURE TO THE MEDIA.
- 3. THE BERM SHALL BE CONSTRUCTED BY HAND, MACHINERY OR PNEUMATIC BLOWER.
- 4. TALL GRASS, BRUSH OR WOODY VEGETATION SHALL BE CUT OR REMOVED PRIOR TO INSTALLATION TO AVOID VOIDS AND BRIDGES THAT WOULD ALLOW FINE SOIL PARTICLES TO WASH AWAY.
- 5. THE BERM SHALL BE A MINIMUM OF 12 INCHES HIGH AND A MINIMUM OF TWO FEET WIDE. ON LONGER STEEPER SLOPES, THE BERM SHALL BE HIGHER AND WIDER.

CRUSHED STONE **EXISTING** PROPOSED **PAVEMENT** SITE **GEOTEXTILE** FILTER FABRIC **PROFILE**

50' MIN.

2"-3" DIA. ¬





STABILIZED CONSTRUCTION ENTRANCE/EXIT NOTES:

- 1. CONSTRUCT PAD AT THE SITE ENTRANCE(S) AS SHOWN ON THE PLANS.
- 2. THE ENTRANCE/EXIT PAD SHALL BE A MINIMUM OF 50 FEET LONG AND 20 FT WIDE.
- 3. THE PAD SHALL BE A MINIMUM OF 6 INCHES THICK WITH 2-3 INCH ANGULAR AGGREGATE.
- 4. THE AGGREGATE SHALL BE PLACED OVER A GEOTEXTILE FABRIC TO PREVENT STONES FROM PUSHING INTO NATIVE SOIL.
- 5. THE PAD SHALL BE INSPECTED WEEKLY AND BEFORE AND AFTER EACH STORM. THE PAD SHALL BE REPLACED IF THE VOIDS BECOME FILLED WITH SEDIMENT.

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

SCALE: NONE







SILT FENCE NOTES:

- 1. SPACING OF FENCE POSTS NOT TO EXCEED 10'-0".
- 2. SILT FENCE SHALL BE INSTALLED BEFORE ANY EARTH REMOVAL OR EXCAVATION TAKES PLACE.
- 3. FILTER FABRIC TO BE FASTENED SECURELY TO POSTS WITH WIRE TIES OR STAPLES AT TOP, MIDPOINT AND BOTTOM
- 4. OVERLAP BY 6". FOLD AND STAPLE ADJOINING SECTIONS OF FILTER FABRIC.
- 5. MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND THE MATERIAL REMOVED WHEN "BULGES" DEVELOP. DO NOT DEPOSIT THE MATERIAL NEAR WETLANDS OR WATERCOURSES.
- 6. FILTER FABRIC SHALL BE ENTRENCHED 6" MINIMUM BELOW EXISTING OR FINISHED GRADE.

SILT FENCE EROSION CONTROL DETAIL

SCALE: NONE






SILT SOCK NOTES:


- SILT SOCK MAY BE USED BY THE CONTRACTOR AS AN APPROVED EQUAL TO THE PROPOSED SILT FENCE FOR PERIMETER EROSION
- 2. SILT SOCK SHALL BE INSTALLED ON THE DOWNSTREAM EDGE OF ANY EARTH REMOVAL OR EXCAVATION AND REMOVED WHEN THE AREA IS
- 3. INSTALL SILT SOCK AROUND ALL MATERIAL STOCKPILES.
- 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND THE MATERIAL REMOVED WHEN "BULGES" DEVELOP. DO NOT DEPOSIT THE MATERIAL NEAR WETLANDS OR WATERCOURSES.




SCALE: NONE



DRAINAGE WAY SECTION



DRAINAGE WAY PROFILE



CHECK DAM SPACING

CHECK DAM NOTES:

- 1. TEMPORARY CHECK DAMS ARE INTENDED TO BE INSTALLED AS NEEDED AS PART OF THE CONTRACTOR'S OVERALL EROSION CONTROL MEASURES.
- 2. CHECK DAMS SHALL BE INSTALLED PRIOR TO DIRECTING RUNOFF TO THE
- 3. THE MAXIMUM HEIGHT OF A CHECK DAM SHALL BE 2 FEET WITH A 6 INCH DEPRESSION AT ITS CENTER FOR OVERFLOW.
- 4. THE CHECK DAMS SHALL BE REMOVED WHEN THE SWALE IS STABILIZED WITH VEGETATION (90% COVERAGE).



SCALE: NONE

EROSION CONTROL NOTES & DETAILS

STB SOLAR LLC

"LECTRON LLC COMP

". ENIGHED, STA 4A, F

WILLIAM A DAVIDSON

ᅐ유ᆂᆣ

0-19494-11

PROJECT NO. 23.141001.00 SHEET 7 OF 9

EROSION CONTROL BERM DETAIL (AS AN APPROVED EQUAL)

2'-0" MIN.

CONTROL

UNDISTURBED

AREA


BERM

SCALE: NONE

AREA

DIRECTION OF

RUNOFF FLOW



CONCRETE WASHOUT AREA DETAIL


ZEE PURLIN-

SCALE: NONE

WASHOUT AREA NOTES:


- 1. CONCRETE WASHOUT AREA(S) SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE. THE CONCRETE WASHOUT AREA SHALL BE ENTIRELY SELF-CONTAINED.
- 2. THE CONTRACTOR SHALL SUBMIT THE DESIGN, LOCATION AND SIZING OF THE CONCRETE WASHOUT AREA(S) WITH THE PROJECT'S EROSION AND SEDIMENTATION CONTROL PLAN.
- 3. LOCATION: WASHOUT AREA(S) ARE TO BE LOCATED A MINIMUM OF 50 FEET FROM ANY STREAM, WETLAND, STORM DRAIN, OR ANY OTHER SENSITIVE RESOURCE. ALL CONCRETE DRIVERS SHALL BE AWARE OF THE LOCATION OF THE WASHOUT AREA PRIOR TO ANY CONCRETE PLACEMENT.
- 4. THE WASHOUT MUST HAVE SUFFICIENT VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS INCLUDING, BUT NOT LIMITED TO, OPERATIONS ASSOCIATED WITH GROUT AND MORTAR.
- 5. SURFACE DISCHARGE IS UNACCEPTABLE. THEREFORE, STRAW BALES OR OTHER CONTROL MEASURES, SHOULD BE USED AROUND THE PERIMETER OF THE CONCRETE WASHOUT AREA FOR CONTAINMENT.

- 6. SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CONCRETE AREA(S) AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT AREA TO CONCRETE TRUCK OPERATORS. WASHOUT AREA(S) SHOULD BE FLAGGED WITH SAFETY FENCING OR OTHER APPROVED METHODS.
- 7. WASHOUT(S) ARE TO BE INSPECTED AT LEAST ONCE A WEEK FOR STRUCTURAL INTEGRITY, ADEQUATE HOLDING CAPACITY AND CHECKED FOR LEAKS, TEARS, OR OVERFLOWS. WASHOUT AREAS SHOULD BE CHECKED AFTER EVERY RAIN EVENT.
- 8. HARDENED CONCRETE WASTE SHOULD BE REMOVED AND DISPOSED OF WHEN THE WASTE HAS ACCUMULATED TO HALF OF THE CONCRETE WASHOUT'S HEIGHT. ALL CONCRETE WASTE SHALL BE DISPOSED OF BY THE CONTRACTOR IN ACCORDANCE WITH ALL APPLICABLE LOCAL AND STATE LAWS, REGULATIONS, AND GUIDELINES



FENCE NOTES:

- 1. REFER TO ELECTRICAL DRAWINGS FOR FINAL FENCE DETAILS AND GROUNDING REQUIREMENTS. THE ELECTRICAL PLANS SHALL GOVERN IN THE CASE OF ANY DISCREPANCIES BETWEEN THE DRAWINGS.
- 2. ALL FENCE POSTS SHALL BE 10' AND EMBEDDED A MIN. 3' INTO THE CONCRETE FOOTING.
- 3. FENCE SIGNAGE MUST BE LOCATED AT EYE LEVEL. SIGNS MUST BE LOCATED ON ALL GATES AND ALL SIDES, NO GREATER THAN 50' BETWEEN SIGNS. REFER TO ELECTRICAL DWGS FOR ADDITIONAL INFORMATION
- 4. AFFIX APPROPRIATE SYSTEM OWNER NAME AND CONTACT INFO DECAL TO ALL FENCE SIGNAGE.
- 5. BOND GATES TO GATE POST WITH FLEXIBLE BRAIDED GROUNDING STRAP.
- 6. FENCE TO BE MIN. 15' AWAY FROM SOLAR ARRAY, TO AVOID NEC GROUNDING REQUIREMENT. GATES MUST BE GROUNDED PER NESC RULE 092E. REFER TO ELECTRICAL DWGS FOR ADDITIONAL INFORMATION




SOLAR RACKING NOTES:

TYPICAL PROFILE VIEW 1. THESE DETAILS ARE INTENDED FOR REFERENCE ONLY

SHEETING

- FOR SITE PERMITTING AND ARE SOLELY BASED ON INFO PROVIDED BY THE SOLAR RACKING PROVIDER.
- 2. REFER TO SOLAR RACKING PLANS FOR ALL FINAL ASPECTS OF THE RACKING DESIGN AND FOR LAYOUT




TYPICAL ELEVATION VIEW FROM FRONT (NORTH-FACING)

TYPICAL SOLAR RACKING ASSEMBLY DETAIL

SCALE: NONE

PERIMETER SECURITY FENCE DETAIL

SCALE: NONE



1. REFER TO ELECTRICAL DRAWINGS FOR FINAL FENCE DETAILS AND GROUNDING REQUIREMENTS. THE ELECTRICAL PLANS SHALL GOVERN IN THE CASE OF ANY DISCREPANCIES BETWEEN THE DRAWINGS.




SHEET 8 OF 9

STB SOLAR LLC ELECTRON LLC COMP. T. ENIGHED, STA 4A, P.

THIS AN I HOY I HO

CONSTRUCTION **DETAILS 1**


PROJECT NO. 23.141001.00



(1) C9

DRIVEWAY 1 DETAIL PLAN

SCALE: 1" = 60'




ROCK BERM NOTES:

- 1. REFER TO PLANS FOR APPROXIMATE LOCATION OF ROCK BERMS.
- 2. THE CONTRACTOR SHALL COORDINATE WITH THE DESIGN ENGINEER IN THE FIELD ON THE FINAL LOCATION AND WIDTH OF THE PROPOSED ROCK BERMS. THE DESIGN INTENT IS TO INSTALL THE BERMS IN THE CENTER OF THE NATURAL DRAINAGE FLOW PATHS WITHIN THE SOLAR FIELD TO SLOW AND DISSIPATE STORMWATER RUNOFF.



PERMANENT ROCK BERM SERIES

SCALE: NONE





SCALE: NONE



CONSTRUCTION DETAILS 2


PROJECT NO. 23.141001.


PROJECT NO. 23.141001.00

SHEET 9 OF 9

Attachment H - Required Maps and Plans







MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) С 1:12.000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D **Soil Rating Polygons** Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil **Water Features** line placement. The maps do not show the small areas of A/D contrasting soils that could have been shown at a more detailed Streams and Canals Transportation B/D Rails ---Please rely on the bar scale on each map sheet for map measurements. Interstate Highways C/D Source of Map: Natural Resources Conservation Service **US Routes** Web Soil Survey URL: D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available -Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Soil Rating Lines Background distance and area. A projection that preserves area, such as the Aerial Photography Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Virgin Islands of the United States Survey Area Data: Version 5, Sep 13, 2023 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Not rated or not available Date(s) aerial images were photographed: Jan 1, 2016—Feb 16. 2023 **Soil Rating Points** The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. B/D

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
CbB	Cinnamon Bay loam, 0 to 5 percent slopes, occasionally flooded	В	9.7	1.5%
CgC	Cinnamon Bay gravelly loam, 5 to 12 percent slopes, occasionally flooded	A	6.5	1.0%
SaA	Salt flats, ponded		4.5	0.7%
SBA	Sandy Point and Sugar Beach soils, 0 to 2 percent slopes, frequently flooded	C/D	64.5	10.1%
SoA	Solitude gravelly fine sandy loam, 0 to 2 percent slopes, frequently flooded	A/D	37.2	5.8%
SrD	Southgate-Rock outcrop complex, 12 to 20 percent slopes	D	9.7	1.5%
SrE	Southgate-Rock outcrop complex, 20 to 40 percent slopes	D	110.3	17.3%
SrF	Southgate-Rock outcrop complex, 40 to 60 percent slopes	D	79.4	12.5%
SrG	Southgate-Rock outcrop complex, 60 to 90 percent slopes	D	16.0	2.5%
Us	Ustorthents		38.4	6.0%
Totals for Area of Inter	rest		637.5	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

Attachment I – Hydrology Report





Hydrology Report

For a Proposed Solar Energy Facility with Battery Storage

Bovoni 17 Remainder Estate Bovoni St. Thomas, U.S. Virgin Islands

HTA Project No. 23.141001.00

October 2025

Applicant:
STB Solar LLC
A Vielectron LLC Company






Table of Contents

Introduction	3
Project Location	3
FEMA Flood Hazard	3
Project Description	4
Hydrologic Analysis	5
Rainfall	5
Soils	6
Hydrographs	6
Modeling	6
Pre-Development Conditions	
Post-Development Conditions	8
Peak Runoff Analysis	10
Conclusion	
Appendix A – Rainfall Data	
Appendix B – NRCS Web Soil Survey	
Appendix C – Pre-Development Watershed Map	
Appendix D – Post-Development Watershed Map	22
Appendix E – HydroCAD Analysis	

Introduction


Project Location

The proposed solar energy facility is located within Tier I (coastal zone) at parcel 17 Remainder Bovoni, Estate Bovoni near the eastern side of St. Thomas, south of Landfill Road (See below image). The total parcel (109402 010100) area is 30.95 +/- acres, where 23.51 +/- acres is anticipated to be disturbed.



FEMA Flood Hazard

The Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) Number FM780000043G, effective date April 16, 2007, covers the project site. The site is predominately located within flood zone "X", with the 100-year flood zone "VE" present in the southern part of the site near the coastline (see below image). No wetlands are present on-site.



Topographic information used for the development of hydrologic and hydraulic models at the project site and contiguous areas was obtained from American Land Title Association (ALTA) and topographic survey (survey) prepared by Marvin Berning & Associates professional land surveyors in May 2024. The survey provided 2-foot interval contours of the project area, the shoreline, cliff line, and limits of the flood zone.

Project Description

The project consists of the construction of a ground mounted racking solar field system with a 10.725+/-MWdc (10 MWac) capacity including on-site battery energy storage system (BESS), equipment pads and access driveways. The racking system will be supported on 2.375-inch diameter ground screws installed into the ground in rows running in the east-west axis with each row separated by a typical 2-foot aisle. Depending on the existing slopes, some rows will be spaced in either 5-foot or 8-foot aisles to the north where the site experiences reverse slopes. The solar panels are set at a fixed tilt of either 10- or 20-degrees that will rest a minimum 24-inches above ground allowing grass and other various open space vegetation to grow underneath.

The site is currently being partially cleared in accordance to an approved Permit Letter Request with a low ground pressure skid steer or track excavator with a mulching attachment to remove and grind the existing trees and vegetation within 2-inches of the existing ground surface to preserve all topsoil and

allow existing roots to remain, where the majority of the mulch is left in place while any excess mulch is placed in a perimeter berm along the downhill slopes toward the coast (see below image). Prior to construction of the solar racking system, the remaining project area will be cleared using the current clearing methods and the security fence will be installed.



Hydrologic Analysis

Rainfall

The runoff analysis is based on the 2, 10, 25, and 100-year storm events using the SCS Technical Release 55 (TR-55) method with Type-II, 24-hour storms. Rainfall precipitation data was obtained from National Oceanic and Atmospheric Administration's (NOAA) National Weather Service Precipitation Frequency Data Server (**Appendix A**) based on the project location. A summary of the rainfall events is shown in the table below.

STORM EVENT	24-HOUR RAINFALL (Inches)
2-Year Storm	3.82
10-Year Storm	7.30
25-Year Storm	9.58
100-Year Storm	13.50

Soils

Existing site soil information was taken from the Natural Resources Conservation Service's (NRCS). The NRCS Web Soil Survey (**Appendix B**) classifies the types of soils found within the watershed according to hydrologic soils group (HSG): A, B, C or D. The site consists entirely of HSG D soils, as the United States Virgin Island of Saint Thomas is known for having volcanic, rocky, soils.

Hydrographs

The overall pre-development and post-development site hydrographs were calculated utilizing the method detailed in TR-55 "*Urban Hydrology for Small Watersheds*" as published by the United States Department of Agriculture Soil Conservation Service, "SCS", and revised in June of 1986.

The site has a natural ridgeline to the north that runs in the east-west direction where the majority of the site drains in the southern direction towards the coast, while portions of the site drain north towards an existing ditch that runs along the southern side of the existing paved road. The entire site eventually discharges into the Caribbean Sea.

To effectively analysis the on-site hydrologic and hydraulic conditions of the project, the site has been divided into three (3) watersheds – due to the natural ridges and valleys – each with a designated design point (assumed critical stormwater discharge point). Watershed 1 drains primarily to the north into the existing ditch running along the south side of the existing paved road, eventually into the Sea. Watershed 2 drains into an existing valley central to the site and eventually into the Sea. Watershed 3 drains into an existing valley on the east side of the site and eventually into the Sea. The watershed delineations for the project area do not change from pre-development to post-development conditions.

Modeling

The hydrologic analysis was performed using the HydroCAD computer program which is based on the NRCS Technical Release 20 (TR-20) Model for Project Formulation Hydrology. Due to the existing grounds and topography, combination of segments of sheet flow and shallow concentrated flow methods were used to determine the time of concentration for each watershed.

For this analysis, rainfall depth was uniformly imposed on the pre- and post-development watersheds over a 24-hour period and then converted to a peak runoff volume using a Runoff Curve Number (CN), which is determined based on the soil types and HSG classified by the NRCS Web Soil Survey. The lower or higher the CN the more permeable or impervious the ground conditions are, respectively. Said volume is transformed into a hydrograph utilizing the Unit Hydrograph Theory and routing procedures, which are dependent on the travel time through each watershed.

Pre-Development Conditions

The existing site has been extensively disturbed, previously used for agricultural purposes, and is currently vacant. The site has been partially cleared and mulched in accordance with an approved Permit Letter Request but was previously underdeveloped and overgrown with woods and grass, which have been used as the pre-development conditions for the purpose of this analysis. The following land covers have been used for the HSG D soils identified on-site: "Artificial desert landscape", "Dirt roads", "Impervious area", "Paved parking", and "Woods/grass comb., Good". Please see Pre-Development Drainage Map (Appendix C).

The site contains a few areas of impervious cover (approximately 5,170 +/- SF) from a paved driveway/parking lot, miscellaneous concrete pads, and paved road to the site that runs along the northern side of the site. For the purposes of this analysis, the area between the property boundary and the existing paved road was considered desert landscape while the remaining impervious cover was considered paved area.

Design Point 1 (DP1) is located on the northern and western side of the site and receives runoff from approximately 12.76 acres and eventually discharges to the Sea. Design Point 2 (DP2) is located central to the site and receives runoff from approximately 8.78 acres and eventually discharges to the Sea. Design Point 3 (DP3) is located on the eastern side of the site and receives runoff from approximately 6.64 acres and eventually discharges to the Sea. Due the existing volcanic soils and topography, sheet flow was assumed for the first 300 feet and eventually transitions to a shallow concentrated flow through the existing wood/brush conditions in naturally occurring valleys for all three (3) design points.

The analysis criteria used for the SCS TR-20 hydraulic analysis of the pre-development conditions are as follows:

- Storm Event Frequency: 2, 10, 25, and 100-year, 24-Hour Storms
- Runoff Coefficients (CN)

Impervious, HSG D	= 98
Paved area, HSG D	= 98
Artificial desert landscape, HSG D	= 96
Dirt roads, HSG D	= 89
Woods/grass comb., Good, HSG D	= 79

The table below provides a summary of the peak runoff rates in the pre-development conditions.

PRE-DEVELOPMENT CONDITIONS (RATES)								
Design Point 1 Design Point 2 Design Point 3								
Inflow Area	12.76 Acres	8.78 Acres	6.64 Acres					
Peak Design Storm	Flow (cfs)	Flow (cfs)	Flow (cfs)					
2-Year; 24-hour	27.24	18.07	15.31					
10-Year; 24-hour	69.49	48.11	40.55					
25-Year; 24-hour	97.68	68.38	57.54					
100-Year; 24-hour	145.86	103.14	86.66					

Post-Development Conditions

The proposed site is designed to utilize the existing topography and minimize the effects on the natural hydrologic and hydraulic patterns of the existing site. The proposed project will maintain the soil type, watersheds, and design points consistent with the pre-development conditions. Please see Post-Development Drainage Map (**Appendix D**).

The site may contain steep slopes that may require steps and/or cut ins to install the proposed solar system that will only be constructed on an as needed basis to reduce the overall ground disturbance of the site. Additional silt fencing may be required to control erosion during construction, and stabilization will be established before the completion of construction. Natural spray tack adhesives will be used for permanent measures to stabilize the site for any necessary stepping access paths or cut ins. Permanent rock berm series will also be installed as needed within naturally occurring drainage flow paths as an erosion control measure and help reduce the overall peak runoff rates for various storm events.

At the end of each row, all power lines used to operate the solar panels will be distributed above ground to connect the equipment pads where the low-voltage wires will run through a Class 2 Circuit (CAV) system and the high-voltage wires will run through conduits on concrete pads. No trenching or excavating is anticipated for this project further minimizing any ground disturbance to the site.

The entire site drains into the Caribbean Sea and concerns of adverse flooding are not anticipated therefore the 2022 U.S. Virgin Islands Environmental Protection Handbook (USVI EP Handbook) requirements to reduce the runoff volume for the 1-year design storm is not applicable for this project.

The proposed development will utilize dense Guinea Grass (Megathyrsus maximus), maintained at a 6"-12" height, to surround the proposed racking system (both within the aisles and underneath the panels) to create a stable ground condition similar to the existing conditions. For this hydrological analysis, a land cover of ">75% Grass Cover, Good" has been used for the developed portions of the site, while the undeveloped potions will maintain the existing land covers of "Woods/grass comb., Good". The panels themselves, tilted at either a 10- or 20-degrees and raised 24" from the ground, are modelled as pervious since all groundcover below them will be stabilized grass to absorb runoff and gaps between

adjacent panels will allow water to drain freely. Below is a photo of a constructed solar site by VIElectron showing the dense stabilized Guinea grass in and around the solar modules.



The additional amounts of impervious cover (approximately 3,450 +/- SF) from the equipment pads, above ground conduit runs, battery storage, and ground screws were accounted for and were considered paved areas for the purposes of this analysis. Additional ground cover includes the proposed access drive, which was considered gravel road.

The analysis criteria used for the SCS TR-20 hydraulic analysis of the post-development conditions are as follows:

• Storm Event Frequency: 2, 10, 25, and 100-year, 24-Hour Storms

Runoff Coefficients (CN)

Impervious, HSG D	= 98
Parked area, HSG D	= 98
Artificial desert landscape, HSG D	= 96
Gravel roads, HSG D	= 96
>75% Grass Cover, Good, HSG D	= 80
Woods/grass comb., Good, HSG D	= 79

The table below provides a summary of the peak runoff rates in the post-development conditions.

POST-DEVELOPMENT CONDITIONS (RATES)							
Design Point 1 Design Point 2 Design Point 3							
Inflow Area	Inflow Area 12.76 Acres		6.64 Acres				
Peak Design Storm	Flow (cfs)	Flow (cfs)	Flow (cfs)				
2-Year; 24-hour	27.21	18.01	15.31				
10-Year; 24-hour	66.40	46.77	39.61				
25-Year; 24-hour	92.61	65.98	56.03				
100-Year; 24-hour	137.71	98.91	83.98				

Peak Runoff Analysis

Peak runoff was compared between the pre- and post-development conditions for each of the three (3) design points. As shown in the tables below and HydroCAD analysis (**Appendix E**), the small increase in impervious cover is mostly absorbed by the overall dense Guinea grass areas in and around the panels, creating a similar ground cover to the existing conditions helping to stabilize the ground and mitigate runoff. The development will generally maintain the existing grades and drainage flow patterns with minimal changes to the current topography. To further reduce the peak rate of runoff and preserve the integrity of the site from future storm event erosion, several series of permanent rock berms will be constructed where naturally occurring drainage flow paths exist on-site.

The watersheds were designed to provide peak runoff rate reductions between the pre- and post-development conditions up to the 100-year design storm for flow rate to comply with the 2022 U.S. Virgin Islands Environmental Protection Handbook (USVI EP Handbook).

Design Point 1 (DP1) has impervious areas from ground screws, access driveway and electrical equipment; while Design Point 2 (DP2) and 3 (DP3) have impervious areas from ground screws only. The site is volcanic HSG D soils, which provide little in the way of stormwater infiltration. Understanding the limited infiltration, the proposed rock berm series uses loose compacted crushed stone to help as a dispersion device while the rest of the disturbed areas of the watershed will feature dense Guinea grass which is intended to capture slow stormwater runoff and prevent erosion.

The tables below provide a summary of the control of the peak rate of runoff between the pre- and post-development conditions.

PEAK RUNOFF DESIGN POINT 1 (RATES)							
Pre-Development Post-Development Difference							
Peak Design Storm	Flow (cfs)	Flow (cfs)	Flow (cfs)				
2-Year; 24-hour	27.24	27.21	-0.03				
10-Year; 24-hour 69.49		66.40	-3.09				
25-Year; 24-hour	97.68	92.61	-5.07				
100-Year; 24-hour	145.86	137.71	-8.15				

PEAK RUNOFF DESIGN POINT 2 (RATES)								
Pre-Development Post-Development Difference								
Peak Design Storm	Flow (cfs)	Flow (cfs)	Flow (cfs)					
2-Year; 24-hour	18.07	18.01	-0.06					
10-Year; 24-hour	48.11	46.77	-1.34					
25-Year; 24-hour	68.38	65.98	-2.40					
100-Year; 24-hour	103.14	98.91	-4.23					

PEAK RUNOFF DESIGN POINT 3 (RATES)							
Pre-Development Post-Development Difference							
Peak Design Storm	Flow (cfs)	Flow (cfs)	Flow (cfs)				
2-Year; 24-hour	15.31	15.31	-0.00				
10-Year; 24-hour	40.55	39.61	-0.94				
25-Year; 24-hour	57.54	56.03	-1.51				
100-Year; 24-hour	86.66	83.98	-2.68				

Conclusion

The project was designed to maintain existing natural soils, topography, and flow patterns. All existing vegetation within the project area will be ground flush with the existing grade with minimal root removal therefore leaving most soils in place and undisturbed. Limited grading is proposed which will allow for natural drainage patterns to be maintained.

The proposed design has minimal impervious surfaces that are typically associated with stormwater runoff. To mitigate impacts from the development, a dense Guinea grass maintained between 6-12-inches in and around the solar field will provide permanent stabilization and slow stormwater runoff. The site will also feature several permanent rock berm series to be installed in the stormwater flow paths to slow runoff and promote infiltration with the Guinea grasses.

The nature of this development does not generate stormwater pollutants typically associated with larger developments. Once constructed, the site will essentially be self-operational with limited vehicle traffic and will not use herbicides, pesticides or cleaning chemicals. Extensive perimeter erosion control measures are proposed and a detailed Stormwater Prevention Pollution Plan (SWPPP) will be implemented to prevent erosion and sediment runoff for the duration of construction until the site is permanently stabilized.

In summary, the project was designed to meet the standards of the 2022 U.S. Virgin Islands Environmental Protection Handbook by providing peak rate of runoff reductions up to the 100-year design storm, while minimizing on-site ground disturbances and limiting impacts to the surrounding properties. Due to the entire site draining into the Caribbean Sea, concerns of adverse flooding are not anticipated, therefore the USVI EP Handbook requirement to reduce the volume of the 1-year design storm is not applicable for this project and is not included in this analysis.

Appendix A – Rainfall Data





NOAA Atlas 14, Volume 3, Version 4 Location name: Southside, US Virgin Islands, VIR* Latitude: 18.3096°, Longitude: -64.8846° Elevation: 203 ft**

* source: ESRI Maps ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M.Yekta, and D. Riley NOAA, National Weather Service, Silver Spring, Maryland

PF tabular | PF graphical | Maps & aerials

PF tabular

PDS	PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹								hes) ¹	
Duration		Average recurrence interval (years)								
Duration	1	2	5	10	25	50	100	200	500	1000
5-min	0.270 (0.246-0.339)	0.377 (0.323-0.438)	0.481 (0.417-0.547)	0.550 (0.475-0.629)	0.635 (0.540-0.734)	0.696 (0.584-0.816)	0.756 (0.628-0.900)	0.814 (0.665-0.980)	0.891 (0.711-1.09)	0.950 (0.743-1.18)
10-min	0.369 (0.337-0.464)	0.515 (0.442-0.599)	0.657 (0.569-0.748)	0.752 (0.649-0.860)	0.868 (0.739-1.00)	0.952 (0.798-1.12)	1.03 (0.858-1.23)	1.11 (0.909-1.34)	1.22 (0.972-1.49)	1.30 (1.02-1.61)
15-min	0.474 (0.432-0.595)	0.661 (0.567-0.768)	0.843 (0.731-0.959)	0.965 (0.833-1.10)	1.11 (0.948-1.29)	1.22 (1.02-1.43)	1.33 (1.10-1.58)	1.43 (1.17-1.72)	1.56 (1.25-1.91)	1.67 (1.30-2.07)
30-min	0.759 (0.692-0.953)	1.06 (0.908-1.23)	1.35 (1.17-1.54)	1.54 (1.33-1.77)	1.78 (1.52-2.06)	1.96 (1.64-2.29)	2.12 (1.76-2.53)	2.29 (1.87-2.75)	2.50 (2.00-3.06)	2.67 (2.09-3.32)
60-min	1.13 (1.03-1.41)	1.57 (1.35-1.82)	2.00 (1.74-2.28)	2.29 (1.98-2.62)	2.64 (2.25-3.06)	2.90 (2.43-3.40)	3.15 (2.62-3.75)	3.39 (2.77-4.08)	3.71 (2.96-4.54)	3.96 (3.10-4.92)
2-hr	1.41 (1.32-1.85)	2.04 (1.73-2.41)	2.70 (2.31-3.13)	3.16 (2.69-3.70)	3.76 (3.13-4.48)	4.21 (3.42-5.12)	4.67 (3.73-5.76)	5.12 (3.99-6.45)	5.75 (4.34-7.44)	6.23 (4.57-8.25)
3-hr	1.74 (1.46-2.07)	2.28 (1.94-2.69)	3.03 (2.59-3.49)	3.54 (3.02-4.11)	4.20 (3.51-4.97)	4.70 (3.84-5.65)	5.21 (4.19-6.38)	5.72 (4.51-7.13)	6.42 (4.91-8.19)	6.97 (5.18-9.08)
6-hr	2.10 (1.73-2.55)	2.78 (2.30-3.37)	3.89 (3.23-4.61)	4.71 (3.88-5.62)	5.82 (4.65-7.14)	6.70 (5.20-8.44)	7.61 (5.74-9.82)	8.57 (6.29-11.2)	9.91 (6.98-13.5)	11.0 (7.48-15.5)
12-hr	2.45 (1.97-3.04)	3.30 (2.66-4.12)	4.82 (3.88-5.88)	6.00 (4.75-7.44)	7.67 (5.86-9.78)	9.02 (6.66-11.8)	10.4 (7.44-14.1)	12.0 (8.26-16.5)	14.1 (9.29-20.2)	15.8 (10.0-23.2)
24-hr	2.82 (2.35-3.40)	3.82 (3.20-4.61)	5.73 (4.79-6.83)	7.30 (6.08-8.68)	9.58 (7.88-11.3)	11.5 (9.34-13.6)	13.5 (10.9-16.0)	15.7 (12.5-18.6)	18.9 (14.8-22.5)	21.5 (16.6-25.6)
2-day	3.61 (3.00-4.35)	4.92 (4.09-5.92)	7.33 (6.10-8.73)	9.24 (7.64-11.0)	11.9 (9.78-14.1)	14.1 (11.4-16.7)	16.4 (13.2-19.4)	18.9 (14.9-22.4)	22.3 (17.4-26.6)	25.0 (19.4-29.9)
3-day	3.77 (3.11-4.58)	5.15 (4.25-6.24)	7.67 (6.34-9.20)	9.65 (7.92-11.5)	12.4 (10.1-14.8)	14.7 (11.8-17.5)	17.1 (13.5-20.4)	19.6 (15.4-23.5)	23.1 (17.9-27.8)	25.9 (19.9-31.2)
4-day	3.92 (3.23-4.80)	5.37 (4.42-6.56)	8.00 (6.58-9.67)	10.1 (8.20-12.1)	12.9 (10.4-15.5)	15.3 (12.2-18.4)	17.7 (13.9-21.4)	20.3 (15.8-24.5)	23.9 (18.4-29.0)	26.8 (20.4-32.6)
7-day	4.47 (3.64-5.54)	6.12 (4.98-7.57)	9.23 (7.49-11.3)	11.7 (9.43-14.2)	15.3 (12.1-18.4)	18.2 (14.2-22.0)	21.3 (16.5-25.8)	24.6 (18.9-29.9)	29.4 (22.2-35.8)	33.2 (24.7-40.7)
10-day	4.92 (4.02-6.07)	6.72 (5.49-8.27)	9.98 (8.12-12.1)	12.5 (10.1-15.1)	16.2 (12.9-19.5)	19.1 (15.1-23.0)	22.2 (17.4-26.8)	25.5 (19.8-30.8)	30.2 (23.0-36.6)	34.0 (25.5-41.4)
20-day	6.52 (5.45-7.77)	8.74 (7.32-10.4)	12.3 (10.3-14.5)	15.0 (12.5-17.6)	18.7 (15.4-21.9)	21.6 (17.7-25.3)	24.6 (20.1-28.9)	27.7 (22.4-32.6)	32.0 (25.5-37.8)	35.4 (27.9-41.9)
30-day	8.14 (6.89-9.51)	10.8 (9.12-12.6)	14.4 (12.2-16.8)	17.1 (14.5-19.8)	20.6 (17.3-23.9)	23.4 (19.5-27.0)	26.1 (21.7-30.3)	28.9 (23.9-33.6)	32.8 (26.8-38.3)	36.1 (29.3-42.2)
45-day	10.3 (8.86-11.8)	13.4 (11.6-15.3)	17.3 (14.9-19.7)	20.1 (17.3-22.9)	23.7 (20.3-27.0)	26.5 (22.6-30.2)	29.2 (24.8-33.4)	32.0 (27.0-36.6)	35.6 (29.8-41.0)	38.5 (32.0-44.4)
60-day	11.4 (9.95-13.0)	14.8 (12.9-16.8)	18.9 (16.5-21.5)	22.0 (19.1-24.8)	25.9 (22.4-29.3)	28.9 (24.9-32.7)	31.9 (27.2-36.1)	34.9 (29.6-39.6)	38.9 (32.7-44.3)	41.9 (35.0-48.0)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top

Appendix B – NRCS Web Soil Survey





MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) С 1:12.000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D **Soil Rating Polygons** Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil **Water Features** line placement. The maps do not show the small areas of A/D contrasting soils that could have been shown at a more detailed Streams and Canals Transportation B/D Rails ---Please rely on the bar scale on each map sheet for map measurements. Interstate Highways C/D Source of Map: Natural Resources Conservation Service **US Routes** Web Soil Survey URL: D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available -Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Soil Rating Lines Background distance and area. A projection that preserves area, such as the Aerial Photography Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Virgin Islands of the United States Survey Area Data: Version 5, Sep 13, 2023 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Not rated or not available Date(s) aerial images were photographed: Jan 1, 2016—Feb 16. 2023 **Soil Rating Points** The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. B/D

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
CbB	Cinnamon Bay loam, 0 to 5 percent slopes, occasionally flooded	В	9.7	1.5%
CgC	Cinnamon Bay gravelly loam, 5 to 12 percent slopes, occasionally flooded	A	6.5	1.0%
SaA	Salt flats, ponded		4.5	0.7%
SBA	Sandy Point and Sugar Beach soils, 0 to 2 percent slopes, frequently flooded	C/D	64.5	10.1%
SoA	Solitude gravelly fine sandy loam, 0 to 2 percent slopes, frequently flooded	A/D	37.2	5.8%
SrD	Southgate-Rock outcrop complex, 12 to 20 percent slopes	D	9.7	1.5%
SrE	Southgate-Rock outcrop complex, 20 to 40 percent slopes	D	110.3	17.3%
SrF	Southgate-Rock outcrop complex, 40 to 60 percent slopes	D	79.4	12.5%
SrG	Southgate-Rock outcrop complex, 60 to 90 percent slopes	D	16.0	2.5%
Us	Ustorthents		38.4	6.0%
Totals for Area of Inter	rest		637.5	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options


Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher


Appendix C – Pre-Development Watershed Map






Appendix D – Post-Development Watershed Map





Appendix E – HydroCAD Analysis





Design Point 1 Design Point 2 Design Point 3









Printed 10/29/2025 Page 2

Area Listing (all nodes)

Area	CN	Description
(sq-ft)	ı	(subcatchment-numbers)
71,750	96	Artifical desert landscape, HSG D (1)
11,295	89	Dirt roads, HSG D (1, 3)
745	98	Impervious area, HSG D (1)
4,425	98	Paved parking, HSG D (3)
1,139,410	79	Woods/grass comb., Good, HSG D (1, 2, 3)
1,227,625	80	TOTAL AREA

Printed 10/29/2025 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(sq-ft)	Group	Numbers
0	HSG A	
0	HSG B	
0	HSG C	
1,227,625	HSG D	1, 2, 3
0	Other	
1,227,625		TOTAL AREA

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 4

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.13% Impervious Runoff Depth>1.81"

Flow Length=910' Tc=20.7 min CN=81 Runoff=27.24 cfs 83,694 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>1.66"

Flow Length=515' Tc=19.1 min CN=79 Runoff=18.07 cfs 52,997 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>1.66"

Flow Length=398' Tc=15.3 min CN=79 Runoff=15.31 cfs 40,124 cf

Reach DP1: Design Point 1 Inflow=27.24 cfs 83,694 cf

Outflow=27.24 cfs 83,694 cf

Reach DP2: Design Point 2 Inflow=18.07 cfs 52,997 cf

Outflow=18.07 cfs 52,997 cf

Reach DP3: Design Point 3 Inflow=15.31 cfs 40,124 cf

Outflow=15.31 cfs 40,124 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 176,815 cf Average Runoff Depth = 1.73" 99.58% Pervious = 1,222,455 sf 0.42% Impervious = 5,170 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.13% Impervious Runoff Depth>4.73"

Flow Length=910' Tc=20.7 min CN=81 Runoff=69.49 cfs 219,084 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>4.51"

Flow Length=515' Tc=19.1 min CN=79 Runoff=48.11 cfs 143,946 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>4.52"

Flow Length=398' Tc=15.3 min CN=79 Runoff=40.55 cfs 108,954 cf

Reach DP1: Design Point 1 Inflow=69.49 cfs 219,084 cf

Outflow=69.49 cfs 219,084 cf

Reach DP2: Design Point 2 Inflow=48.11 cfs 143,946 cf

Outflow=48.11 cfs 143,946 cf

Reach DP3: Design Point 3 Inflow=40.55 cfs 108,954 cf

Outflow=40.55 cfs 108,954 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 471,984 cf Average Runoff Depth = 4.61" 99.58% Pervious = 1,222,455 sf 0.42% Impervious = 5,170 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment 1: Solar Field

Runoff = 69.49 cfs @ 12.13 hrs, Volume= 219,084 cf, Depth> 4.73"

Routed to Reach DP1 : Design Point 1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

	Α	rea (sf)	CN [CN Description				
*		745	98 I	98 Impervious area, HSG D				
		71,750	96 A	Artifical desert landscape, HSG D				
*		9,685	89 [Dirt roads, HSG D				
	4	73,490	79 \	Woods/grass comb., Good, HSG D				
_	5	55,670	81 \	Veighted A	verage			
	5	54,925	ç	9.87% Per	vious Area			
		745	().13% Impe	ervious Area	a		
				-				
	Tc	Length	Slope	Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	15.9	300	0.3067	0.31		Sheet Flow, Woods		
						Woods: Light underbrush n= 0.400 P2= 3.82"		
	4.8	610	0.1771	2.10		Shallow Concentrated Flow, Woods		
						Woodland Kv= 5.0 fps		
	20.7	910	Total	·	·			

Summary for Subcatchment 2: Solar Field

Runoff = 48.11 cfs @ 12.11 hrs, Volume= 143,946 cf, Depth> 4.51"

Routed to Reach DP2 : Design Point 2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

_	Α	rea (sf)	CN D	escription				
	382,660 7			Woods/grass comb., Good, HSG D				
	382,660		1	00.00% Pe	ervious Are	a		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
_	18.0	300	0.2233	0.28	, ,	Sheet Flow, Woods		
	1.1	215	0.4186	3.23		Woods: Light underbrush n= 0.400 P2= 3.82" Shallow Concentrated Flow, Woods Woodland Kv= 5.0 fps		
_	19.1	515	Total					

Pre Dev - Bovoni

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment 3: Solar Field

Runoff = 40.55 cfs @ 12.07 hrs, Volume= 108,954 cf, Depth> 4.52"

Routed to Reach DP3: Design Point 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

_	Α	rea (sf)	CN E	escription		
		4,425	98 F	aved park	ing, HSG D	
*		1,610	89 D)irt roads, l	HSG D	
_	2	83,260	79 V	Voods/gras	ss comb., G	Good, HSG D
289,295 79 Weighted Average				Veighted A	verage	
	2	84,870	9	8.47% Per	vious Area	
		4,425	1	.53% Impe	ervious Area	a
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
_	14.7	300	0.3733	0.34		Sheet Flow, Woods
						Woods: Light underbrush n= 0.400 P2= 3.82"
	0.6	98	0.2857	2.67		Shallow Concentrated Flow, Woods
						Woodland Kv= 5.0 fps
	15.3	398	Total			<u>. </u>

Summary for Reach DP1: Design Point 1

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 555,670 sf, 0.13% Impervious, Inflow Depth > 4.73" for 10-Yr event

Inflow = 69.49 cfs @ 12.13 hrs, Volume= 219,084 cf

Outflow = 69.49 cfs @ 12.13 hrs, Volume= 219,084 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Reach DP2: Design Point 2

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 382,660 sf, 0.00% Impervious, Inflow Depth > 4.51" for 10-Yr event

Inflow = 48.11 cfs @ 12.11 hrs, Volume= 143,946 cf

Outflow = 48.11 cfs @ 12.11 hrs, Volume= 143,946 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 8

Summary for Reach DP3: Design Point 3

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 289,295 sf, 1.53% Impervious, Inflow Depth > 4.52" for 10-Yr event

Inflow = 40.55 cfs @ 12.07 hrs, Volume= 108,954 cf

Outflow = 40.55 cfs @ 12.07 hrs, Volume= 108,954 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type II 24-hr 25-Yr Rainfall=9.58"

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.13% Impervious Runoff Depth>6.77"

Flow Length=910' Tc=20.7 min CN=81 Runoff=97.68 cfs 313,322 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>6.53"

Flow Length=515' Tc=19.1 min CN=79 Runoff=68.38 cfs 208,085 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>6.53"

Flow Length=398' Tc=15.3 min CN=79 Runoff=57.54 cfs 157,487 cf

Reach DP1: Design Point 1 Inflow=97.68 cfs 313,322 cf

Outflow=97.68 cfs 313,322 cf

Reach DP2: Design Point 2 Inflow=68.38 cfs 208,085 cf

Outflow=68.38 cfs 208,085 cf

Reach DP3: Design Point 3 Inflow=57.54 cfs 157,487 cf

Outflow=57.54 cfs 157,487 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 678,893 cf Average Runoff Depth = 6.64" 99.58% Pervious = 1,222,455 sf 0.42% Impervious = 5,170 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 10

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.13% Impervious Runoff Depth>10.32"

Flow Length=910' Tc=20.7 min CN=81 Runoff=145.86 cfs 477,982 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>10.06"

Flow Length=515' Tc=19.1 min CN=79 Runoff=103.14 cfs 320,940 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>10.07"

Flow Length=398' Tc=15.3 min CN=79 Runoff=86.66 cfs 242,841 cf

Reach DP1: Design Point 1 Inflow=145.86 cfs 477,982 cf

Outflow=145.86 cfs 477,982 cf


Reach DP2: Design Point 2 Inflow=103.14 cfs 320,940 cf

Outflow=103.14 cfs 320,940 cf

Reach DP3: Design Point 3 Inflow=86.66 cfs 242,841 cf

Outflow=86.66 cfs 242,841 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 1,041,763 cf Average Runoff Depth = 10.18" 99.58% Pervious = 1,222,455 sf 0.42% Impervious = 5,170 sf











Printed 10/29/2025 Page 2

Area Listing (all nodes)

Area	CN	Description
(sq-ft)		(subcatchment-numbers)
970,475	80	>75% Grass cover, Good, HSG D (1, 2, 3)
71,750	96	Artifical desert landscape, HSG D (1)
41,125	96	Gravel surface, HSG D (1)
4,195	98	Impervious area, HSG D (1)
4,425	98	Paved parking, HSG D (3)
135,655	79	Woods/grass comb., Good, HSG D (1, 2, 3)
1,227,625	81	TOTAL AREA

Prepared by Hoyle, Tanner & Associates
HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Printed 10/29/2025 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(sq-ft)	Group	Numbers
0	HSG A	
0	HSG B	
0	HSG C	
1,227,625	HSG D	1, 2, 3
0	Other	
1,227,625		TOTAL AREA

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Printed 10/29/2025 Page 4

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.75% Impervious Runoff Depth>1.96"

Flow Length=910' Tc=23.9 min CN=83 Runoff=27.13 cfs 90,710 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>1.73"

Flow Length=515' Tc=20.9 min CN=80 Runoff=17.91 cfs 55,267 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>1.74"

Flow Length=398' Tc=16.7 min CN=80 Runoff=15.33 cfs 41,849 cf

Reach DP1: Design Point 1 Inflow=27.21 cfs 89,323 cf

Outflow=27.21 cfs 89,323 cf

Reach DP2: Design Point 2 Inflow=18.01 cfs 54,852 cf

Outflow=18.01 cfs 54,852 cf

Reach DP3: Design Point 3 Inflow=15.31 cfs 40,977 cf

Outflow=15.31 cfs 40,977 cf

Pond 1P: Rock Berm Peak Elev=41.30' Storage=1,272 cf Inflow=27.13 cfs 90,710 cf

Discarded=0.00 cfs 137 cf Primary=27.21 cfs 89,323 cf Outflow=27.21 cfs 89,460 cf

Pond 2P: Rock Berm Peak Elev=93.20' Storage=368 cf Inflow=17.91 cfs 55,267 cf

Discarded=0.00 cfs 38 cf Primary=18.01 cfs 54,852 cf Outflow=18.01 cfs 54,890 cf

Pond 3P: Rock Berm Peak Elev=97.16' Storage=796 cf Inflow=15.33 cfs 41,849 cf

Discarded=0.00 cfs 75 cf Primary=15.31 cfs 40,977 cf Outflow=15.31 cfs 41,051 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 187,826 cf Average Runoff Depth = 1.84" 99.30% Pervious = 1,219,005 sf 0.70% Impervious = 8,620 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.75% Impervious Runoff Depth>4.95"

Flow Length=910' Tc=23.9 min CN=83 Runoff=66.59 cfs 229,122 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>4.62"

Flow Length=515' Tc=20.9 min CN=80 Runoff=46.69 cfs 147,354 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>4.63"

Flow Length=398' Tc=16.7 min CN=80 Runoff=39.73 cfs 111,547 cf

Reach DP1: Design Point 1 Inflow=66.40 cfs 227,696 cf

Outflow=66.40 cfs 227,696 cf

Reach DP2: Design Point 2 Inflow=46.77 cfs 146,928 cf

Outflow=46.77 cfs 146,928 cf

Reach DP3: Design Point 3 Inflow=39.61 cfs 110,641 cf

Outflow=39.61 cfs 110,641 cf

Pond 1P: Rock Berm Peak Elev=41.61' Storage=1,272 cf Inflow=66.59 cfs 229,122 cf

Discarded=0.00 cfs 176 cf Primary=66.40 cfs 227,696 cf Outflow=66.40 cfs 227,872 cf

Pond 2P: Rock Berm Peak Elev=93.47' Storage=368 cf Inflow=46.69 cfs 147,354 cf

Discarded=0.00 cfs 49 cf Primary=46.77 cfs 146,928 cf Outflow=46.77 cfs 146,977 cf

Pond 3P: Rock Berm Peak Elev=97.42' Storage=796 cf Inflow=39.73 cfs 111,547 cf

Discarded=0.00 cfs 98 cf Primary=39.61 cfs 110,641 cf Outflow=39.62 cfs 110,739 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 488,023 cf Average Runoff Depth = 4.77" 99.30% Pervious = 1,219,005 sf 0.70% Impervious = 8,620 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment 1: Solar Field

Runoff = 66.59 cfs @ 12.16 hrs, Volume= 229,122 cf, Depth> 4.95"

Routed to Pond 1P: Rock Berm

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

	Α	rea (sf)	CN E	escription		
*		4,195	98 Ir	mpervious	area, HSG	D
		71,750	96 A	rtifical des	ert landsca	ape, HSG D
		41,125	96 G	Gravel surfa	ace, HSG [)
		27,000			,	Good, HSG D
_	4	11,600	80 >	75% Gras	s cover, Go	ood, HSG D
	5	55,670	83 V	Veighted A	verage	
	5	51,475	9	9.25% Per	vious Area	
		4,195	0	0.75% Impervious Area		
	-		01		0 "	D
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	17.5	300	0.3067	0.29		Sheet Flow, Dense Grass 6"-12"
						n= 0.450 P2= 3.82"
	2.4	405	0.2519	2.76		Shallow Concentrated Flow, Dense Grass 6"-12"
						Kv= 5.5 fps
	4.0	205	0.0293	0.86		Shallow Concentrated Flow, Woods
_						Woodland Kv= 5.0 fps
	23.9	910	Total			

Summary for Subcatchment 2: Solar Field

Runoff = 46.69 cfs @ 12.13 hrs, Volume= 147,354 cf, Depth> 4.62"

Routed to Pond 2P: Rock Berm

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

Area (sf)	CN	Description
41,715	79	Woods/grass comb., Good, HSG D
 340,945	80	>75% Grass cover, Good, HSG D
382,660	80	Weighted Average
382,660		100.00% Pervious Area

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 7

	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
_	19.8	300	0.2233	0.25		Sheet Flow, Dense Grass 6"-12" n= 0.450 P2= 3.82"
	0.9	185	0.4000	3.48		Shallow Concentrated Flow, Dense Grass 6"-12" Kv= 5.5 fps
	0.2	30	0.4000	3.16		Shallow Concentrated Flow, Woods Woodland Kv= 5.0 fps
-	20.9	515	Total			Troculation 111 Clotpo

Summary for Subcatchment 3: Solar Field

Runoff = 39.73 cfs @ 12.09 hrs, Volume= 111,547 cf, Depth> 4.63"

Routed to Pond 3P: Rock Berm

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Yr Rainfall=7.30"

_	Aı	rea (sf)	CN E	Description		
4,425 98 Paved parking, HSG D						
	2	17,930	80 >	75% Gras	s cover, Go	ood, HSG D
_		66,940	79 V	Voods/gras	ss comb., G	Good, HSG D
	2	89,295	80 V	Veighted A	verage	
	2	84,870	g	8.47% Per	vious Area	
		4,425	1	.53% Impe	ervious Area	a
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	16.1	300	0.3733	0.31		Sheet Flow, Dense Grass 6"-12"
						n= 0.450 P2= 3.82"
	0.4	68	0.2353	2.67		Shallow Concentrated Flow, Dense Grass 6"-12"
						Kv= 5.5 fps
	0.2	30	0.4000	3.16		Shallow Concentrated Flow, Woods
_						Woodland Kv= 5.0 fps
	16.7	398	Total			

Summary for Reach DP1: Design Point 1

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 555,670 sf, 0.75% Impervious, Inflow Depth > 4.92" for 10-Yr event

Inflow = 66.40 cfs @ 12.17 hrs, Volume= 227,696 cf

Outflow = 66.40 cfs @ 12.17 hrs, Volume= 227,696 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Printed 10/29/2025 Page 8

Summary for Reach DP2: Design Point 2

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 382,660 sf, 0.00% Impervious, Inflow Depth > 4.61" for 10-Yr event

Inflow = 46.77 cfs @ 12.13 hrs, Volume= 146,928 cf

Outflow = 46.77 cfs @ 12.13 hrs, Volume= 146,928 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Reach DP3: Design Point 3

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 289,295 sf, 1.53% Impervious, Inflow Depth > 4.59" for 10-Yr event

Inflow = 39.61 cfs @ 12.09 hrs, Volume= 110,641 cf

Outflow = 39.61 cfs @ 12.09 hrs, Volume= 110,641 cf, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Pond 1P: Rock Berm

[92] Warning: Device #2 is above defined storage

[92] Warning: Device #3 is above defined storage

[93] Warning: Storage range exceeded by 1.61'

[85] Warning: Oscillations may require smaller dt or Finer Routing (severity=103)

Inflow Area = 555,670 sf, 0.75% Impervious, Inflow Depth > 4.95" for 10-Yr event

Inflow = 66.59 cfs @ 12.16 hrs, Volume= 229,122 cf

Outflow = 66.40 cfs @ 12.17 hrs, Volume= 227,872 cf, Atten= 0%, Lag= 0.2 min

Discarded = 0.00 cfs @ 6.95 hrs, Volume= 176 cf Primary = 66.40 cfs @ 12.17 hrs, Volume= 227,696 cf

Routed to Reach DP1 : Design Point 1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 41.61' @ 12.17 hrs Surf.Area= 1,500 sf Storage= 1,272 cf

Plug-Flow detention time= 4.4 min calculated for 227,113 cf (99% of inflow)

Center-of-Mass det. time= 2.3 min (776.8 - 774.5)

Volume	Invert	Avail.Storage	Storage Description
#1	36.00'	1,272 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			3 180 cf Overall x 40 0% Voids

Elevation	Surf.Area	Inc.Store	Cum.Store
 (feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
36.00	260	0	0
38.00	710	970	970
40 00	1 500	2 210	3 180

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 9

Device	Routing	Invert	Outlet Devices
#1	Discarded	36.00'	0.100 in/hr Exfiltration over Surface area
#2	Primary	40.00'	40.00' long x 5.00' breadth x 4.00' high Rock Fill
	-		Rock Diam.= 6.000", S.D.= 2.000", Voids= 40.0%
#3	Primary	41.00'	40.0' long + 0.3 '/' SideZ x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.00 cfs @ 6.95 hrs HW=40.07' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=65.83 cfs @ 12.17 hrs HW=41.61' (Free Discharge)

-2=Rock Fill (Rockfill Controls 14.83 cfs @ 0.46 fps)

-3=Broad-Crested Rectangular Weir (Weir Controls 51.00 cfs @ 2.10 fps)

Summary for Pond 2P: Rock Berm

[92] Warning: Device #2 is above defined storage

[92] Warning: Device #3 is above defined storage

[93] Warning: Storage range exceeded by 1.47'

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

382,660 sf, 0.00% Impervious, Inflow Depth > 4.62" for 10-Yr event Inflow Area =

Inflow 46.69 cfs @ 12.13 hrs, Volume= 147,354 cf

Outflow 46.77 cfs @ 12.13 hrs, Volume= 146,977 cf, Atten= 0%, Lag= 0.1 min

0.00 cfs @ 7.00 hrs, Volume= Discarded = 49 cf 46.77 cfs @ 12.13 hrs, Volume= 146.928 cf Primary =

Routed to Reach DP2: Design Point 2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 93.47' @ 12.13 hrs Surf.Area= 430 sf Storage= 368 cf

Plug-Flow detention time= 1.9 min calculated for 146,489 cf (99% of inflow)

Center-of-Mass det. time= 0.9 min (779.3 - 778.4)

Volume	Invert	Avail.Sto	rage Sto	rage Des	cription			
#1	88.00'	36			ge Data (Pr	ismatic) Listed below (Recalc)		
			920	o di Overa	III X 4U.U70	Volus		
Elevation	on Si	urf.Area	Inc.Sto	re (Cum.Store			
(fee	et)	(sq-ft)	(cubic-feet)		cubic-feet)			
88.0	00	60		0	0			
90.0	00	215	2	7 5	275			
92.0	00	430		15	920			
Device	Routing	Invert	Outlet D	evices				
#1	Discarded	scarded 88.00'		0.100 in/hr Exfiltration over Surface area				
#2	Primary	rimary 92.00' 40.00' long x 5.00' breadth x 4.00' high Rock Fill			4.00' high Rock Fill			
	_		Rock Dia	am.= 6.00	0". S.D.= 2.	000", Voids= 40.0%		

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 10

#3 Primary 93.00' **40.0' long + 0.3 '/' SideZ x 5.0' breadth Broad-Crested Rectangular Weir**Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00

2.50, 3.00, 3.50, 4.00, 4.50, 5.00, 5.50

2.50 3.00 3.50 4.00 4.50 5.00 5.50

Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65

2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.00 cfs @ 7.00 hrs HW=92.03' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=46.09 cfs @ 12.13 hrs HW=93.47' (Free Discharge)

2=Rock Fill (Rockfill Controls 12.98 cfs @ 0.44 fps)

—3=Broad-Crested Rectangular Weir (Weir Controls 33.11 cfs @ 1.76 fps)

Summary for Pond 3P: Rock Berm

[92] Warning: Device #2 is above defined storage

[92] Warning: Device #3 is above defined storage

[93] Warning: Storage range exceeded by 1.42'

[85] Warning: Oscillations may require smaller dt or Finer Routing (severity=96)

Inflow Area = 289,295 sf, 1.53% Impervious, Inflow Depth > 4.63" for 10-Yr event

Inflow = 39.73 cfs @ 12.09 hrs, Volume= 111,547 cf

Outflow = 39.62 cfs @ 12.09 hrs, Volume= 110,739 cf, Atten= 0%, Lag= 0.0 min

Discarded = 0.00 cfs @ 7.85 hrs, Volume= 98 cf Primary = 39.61 cfs @ 12.09 hrs, Volume= 110,641 cf

Routed to Reach DP3: Design Point 3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 97.42' @ 12.09 hrs Surf.Area= 880 sf Storage= 796 cf

Plug-Flow detention time= 5.3 min calculated for 110,371 cf (99% of inflow)

Center-of-Mass det. time= 2.5 min (777.5 - 775.0)

Volume	Inve	ert Avail.S	Storage	Storage I	Description	
#1	92.0	00'	796 cf		Stage Data (Pri Overall x 40.0%	smatic) Listed below (Recalc) 6 Voids
Elevatio		Surf.Area (sq-ft)		.Store c-feet)	Cum.Store (cubic-feet)	
92.0	00	150		0	0	
94.0	00	480		630	630	
96.0	00	880		1,360	1,990	
Device	Routing	Inve	ert Outle	et Devices	8	
#1	Discarde	4 92 0	no' 0 10	በ in/hr Fx	filtration over S	Surface area

DCVICC	rtouting	IIIVCIL	Odilet Devices
#1	Discarded	92.00'	0.100 in/hr Exfiltration over Surface area
#2	Primary	96.00'	40.00' long x 5.00' breadth x 4.00' high Rock Fill
	-		Rock Diam.= 6.000", S.D.= 2.000", Voids= 40.0%
#3	Primary	97.00'	40.0' long + 0.3 '/' SideZ x 5.0' breadth Broad-Crested Rectangular Weir
	-		Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65

Printed 10/29/2025

<u> Page 11</u>

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.00 cfs @ 7.85 hrs HW=96.13' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=38.93 cfs @ 12.09 hrs HW=97.41' (Free Discharge)

2=Rock Fill (Rockfill Controls 12.24 cfs @ 0.43 fps)

-3=Broad-Crested Rectangular Weir (Weir Controls 26.69 cfs @ 1.61 fps)

Type II 24-hr 25-Yr Rainfall=9.58"

Prepared by Hoyle, Tanner & Associates

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 12

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.75% Impervious Runoff Depth>7.00"

Flow Length=910' Tc=23.9 min CN=83 Runoff=92.66 cfs 324,167 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>6.64"

Flow Length=515' Tc=20.9 min CN=80 Runoff=66.01 cfs 211,881 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>6.65"

Flow Length=398' Tc=16.7 min CN=80 Runoff=56.07 cfs 160,372 cf

Reach DP1: Design Point 1 Inflow=92.61 cfs 322,716 cf

Outflow=92.61 cfs 322,716 cf

Reach DP2: Design Point 2 Inflow=65.98 cfs 211,464 cf

Outflow=65.98 cfs 211,464 cf

Reach DP3: Design Point 3 Inflow=56.03 cfs 159,467 cf

Outflow=56.03 cfs 159,467 cf

Pond 1P: Rock Berm Peak Elev=41.79' Storage=1,272 cf Inflow=92.66 cfs 324,167 cf

Discarded=0.00 cfs 183 cf Primary=92.61 cfs 322,716 cf Outflow=92.61 cfs 322,899 cf

Pond 2P: Rock Berm Peak Elev=93.61' Storage=368 cf Inflow=66.01 cfs 211,881 cf

Discarded=0.00 cfs 53 cf Primary=65.98 cfs 211,464 cf Outflow=65.98 cfs 211,517 cf

Pond 3P: Rock Berm Peak Elev=97.54' Storage=796 cf Inflow=56.07 cfs 160,372 cf

Discarded=0.00 cfs 105 cf Primary=56.03 cfs 159,467 cf Outflow=56.03 cfs 159,573 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 696,420 cf Average Runoff Depth = 6.81" 99.30% Pervious = 1,219,005 sf 0.70% Impervious = 8,620 sf

Printed 10/29/2025

HydroCAD® 10.20-5c s/n 00471 © 2023 HydroCAD Software Solutions LLC

Page 13

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Solar Field Runoff Area=555,670 sf 0.75% Impervious Runoff Depth>10.57"

Flow Length=910' Tc=23.9 min CN=83 Runoff=137.10 cfs 489,372 cf

Subcatchment 2: Solar Field Runoff Area=382,660 sf 0.00% Impervious Runoff Depth>10.19"

Flow Length=515' Tc=20.9 min CN=80 Runoff=99.08 cfs 325,011 cf

Subcatchment 3: Solar Field Runoff Area=289,295 sf 1.53% Impervious Runoff Depth>10.20"

Flow Length=398' Tc=16.7 min CN=80 Runoff=84.02 cfs 245,936 cf

Reach DP1: Design Point 1 Inflow=137.71 cfs 487,854 cf

Outflow=137.71 cfs 487,854 cf

Reach DP2: Design Point 2 Inflow=98.91 cfs 324,616 cf

Outflow=98.91 cfs 324,616 cf

Reach DP3: Design Point 3 Inflow=83.98 cfs 245,027 cf

Outflow=83.98 cfs 245,027 cf

Pond 1P: Rock Berm Peak Elev=42.05' Storage=1,272 cf Inflow=137.10 cfs 489,372 cf

Discarded=0.00 cfs 186 cf Primary=137.71 cfs 487,854 cf Outflow=137.71 cfs 488,040 cf

Pond 2P: Rock Berm Peak Elev=93.83' Storage=368 cf Inflow=99.08 cfs 325,011 cf

Discarded=0.00 cfs 54 cf Primary=98.91 cfs 324,616 cf Outflow=98.92 cfs 324,669 cf

Pond 3P: Rock Berm Peak Elev=97.73' Storage=796 cf Inflow=84.02 cfs 245,936 cf

Discarded=0.00 cfs 109 cf Primary=83.98 cfs 245,027 cf Outflow=83.99 cfs 245,136 cf

Total Runoff Area = 1,227,625 sf Runoff Volume = 1,060,320 cf Average Runoff Depth = 10.36"

99.30% Pervious = 1,219,005 sf 0.70% Impervious = 8,620 sf